



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.


About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>


UC-NRLF



\$B 26 696



EX LIBRIS





RIVER DISCHARGE.

**PREPARED FOR THE USE OF ENGINEERS
AND STUDENTS**

BY

JOHN CLAYTON HOYT

M. Am. Soc. C. E.

*Hydraulic Engineer in charge Division of Surface Waters
United States Geological Survey*

AND

NATHAN CLIFFORD GROVER

M. Am. Soc. C. E.

*Chief Hydraulic Engineer
United States Geological Survey*

THIRD EDITION REVISED AND ENLARGED

FOURTH THOUSAND.

NEW YORK

JOHN WILEY & SONS, INC.

LONDON : CHAPMAN & HALL, LIMITED

1914.

TC 175
H. F.
S. H.

COPYRIGHT, 1907, 1912, 1914.

BY

JOHN C. HOYT AND NATHAN C. GROVER.

TO THE
LIBRARY OF

THE McQUEEN PRESS WASHINGTON, D. C.

PREFACE TO THIRD EDITION.

Developments in the application of water to power, irrigation, and other engineering works during the last ten years have been accompanied by such progress in the development of methods for collecting and using data concerning the flow of streams that the art of river-discharge measurement has attained a recognized position as a branch of hydraulics. The subject is now included in the regular courses of engineering schools and is admittedly essential to the work of the practicing engineer.

The first edition of *River Discharge* correlated the methods of collecting, analyzing, and using stream-flow records as developed at that time; the second edition was revised and expanded to include progress in the art; this new edition has been further expanded to present the latest information on the subject.

In the preparation of the book clearness and conciseness have been sought, and lengthy theoretical and mathematical discussions have been avoided in order to adapt the book to the use of both student and engineer.

J. C. H.
N. C. G.

WASHINGTON, D. C., *August*, 1914.

PREFACE TO FIRST EDITION.

With the rapid increase in the development of the water resources of the United States there has arisen among capitalists and engineers throughout the country a great demand for information in regard to the flow of streams. Although much has been written on the methods of measuring stream flow and the interpretation of the data, such information is widely scattered through periodicals and Government reports, many of which are out of print and therefore not easily accessible for use by either the student or the engineer. The short descriptions of stream gaging in text-books are indefinite in character, stating only general methods and giving but little information in regard to the details of field work or the conditions requisite for reliable records of river discharge.

Experience with the graduates of many of the best engineering schools in the country indicates that these men have generally had but little instruction in hydraulic field work or methods, and are practically helpless in attempting to carry on even the simplest hydrologic investigation. Correspondence with engineers in all sections of the country shows that they are not getting the maximum benefit from the available stream-gaging data, apparently on account of lack of understanding of the records.

In the preparation of this book there has been brought together from all available sources information in regard to the best practice in this work. Much new matter is also presented, especially the descriptions of the conditions necessary for good gaging stations at which measurements of discharge may be made either by weir, current meters, floats, or slope; the routine of the selection, establishment, and maintenance of gaging stations; the details of the field work of discharge measurements, and the office methods of computing the regimen of flow.

The authors hope and believe that the information here presented will be valuable both to the student and the engineer.

Acknowledgments are here made to the United States Geological Survey, the United States Weather Bureau, and the American Society of Civil Engineers, for use of cuts and other material; also to Messrs. J. C. Stevens, R. H. Bolster, G. M. Wood, F. W. Hanna, and E. C. Murphy for assistance and suggestions.

JOHN C. HOYT.

NATHAN C. GROVER.

WASHINGTON, D. C., *May*, 1907.



CONTENTS.

| | PAGE. |
|--|-------|
| CHAPTER I.—Introduction | 1 |
| Historical sketch | 1 |
| Scope of discussion | 2 |
| Outline of methods | 3 |
| CHAPTER II.—Instruments and equipment | 5 |
| Instruments for determining velocity | 5 |
| Floats | 5 |
| Surface floats | 5 |
| Subsurface floats | 5 |
| Tube or rod floats | 6 |
| Current meters | 6 |
| General features of current meters | 8 |
| Description of the small Price current meter and equipment | 9 |
| The head | 9 |
| The tail | 11 |
| The hanger and weights | 12 |
| The recording or indicating device | 12 |
| The suspending device | 13 |
| Care of the current meter | 16 |
| Rating the current meter | 20 |
| Sounding appliances | 22 |
| Gages | 23 |
| Non-recording gages | 24 |
| Direct gages | 24 |
| Vertical staff gages | 24 |
| Inclined staff gages | 25 |
| Indirect gages | 25 |
| Hook gages | 25 |
| Weight gages | 26 |
| Float gages | 28 |
| Establishment and maintenance of non-recording gages | 28 |
| Installation of gage | 28 |
| Checking gage datum | 28 |
| Stilling box | 30 |
| Recording gages | 30 |
| Continuous record gages | 31 |
| Intermittent record gages | 33 |
| Installation of recording gages | 35 |
| Structures for making discharge measurements | 36 |
| Structure from which measurements are made | 36 |
| Bridges | 37 |

| | |
|--|--------------|
| CHAPTER II.—Structure from which measurements are made—Continued. | PAGE. |
| Cables | 37 |
| The cable | 37 |
| Supports | 38 |
| Anchorage | 39 |
| Turnbuckle | 39 |
| Car | 39 |
| Boats | 41 |
| Stay line cables | 42 |
| Lines for indicating measuring points | 42 |
| Artificial controls | 42 |
| Instruments for determining climatological data | 43 |
| CHAPTER III.—Velocity-area stations | 44 |
| Selection of site | 44 |
| Requisite conditions | 44 |
| Conditions pertaining to measurements of flow and stage | 44 |
| Conditions pertaining to computation of flow | 45 |
| Conditions pertaining to cost of records | 46 |
| Reconnaissance | 46 |
| Establishment and maintenance of stations | 48 |
| Gages | 48 |
| Structures for making measurements | 48 |
| Controls | 49 |
| Description of station | 49 |
| Measurement of discharge | 49 |
| Area of cross-section | 50 |
| Soundings | 50 |
| Standard cross-sections | 51 |
| Velocity | 51 |
| Laws governing velocity | 52 |
| Vertical velocity-curves | 53 |
| Distribution of velocity in the vertical | 54 |
| Methods of determining mean velocity in a vertical | 55 |
| Vertical velocity-curve method | 55 |
| Six-tenth-depth method | 59 |
| Surface method | 60 |
| Two-point method | 60 |
| Three-point method | 61 |
| Integration method | 61 |
| Current meter measurements | 61 |
| Procedure | 61 |
| Computations | 64 |
| Low-water and wading measurements | 65 |
| High-water measurements | 68 |
| Measurements of ice-covered streams | 69 |
| Measurements in artificial channels | 76 |
| Float measurements | 76 |
| Slope measurements | 77 |
| Observations of stage | 80 |

CONTENTS.

IX

| | PAGE. |
|---|-------|
| CHAPTER IV.—Weir stations | 82 |
| Sharp-crested weirs | 82 |
| Broad-crested weirs | 84 |
| Weir formulas | 86 |
| Fundamental formulas | 86 |
| Rectangular weirs | 87 |
| Trapezoidal weirs | 88 |
| Broad-crested weirs | 89 |
| Computations | 89 |
| CHAPTER V.—Discussion and use of data | 91 |
| Computations of daily flow | 91 |
| Gaging stations with permanent control | 91 |
| Area curve | 92 |
| Mean velocity curve | 95 |
| Station rating curve | 97 |
| Ordinary cross-section paper with discharge and gage height as coordinates | 97 |
| Ordinary cross-section paper with discharge and $A\sqrt{d}$ as coordinates | 101 |
| Logarithmic cross-section paper | 103 |
| Rating or discharge table | 104 |
| Application of rating table to gage heights | 104 |
| Gaging stations with changeable beds | 109 |
| Periodically changing beds | 109 |
| Constantly changing beds | 109 |
| Stout method | 109 |
| Bolster method | 110 |
| Ice-covered streams | 113 |
| First method | 114 |
| Second method | 114 |
| Third method | 115 |
| Eye method | 115 |
| Graphic method | 116 |
| Application of graphic method | 118 |
| Computation of other values of discharge and runoff | 120 |
| Units of discharge | 121 |
| The second-foot | 121 |
| Gallons per minute | 121 |
| Miner's inch | 121 |
| Second-feet per square mile | 121 |
| Units of runoff | 121 |
| Runoff in inches | 121 |
| Acre-feet | 121 |
| Accuracy of stream-gaging data | 122 |
| Determination of duration of flow and horsepower | 122 |
| Suggestions for estimating discharge | 125 |
| Hydrographs | 125 |
| Measurement of drainage areas from maps | 125 |

| | |
|---|-------|
| CHAPTER V.—Discussion and use of data—Continued. | PAGE. |
| Logarithmic plotting | 129 |
| Where stream-gaging data can be found | 137 |
| Reports of the United States Geological Survey | 138 |
| Reports of the United States Census | 138 |
| Reports of the United States Weather Bureau | 138 |
| Reports of the Chief Engineer, United States Army | 139 |
| Reports of State officials | 139 |
| Reports of special commissions | 139 |
| Reports of city officials | 139 |
| How to obtain Government publications | 139 |
| CHAPTER VI.—Conditions affecting stream flow | 141 |
| Precipitation | 141 |
| Evaporation | 150 |
| Temperature | 152 |
| Geology | 153 |
| Topography | 154 |
| Vegetation | 155 |
| Artificial control | 156 |
| Tables | 157 |
| Index | 179 |

ILLUSTRATIONS.

| | PAGE. |
|---|-------|
| PLATE I. A, Various forms of the Price meter; B, Types of meters experimented with by the United States Geological Survey | 6 |
| II. A, United States Geological Survey current-meter rating station, Chevy Chase, Md.; B, Typical gaging station for bridge measurement | 22 |
| III. Recording gages. A, Stevens; B, Gurley; C, Friez | 30 |
| IV. A, Box shelter for recording gage; B, Cable tower and car | 34 |
| V. A, Typical cable station with automatic gage; B, Typical gaging station for wading measurement | 26 |
| VI. A, Natural control section; B, Artificial control section | 42 |
| VII. Diagram for the Kutter formula | 80 |
| VIII. A, Precipitation and evaporation station, Madison, Wis.; B, Snow observation station, White Mountains, N. H. | 142 |
| IX. Map of United States showing mean annual precipitation | 144 |
| X. Map of United States showing mean annual run-off | 150 |
| FIG. 1. Subsurface float | 6 |
| 2. Price current-meter and attachments | 10 |
| 3. Arrangement of circuit in single wire suspension | 16 |
| 4. Testing meter circuit | 19 |
| 5. Testing meter circuit | 19 |
| 6. Testing meter circuit | 19 |
| 7. Rating curve for small Price meter | 21 |
| 8. Typical current meter rating curves | 23 |
| 9. Simple form of hook gage | 26 |
| 10. United States Geological Survey weight gage | 27 |
| 11. Typical continuous-record gage sheet | 32 |
| 12. Typical intermittent-record gage sheet | 34 |
| 13. Details of hangers for cable car | 40 |
| 14. Distribution of velocity in open channel, Zumbro River at Zumbro Falls, Minn. | 52 |
| 15. Groups of vertical velocity-curves, Chenango River at Binghamton, N. Y. | 53 |
| 16. Typical vertical velocity-curve | 58 |
| 17. Cross-section of stream to illustrate discharge measurement computation | 65 |
| 18. Distribution of velocity under ice cover, Cannon River at Welch, Minn. | 72 |
| 19. Diagram showing factors used in making discharge measurements under ice and form for notes | 75 |
| 20. Cippoletti weir with water register in place | 83 |
| 21. Typical area curves illustrating their form | 93 |
| 22. Typical area curves illustrating their construction | 94 |
| 23. Typical rating curve showing low water extension | 96 |

| | |
|--|-----|
| 24. Discharge, mean velocity, and area curves, Potomac River at Point of Rocks, Md. | 98 |
| 25. Discharge, mean velocity, and area curves, Ohio River at Wheeling, W. Va. | 100 |
| 26. Rating curve showing discharge as a function of $A\sqrt{d}$ | 102 |
| 27. Typical curves illustrating the Stout and the Bolster methods of computing the daily flow | 111 |
| 28. Gage height, backwater temperature and precipitation curves. Rainy River, International Falls, Minn. | 117 |
| 29. Computation sheet, winter records | 118 |
| 30. Hydrograph and curve of duration of flow for 1904, Potomac River at Point of Rocks, Md. | 123 |
| 31. Logarithmic plotting | 129 |
| 32. Logarithmic plotting | 130 |
| 33. Logarithmic plotting | 133 |
| 34. Logarithmic plotting | 134 |
| 35. Logarithmic plotting | 135 |
| 36. Logarithmic plotting | 136 |
| 37. Rain gage and support | 142 |
| 38. Types of weirs referred to in Tables 5, 6, and 7 | 170 |

RIVER DISCHARGE.

By JOHN C. HOYT and NATHAN C. GROVER

CHAPTER I.

INTRODUCTION.

HISTORICAL SKETCH.

Practical acquaintance with and useful application of the general laws of flowing water date from the first century. In A. D. 98 Rome was supplied with water by nine aqueducts having an aggregate length of 250 miles and discharging 27,000,000 cubic feet a day. Yet hydraulics was not regarded as a science until about the fourteenth century, and there was little advancement until the seventeenth century, when, owing to the influence of Galileo, more rapid progress was made. The principal investigations during the seventeenth and the first half of the eighteenth century were made by Castelli (1628), Torricelli (1643), Guglielmini (1700), Pitot (1730), and Bernouilli (1738), and the work done was mainly theoretical.

Active experimental hydraulic investigations were begun by Professor Michelotti in 1764, and from this time the modern school of hydraulics dates. Writings and investigations made prior to 1764 are now of comparatively little importance to the practicing engineer.^a

In 1775 M. Chezy, the celebrated French engineer, developed the formula now known by his name, $V = c_1 \sqrt{Rs}$, in which V = velocity and c = a coefficient combining the effects of roughness of the bed and all other conditions affecting velocity except the slope (s) and hydraulic radius (R), which equals the area of the cross-section of water divided by the wetted perimeter. This was the first algebraic expression of the law of moving water and has served as the basis of all subsequent slope formulas.

^aA detailed review of early hydraulic studies is given in "Physics and Hydraulics of the Mississippi," by Humphreys and Abbot.

In the United States attention was first given to the flow of water in open channels between 1840 and 1850, in work on the Mississippi River and its tributaries. In 1850 Humphreys and Abbot started their extensive investigations on that river, and in about the same year Charles Ellet used gage heights and a rating curve based on discharge measurements to determine the daily discharge of Ohio River at Wheeling.^a In 1855 Francis published the results of his investigations made at Lowell, Mass., in which he developed his formula for flow over weirs. In 1870 Ellis, in his work on the Connecticut River, added much valuable data. It was not until 1888, when the United States Geological Survey began to collect data in regard to the water supply of the country at large, that the general applicability of hydraulic laws was investigated and methods were developed for determining the regimen or the distribution of flow.

In starting the hydrographic work of the Survey, Major J. W. Powell, then Director, stated:^b

It will be necessary to gage a certain number of representative streams at all seasons of the year, so as to ascertain their total discharge and its seasonal distribution, and also to gage a greater number of streams at certain seasons determined to be critical.

Starting with this object, the Survey developed methods for universal stream gaging and collected data in regard to the flow of streams in all sections of the United States, which are now extensively used by engineers in enterprises involving the use of water. In all this work the Survey has contended that, inasmuch as the flow of a stream is constantly changing, data of reasonable accuracy showing the distribution of flow over several consecutive years are of more importance than very accurate measurements covering short periods of time.

SCOPE OF DISCUSSION.

The hydraulic engineer is interested in water from the time it reaches the earth in the form of rain or snow until it returns again to the atmosphere in the form of an invisible vapor. Of the water which falls upon the earth, a portion immediately returns to the atmosphere; a portion soaks into the earth, reappearing in vegetation or as surface water, or remaining below in small amount as permanent ground water; and another portion stays for a time on the surface of the earth, in streams, ponds, lakes, or oceans. A knowledge of the phenomena that pertain to these changes in conditions and of the physical and chemical prop-

^a The Mississippi and Ohio rivers, Lippencott, Grambo & Co., 1853.

^b Tenth Ann. Report, U. S. Geol. Survey, 1890, p. 8.

erties of the water itself constitutes the science of hydrology. Every feature of this great science is of direct value in the economic development of the country, but probably none is of greater importance than a knowledge of the discharge of surface streams and of the conditions that affect its magnitude and variations—knowledge that is prerequisite for preliminary as well as final plans for the construction and successful operation of works utilizing the water in surface streams. Among the hydrologic data necessary either for the design or operation of such works records of daily discharge are the most important. Isolated observations of stage or discharge are of little value unless made at stages that are known to be extreme, and even then the record of the duration is equal in importance to that of the magnitude of the flow. This discussion of surface flow is arranged under the following heads:

Instruments and equipment.

Velocity-area stations.

Weir stations.

Discussion and use of data.

Conditions affecting stream flow.

OUTLINE OF METHODS.

The discharge of a stream is the quantity of water flowing past a given section in a unit of time and is expressed in various units, among which the second-foot is the most common. This term is an abbreviation for cubic foot per second, which is equivalent to the quantity of water flowing in a stream 1 foot wide, 1 foot deep, at a velocity of 1 foot per second. The determination of the discharge is termed "discharge measurement." The discharge may be obtained as the product of two factors—(1) the area of cross-section, which depends on the shape and dimensions of the bed and banks and on the stage; (2) the velocity, which depends on the surface slope, the roughness of the bed and banks, the hydraulic radius, and the conditions along the channel of the stream. In general these factors are controlled by the stage. Therefore the discharge may be considered as a function of the stage.

By means of this general law it is possible, from discharge measurements covering the range of stage, to construct a rating curve and table from which, the main daily stage of the stream being known, the daily discharge can be taken. Points at which discharge measurements are made and records of the daily fluctuations of stage are kept for determining the daily flow are termed "gaging stations." These stations may be grouped in two classes, one comprising those where measure-

ments are made by the velocity-area method, which consists in measuring the velocity of the current and the area of the cross-section; the other comprising those where measurements are made by the weir method, in which the discharge is obtained by measuring the head on a weir and using a weir formula.

The selection of a gaging station, the equipment, and the method to be used in determining the discharge depend on many factors and are accomplished in various ways. Among the principal factors are the use for which the records are to be collected, the funds available, the period of time over which the observations are to be extended, and the conditions of the stream to be measured, as explained in the following pages.

CHAPTER II.

INSTRUMENTS AND EQUIPMENT.

The establishment and maintenance of gaging stations for obtaining records of discharge of rivers and other hydrologic data require the use of certain instruments and equipment. These may consist of:

1. Instruments for determining the velocity and other factors of the discharge measurement.
2. Gages and bench marks for determining stage relative to a fixed datum.
3. Structures from which discharge measurements are made and the appurtenances thereto.
4. Structures to produce artificial control and regulate the relation between stage and discharge.
5. Instruments for determining climatological data.

INSTRUMENTS FOR DETERMINING VELOCITY.

Two principal types of instruments are used for measuring the velocity of flowing water—floats, which measure the velocity directly, and current meters, by which the velocity is obtained indirectly from observations of the number of revolutions of the wheel. Another instrument sometimes used for measuring velocity is the Pitot tube, but it is not practicable to use this tube for the work discussed in this book.

FLOATS.

Floats are utilized for the direct measurement of the velocity of streams. Those in common use are surface, subsurface, and tube or rod floats.

Surface floats.—A corked bottle with a flag in the top and a weight in the bottom makes a very satisfactory surface float, as it is but little affected by the wind. In flood measurements good results can be obtained by observing the velocity of débris or of floating cakes of ice. In all surface-float measurements coefficients must be used to reduce observed velocities to the mean velocity.

Subsurface floats.—The subsurface float (Fig. 1) is designed to measure velocities below the surface and may be made to float at any depth. By

arranging the submerged float at the depth of mean velocity it may be utilized in observing mean velocity directly. Allowance must be made, however, for the accelerating effect of the attached line and surface float.




FIG. 1.—Subsurface Float.

Tube or rod floats.—The tube or rod float is designed also to measure directly the mean velocity in a vertical. It is generally a cylinder of tin, about $2\frac{1}{2}$ inches in diameter, weighted at its lower end and plugged with wood or cork at its top. Small extra weight to make it float at the exact depth desired may readily be added by admitting water or by putting in shot. The tube should be graduated, and alternate feet painted black and red in order that the depth of flotation may be readily observed.

A number of tubes of different lengths are necessary for measuring the velocity at different depths in an ordinary cross-section. A float of this type is consequently best adapted for use in artificial channels, in which the depth is nearly uniform, as natural channels are generally too rough and too variable to permit its satisfactory use.

Although designed to measure directly the mean velocity in a vertical, the tube can not be made to float in contact with the bed of the stream, and consequently it does not receive the effect of the slowest moving water. The rougher the bed the greater the error in this respect. A factor less than unity is therefore necessary to reduce the observed velocity to the mean.

CURRENT METERS.^a


A current meter for measuring the velocity of flowing water comprises two essential parts: (a) a wheel arranged so that when suspended in flowing water the pressure of the water against it causes it to revolve; (b) a device for recording or indicating the number of revolutions of this wheel. The relation between the velocity of the moving water and the revolutions of the wheel is determined by rating each meter.

The earliest type of meter was the float wheel, which was used by Borda


^a Transactions American Society of Civil Engineers, Paper No. 1133, Vol. LXVI, page 70 (1910).



A. VARIOUS FORMS OF THE PRICE METER.



B. TYPES OF METERS EXPERIMENTED WITH BY UNITED STATES GEOLOGICAL SURVEY.



and Dupuit in the latter part of the eighteenth century, and was practicable only for measuring velocities at the surface. About 1790, Woltmann modified this wheel so that it could be used beneath the surface, the number of revolutions being recorded by a gear mechanism, which was started and stopped at the beginning and end of a run by a catch operated by a cord. It was necessary, however, to lift the meter out of the water in order to read it. LaPointe arranged the recording apparatus above the surface by connecting the axle with a vertical rod and beveled gear. Baumgarten, Saxton, Brewster, Laignel, and others made various modifications of the instrument. Prior to the invention of an electric device for recording or indicating the number of revolutions of the wheel, the meter was of limited use because of its lack of adaptability to varying conditions and because of difficulties with the operation of the recording mechanism.

In America current meters were earliest used in connection with the investigations of the Mississippi, started in 1850 by Humphreys and Abbot,^a in which the ship's log and the Saxton meter were used to a small extent and with little success.

About 1860, the late D. Farrand Henry, M. Am. Soc. C. E., Assistant, United States Lake Survey, invented for use with the current meter an electrical recorder,^b which eliminated the serious difficulties peculiar to the mechanical recorder, and made feasible the further development of the meter.

The first extended and successful series of measurements with the current meter in the United States was made on Connecticut River by the late T. G. Ellis, M. Am. Soc. C. E., in connection with studies begun in 1871.^c General Ellis started his work with the Woltmann meter, equipped with an electrical recording device, but later used an electrical recording meter devised by himself. The results obtained by these measurements have had an important effect on the development of stream-gaging instruments.

The earliest American patents for current meters were taken out in 1851. There are now on file in the Patent Office, classified under ship's logs, more than fifty patents for devices for measuring the velocity of water. Many unpatented devices have also been constructed. The only meters which have had much general use, however, are those devised by Price, Haskell, Fteley, and Ellis or modifications of these types (Pl. I, B, Nos. 3-2-4 and 1).

Each of the various meters has first been developed to meet the require-

^a Report upon the Physics and Hydraulics of the Mississippi River, 1861.

^b Journal of the Franklin Institute, Vol. XCII, 1871.

^c Report, Chief of Engineers, U. S. Army, 1878, Part I.

ments of some special condition, and, until recently, the use of all has been confined to special hydrologic investigations in connection with some public work, municipal, State, or Federal. The present widespread interest in the value and use of water has created such a demand for records of the discharge of streams that the current meter is now in general use, and has become an essential part of the equipment of every engineer engaged in hydraulic work.

In 1888 the United States Geological Survey began the gaging of streams of all sizes and in all sections of the country. These streams presented an infinite variety in combination of range in depth, width, and velocity. No adequate meter or methods had been developed for work of this varied nature. Furthermore, elaborate equipment and methods were out of question on account of the limited funds. It was necessary to devise or adapt a current meter which could be readily carried in the field and operated by one man, either from a bridge, boat, cable and car, or by wading.

After experimenting with various types (Pl. I, B) the engineers of the Survey developed a meter combining certain essential features of the Price acoustic and the large Price electric meter* (Pl. I, A, Nos. 1 and 2.) This is known as the small Price meter, and has since been in general use in the Survey work. Modifications in its construction have been made from time to time until now it represents the ideas of many engineers, resulting from the experience of more than twenty years in stream gaging.

The methods developed by the Survey engineers are also believed to represent the best practice in this line of work. The Survey's data are now used extensively in all hydraulic development in the United States. Its methods have been accepted as standard in this country and have been adopted in similar work by many engineers in all parts of the world.

GENERAL FEATURES OF CURRENT METERS.

Current meters may be divided into two general classes: direct action and differential action, the division depending on whether the water, in revolving the wheel, does or does not exert a force which tends to retard the motion of the wheel.

The wheel of the direct-action meter consists of flat or warped-surface vanes set on a horizontal axis, which are caused to revolve by the direct pressure of the water against them. Each vane receives the water pressure in the same way as all of the others. The principal types of direct-action meters are the Haskell and Fteley (Pl. I, B, Nos. 2 and 4).

The wheel of the differential meter consists of a vertical axis carrying a series of cups which are revolved by the water pressure on the concave

* Manufactured and sold by W. & L. E. Gurley, Troy, N. Y.

side of the cups and are retarded by the lesser pressure on the convex side. The principal types of differential meters are the Price and the Ellis (Pl. I, B, Nos. 3 and 1).

The essentials for a good current meter are: (a) simplicity and lightness of construction, with no delicate parts which easily get out of order; (b) simplicity in operation, including its preparation for use under any conditions, and its dismantling, cleaning, and boxing after use; (c) a small area of resistance to the action of the water; (d) a simple and effective device for indicating the number of revolutions of the wheel; and (e) adaptability for use under all conditions.

The small Price meter is the only one fully described herein. The discussion on the care and use of current meters is, however, generally applicable to any type.

DESCRIPTION OF THE SMALL PRICE CURRENT METER AND EQUIPMENT.


The small Price current meter and equipment consists of five principal parts: (1) the head; (2) the tail; (3) the hanger and weights; (4) the recording or indicating device; and (5) the suspending device. In the following descriptions the numbers in parentheses refer to figure 2.

The Head.—The head consists of a \cap -shaped yoke (1) carrying a wheel made of six conical cups (2), brazed to a horizontal frame (3). This wheel, referred to as the cups, turns in a counter clockwise direction on a vertical axis known as the cup shaft, which rests and revolves on a cone point bearing at the lower end and engages the recording mechanism at the upper end.

The cup shaft consists of two parts (4, 5), screwed together from either side of the cup frame, thus fastening the cups rigidly to the cup shaft. At the lower part of the cup shaft there is a cone bearing which receives the cone point (6) on which the cups revolve.

The cone point is screwed through a metal bushing (7) known as the cone plug, and is firmly held by a lock-nut (8). The cone plug fits into the lower arm of the yoke by a sliding connection, and is clamped in position by a set-screw. By means of a sleeve-nut (9) on the lower part of the shaft, the cups can be lifted from the cone point when the meter is not in use. This sleeve-nut has a left-handed thread, so that it will not tighten when the cups revolve.

The upper part of the cup shaft is fitted with either a worm gear or an eccentric which passes into a cylindrical chamber (10), known as the contact chamber, as it contains the mechanism for making the contact which indicates the revolutions of the cups. The construction and arrangement of both the contact chamber and the mechanism contained in it



depend on whether the indicating device is penta-count electric, single-count electric or acoustic.

When the penta-count electric indicating device is used, the contact chamber (10) which is closed by a screw cap (11) provided with a leather gasket for keeping out the water, fits by a sliding connection into the upper end of the yoke, and is clamped into position by a set-screw. In the contact chamber there is fitted a cylindrical plug (12) which is held in position by a screw and carries a gear-wheel (13) which engages the worm gear on the upper end of the cup shaft, the gearing being arranged so that the wheel makes one revolution for every twenty revolutions of the cups. On the side of the wheel there are four platinum pins, equally spaced and set so that they will strike the contact spring (14) at each fifth revolution of the cups, thus closing the electric circuit to the indicating device, as explained later. These contact parts are known as the contact wheel, the contact pins, and the contact spring. The contact spring is of platinum, and is carried by the contact plug (15) which is screwed into the contact chamber through a hard-rubber bushing (16), thus insulating the contact spring from the meter when it is not touching one of the pins on the contact wheel. In the end of the contact plug there is a hole and a set-screw for connecting with a wire from the indicating device.

When the single-count electric indicating device is used, the contact chamber (10a) and appurtenances are the same as described for the penta-count contact chamber with the exception that the gear wheel (13) is omitted and the worm gear on the upper part of the shaft (4) is replaced by the eccentric (4a) which strikes the contact spring (14a) at each revolution, thus closing the electric circuit to the indicating device. The penta- and single-count contact chambers are interchangeable.

When the acoustic indicating device is used, the contact chamber (10b) is closed with a cap (11b) fitted with a metal drum (49), and, in place of the platinum contact spring (14) and plug (16), there is a small hammer (50) which is caused by the pins on the side of the gear-wheel (13a) to strike the drum at each fifth revolution of the cups. In order to keep the water from deadening the sound by rising into the contact chamber (10b), it is raised about four inches above the yoke (1a) by inserting the tube (59) and lengthening the upper part of the shaft (4a).

When the electric indicating device is used, the yoke is equipped with a stem which contains a slot and a screw hole (22) for attaching the meter hanger (23), and a socket into which the tail of the meter (17) is fastened. When the acoustic indicating device is used, this stem is omitted and the meter is supported on a rod (51) attached to the contact chamber.

The Tail.—The tail is used when the meter is suspended by a cable, or

on a sliding hanger rod. It provides for balancing the head, and also keeps the axis of the meter parallel to the direction of the current. It consists of a stem (17) which fits by a sliding connection into a socket in the stem of the yoke where it is clamped by a set-screw. On this stem there are two vanes (18 and 19) set at right angles. One of the vanes is rigidly attached to the stem; the other fits into it by grooves, so that it can readily be pulled out when the key (20) which holds it in place is turned. On one of the vanes there is a slot carrying a weight (21) which can be so adjusted as to balance the meter.

The Hanger and Weights.—When suspended by a cable, the meter is hung by a screw-bolt (22) on a steel stem (23) which passes through a slot in the stem of the yoke. The slot in the stem of the yoke is wide enough to allow the meter to swing freely in a vertical plane, and the bolt passes through the frame a little above the center of gravity of the meter, so that the latter will readily adjust itself to a horizontal position. In the upper end of the hanger there is a hole for attaching the suspending cable, and at intervals along the stem there are other holes by which the meter and lead weights may be hung. The weights (24) are of torpedo shape—this design offering the least resistance to the current—and are made in two sizes, weighing, respectively, 10 and 15 pounds. They are attached to the stem by a screw bolt. The manner of arrangement of the weights and meter on the stem depends on the conditions under which the measurements are to be made.

When the meter is used on a rod, the hanger, weights, and usually the tail are dispensed with.

The set-screws for clamping the various sliding connections are all of the same size and are of standard make. Beveled grooves are provided in each of these connections so that when the set-screws engage them the parts are drawn into place.

All parts of the meter are standard, and can readily be replaced in the field.

The Recording or Indicating Device.—A recording or indicating device is necessary for determining the number of revolutions of the meter wheel, and the successful use of the meter depends largely on this part of the apparatus. Various devices, operated either on the mechanical, electric, or acoustic principle, have been used for this purpose. These include the telegraph ticker, automatic recorder, electric buzzer, telephone receiver, drums, etc. Of these, however, the telephone attachment and the acoustic indicator have been found to be most satisfactory in general practice.

The telephone attachment consists of a telephone receiver (25) and small battery (26) placed in a partial circuit which terminates in a con-

necting plug (27) by means of which the apparatus can be readily connected in circuit with the meter. The magnets of the telephone receiver are wound for 10-ohm resistance so as to secure a loud click.

Either a dry-cell or a wet-cell battery may be used. The most satisfactory dry cell (26) which has been tested is the No. 409, "Ever Ready" cell, which is 1 inch in diameter and 3 inches long. This cell is equipped with two screw connecting posts (28), both at the same end.

The wet cell in common use consists of an outer casing of hard rubber (29), about $1\frac{1}{2}$ inches square, containing a carbon compartment (30) into which a zinc pole (31) having a rubber stopper (32) is inserted. The current is generated by means of a solution of bisulphate of mercury and water. Contact is made with the cell through a platinum plug (33) extending into the carbon at the bottom and through the screw (34) in the zinc pole which extends through the rubber stopper.

The cell is encased in a leather box (35), and connection is made with it through two screw connecting posts (36), each of which terminates in a separate spring plate (37) against which the poles of the battery bear.

In use, the telephone receiver is pinned to the shoulder (Pl. II, B) and the battery cell is placed in the side coat pocket. The connecting plug (27) will then hang a little below the shoulder and is easily accessible for attaching and detaching the meter.

In the acoustic indicator, the striking of the hammer (50) on the drum (49) in the contact chamber (10b) indicates each fifth or tenth revolution of the meter, as already explained. The sound is transmitted through the rods (51) and a rubber tube to the ear of the operator. The rubber tube and ear-piece are not necessary unless there is considerable noise.

Automatic recorders have been used to some extent, but for general work have not been found to be satisfactory, because they are likely to get out of order. They frequently require an assistant to operate them and make the outfit more cumbersome. Furthermore, a sounding device which requires the operator to count the revolutions of the meter is always safer and more satisfactory than either a mechanical or electric self-counting device or recorder, because the operator will at once detect any irregularities caused by trouble with the meter, battery, electric circuit, or other part of the equipment. A stop-watch is essential to the proper observation of time.

The Suspending Device.—The suspending device, which consists of a rod or of some form of cable, must make provision for lowering the meter and weight into the water and also for completing an electric circuit between the contact chamber of the meter and the recording device.

The rod in common use in connection with the electric recorder consists of a $\frac{1}{2}$ -inch tube (55) graduated to feet and tenths. For convenience in carrying, it is made in 1.0 or 1.5-foot sections fitted with screw threads.

Two methods of hanging the meter on the rod are in use. By the first the head and tail of the meter are attached to a sliding hanger (54), which can be moved up and down the rod or clamped in any position. On the bottom of the rod there is a flat foot (53) which keeps it from sinking into the bed of the stream, and at the top there is a plug (56) for connecting one of the wires from the recording device. The circuit between the meter wheel and the recording device is made by attaching one of the wires from the recording device to the plug in the top of the rod. The other wire follows down the rod and is attached to the contact plug of the meter. In the second method the rod (58) is connected by the screw socket (57) in the yoke.

The rods (51) for use with the acoustic indicator are of $\frac{1}{4}$ -inch tubing graduated to feet and tenths, and, for convenience in carrying, are made in 1.0 or 1.5-foot sections which screw together. The bottom rod connects with the contact chamber (49) by a screw, and is cut so that the distance from the center of the cups to the end of the rod is just 1.0 foot. On the upper end of the top rod there is a flat plate (52), in the center of which there is a hole through which the sound from the drum can be heard. The soundings are made with this end of the rod, and the plate keeps the end from sinking into the bed of the stream.

The best form of cable in use is a combination of No. 16, "old code, double-insulated, show-window cord" (38) and No. 12 or 14 galvanized wire (39) about which is wound a small insulated wire (40). The show-window cord is used for the upper part of the cable. It is large enough to be manipulated easily with bare hands, and, being made of two insulated wires, provides for making a circuit between the meter and the recording device. In its use, the two wires of which it is made must be separated at either end (41, 42, 43, 44) in order to make the attachment with the connecting plug (27) of the indicating device at the upper end and with the galvanized wire (39) and small wire (40) which lead to the meter at the lower end. A ring or snap (45), into which the galvanized wire is looped, is fastened, either by a loop (46) or a knot (47) to the lower end of the show-window cord.

In fastening the meter cable to the snap or ring with a knot (47), a strip of adhesive tape is wound around the cable two or three times, about 1 foot from the end, leaving about 6 inches of the tape at the beginning and end of the winding. The cable is then inserted through the snap or ring so that the snap bears on the adhesive tape, and a knot is tied in the

cable about the snap (45) and drawn down as tight as possible. The ends of the adhesive tape (48) are then wound around the cable, one above and the other below the knot, to keep it from sliding. The outside covering of the end of the cable can then be taken off to within 3 or 4 inches of the knot, exposing the ends of the two insulated wires (41, 42) which may then be fastened to the wires (39, 40) leading to the contact plug and to the hanger.

If the snap is held in a loop (46), a length of about 12 or 14 inches of the outside insulation is removed so that the wires can be doubled back and connected with those leading to the contact plug and hanger. The loop is first tied with string and then wound with adhesive tape, the tape being placed also around the cable where the ring bears on it.

The galvanized and small wires (39 and 40), which make up the lower end of the cable, should be long enough to reach from the surface to the bottom at the deepest point in the stream. Their use is advantageous because they offer small resistance to the moving water and thus reduce the distance that the meter is carried down stream.

The galvanized wire (39) provides both for carrying the weight of the meter and for one side of the circuit between the meter and the recording device. It is attached by ordinary loop connections to the snap in the lower end of the show-window cord and to the meter hanger (23). The circuit is made through it by the direct connection with the meter stem and by its connection at the upper end with one of the insulated wires (41) from the show-window cord.

The small wire (40), which provides for the other side of the circuit between the meter and the recording device, should be wound loosely around the galvanized wire in order to prevent annoying motion and wear, and may, if the water is swift, be held more securely if fastened with tire tape. At the upper end it is connected with one of the insulated wires (42) from the show-window cord, and at the lower end with the contact plug (15) of the meter. In order to aid in preserving the insulation between the galvanized and small wires they may be shellacked.

If the velocities or depths are not so great as to carry the meter down stream, the galvanized and small wires may be dispensed with. The snap (45) at the lower end of the show-window cord would then be attached directly to the meter stem and the circuit completed by attaching the insulated wires (41, 42) to the contact plug at one end and to the screw of the meter hanger at the other.

The meter may also be suspended by a single uninsulated galvanized wire, the circuit being completed through the water and ground (Fig. 3). In using the single wire the connection is from the water to the meter

through the contact point to the line, then to the battery and through the telephone to the bridge or cable, then to the ground and back to the water.




FIG. 3.—Arrangement of Circuit in Single Wire Suspension.

It makes no difference on which side of the battery the telephone is placed in the line.

When using a single wire, a clean metallic contact must be made between it and the bridge or cable from which the observations are taken. A little paint, rust, or other coating will prevent efficient work.

In measuring high velocities and deep streams, stay-lines or guy-lines are used in addition to the suspending cable to keep the meter in place.

CARE OF THE CURRENT METER.

The equipped current meter consists of:

- (a) Meter itself.
- (b) Telephone or other indicating device.
- (c) Battery.
- (d) Connecting wires.
- (e) Connecting plug.
- (f) Cable for supporting the meter.
- (g) Insulated wires for completing the circuit.
- (h) Weights.
- (i) Hangers.
- (j) Hanger screws.
- (k) Stop-watch.
- (l) Rods for wading measurement.
- (m) Rods or lines for sounding.

Aside from this equipment, the engineer, when on a field trip, should always be supplied with the following articles which are frequently necessary or desirable for making repairs to the station equipment and for the ordinary operation and care of the current meter.

- (a) Small screw-driver.
- (b) Parallel pliers with wire cutter.
- (c) Spanner wrench for dismantling meter.
- (d) Can of oil.
- (e) Roll of adhesive tire tape.
- (f) 25-foot metallic tape.

- (g) 50-foot steel tape.
- (h) Extra cone point.
- (i) Extra set of screws.
- (j) Small hatchet.
- (k) Extra battery.
- (l) Insulated wire.
- (m) Assortment of nails.

For carrying the meter and equipment two types of cases are in general use. One is a box $8\frac{1}{2}$ by $6\frac{1}{2}$ by 5 inches, arranged with a shoulder strap and just large enough to carry the meter and tail when taken apart, the weights, cable, and other equipment being carried in a separate case. The other is a box 17 by 12 by 6 inches, with a lower and upper compartment, the lower being designed to carry the weights, cable, and heavier tools, and the upper to carry the meter and more delicate parts of the equipment. A partition in the upper compartment provides a space into which the head is fitted and carefully packed so as to avoid injury. This case is shaped like a small suitcase and arranged with a carrying strap.

When an additional case is needed for the equipment, the canvas hand-bag, used by masons for carrying tools, is most convenient.

In taking the meter apart, remove the tail vanes and the hanger stem; then loosen the set-screw to the contact chamber, and pull the chamber out by a slight twisting motion. Care must be taken to let the cups be free to turn, so that the worm gear on the upper end of the shaft can disengage from the teeth of the contact wheel. In handling the contact chamber, it is well to take off the cap, so that the gear-wheel can be seen during the operation. The cone point can then be taken out and the cups released by loosening the upper part of the shaft with a spanner wrench. This wrench is so arranged that it can be used for loosening all parts of the meter.

In putting the meter together, first attach the cups to the cup shaft. In doing this, the upper part of the shaft should be inserted through the upper hole of the yoke before it is screwed to the lower part. Care must be taken to place the cups so that they will move counter-clockwise. After the cups have been fastened to the shaft, insert the cone point and clamp it in place, and then insert the contact chamber. In replacing the contact chamber, the cups should be left free to move on the cone point and care should be taken not to allow the cogs on the worm gear to catch on the teeth of the contact wheel. Before inserting the cone plug, the cone point should be adjusted and firmly secured with a lock-nut. The adjustment should allow a slight vertical motion of the cups.

Although the current meter is substantially made and will stand con-

siderable hard usage, it needs special attention and care to insure its proper working. In this connection the following instructions should be carefully observed :

1. Be sure that the set-screws are all tightened before putting the meter in the water; otherwise one of the parts may be lost.

2. Loosen the sleeve-nut and see that the meter runs freely before beginning a measurement; and spin the meter cups occasionally during a measurement to see that they are running freely, that is, that they will continue to move for a considerable time at a slow velocity.

3. See that the weights play freely on the stem, so as to take the direction of the current and thus avoid an unnecessary drag on the line.

4. If any apparent inconsistency in the results of an observation throws doubt on its accuracy, investigate the cause at once. Grass may be wound around the cup shaft; the cups may be tilted by tension on the contact-wire; the channel may be obstructed immediately above the meter; the meter may be in a hole; or the cups may be bent so as to come in contact with the yoke.

5. After a measurement, clean and oil the bearings (in order to prevent rust) and inspect the cone point.

6. In packing the meter, turn the sleeve-nut to lift the cups from the cone point.

7. Always see that the lock-nut on the cone point is screwed firmly against the cone plug.

8. If the cone point is dulled, it can be sharpened with an oilstone.

9. In measuring low velocities, be sure that the meter is in a horizontal position. If it has a tendency to tip, the balance weight on the tail should be adjusted or the meter be held rigidly by inserting a plug in the slot against the stem.

10. Avoid taking measurements in velocities of less than 0.5 foot per second, because the accuracy of the meter diminishes as zero velocity is approached.

11. For velocities of less than 1 foot per second the bearing point should be the same as at the time of rating. As the velocity increases, the condition of the point is less important, because the friction factor decreases.

12. In taking measurements at high velocities, sufficient weight, and a stay-line, should be used to hold the meter in the vertical.

13. In very shallow streams the meter should be suspended from the lower hole on the stem, and the weight should be placed above.

14. If the cups of a small Price meter are bent, they may be easily put in shape by pressing them with a piece of wood or metal with a round, smooth end.

15. The telephone receiver is very sensitive to electric currents, and can be used to locate any break in the circuit. First try the telephone and battery together (Fig. 4) in a circuit having a make-and-break point, as at *a*. This may be done by using a knife blade or a screw-driver, making connection where the wires enter the plug. If there is no click in the telephone, then the battery or the telephone does not make a circuit. If there is a click, insert the meter in the line and test for a contact in the meter head (Fig. 5) by revolving the meter wheel. If the meter is all right, put the meter cord in the circuit and test both sides by making double connection and touching alternate sides of the line, *a* (Fig. 6).

16. When the meter is not in use, disconnect the meter line from the battery, so that it will not become exhausted.

17. When a wet cell is used, the solution may be left in it for a time, if the zinc pole and stopper are replaced by a cork.

18. Never let the bisulphate dry, however, in the cell, as it forms a hard cake and polarizes the battery.

19. Do not let any bisulphate of mercury remain loose in the meter box; if it gets into the meter bearings it will corrode them.

20. The zinc pole in the bisulphate cell sometimes gets pushed down so that it touches the bottom of the cell, in which case the cell is short-circuited and becomes useless. To test this, lift the plug a little way out of the battery and see if there is a flow of current.

21. Keep the points clean where the battery makes contact with the metal plates.

22. The amount of current necessary to work a telephone receiver is very small, and a battery may be serviceable even though nearly exhausted.

23. If care is taken, it is very improbable that the telephone receiver will get out of order.

24. Do not strike the telephone receiver, as a heavy jar will to a greater or less extent damagnetize the pole pieces, and to that extent will injure the receiver.




FIG. 4.




FIG. 5.




FIG. 6.

Testing Meter Circuit.

25. Care must be taken not to short-circuit the dry battery when the meter is not in use, as in that way the cell becomes exhausted in a short time, the energy being used in heating the cell. To avoid this, the poles may be wound with adhesive tape.

26. If a dry cell which has been long in stock fails to work well, punch two nail holes in the wax on top of the cell and put it in water over night, when it may absorb enough moisture to renew it. The holes should then be coated over by heating the wax with a match and pressing it into place, or by pouring in melted paraffin. A cell which has been exhausted by use is not benefited much by this treatment. The life of a cell depends largely on the amount of leakage in the line during use.

RATING THE CURRENT METER.

The relation between the revolutions of the meter wheel and the velocity of the water must be determined by rating each meter before it is used. Theoretically, the rating for all meters of the same make should be the same, but, as a result of slight variations in construction, and in the bearing of the wheel on the axis at different velocities, the ratings differ.

Observations for rating meter No. 315, made February 19, 1912, at Chevy Chase Lake, Maryland, by W. McC. and M. I. W. Method of suspension, Cable; meter last rated at Chevy Chase Lake, May 12, 1909; present condition good, in repair.

| No. of run. | Observations for length of run. | | | Time in seconds. | No. of revolu- tions. | Revolu- tions per second. | Velocity ft. per second. |
|-------------------|---------------------------------|--------------|--------------|---------------------|-----------------------------|---------------------------------|--------------------------------|
| | Start. | End. | Distance. | | | | |
| | <i>Fect.</i> | <i>Fect.</i> | <i>Fect.</i> | | | | |
| 1 | 30.3 | 54.0 | 23.7 | 42 | 10 | .238 | .562 |
| 2 | 50.5 | 26.5 | 24.0 | 43 | 10 | .233 | .558 |
| 3 | 28.4 | 51.7 | 23.3 | 27 | 10 | .371 | .863 |
| 4 | 43.8 | 20.6 | 23.2 | 26 | 10 | .385 | .892 |
| 5 | 24.5 | 70.8 | 46.3 | 34 | 20 | .588 | 1.357 |
| 6 | 63.9 | 18.1 | 45.8 | 30 | 20 | .667 | 1.527 |
| 7 | 20.3 | 66.2 | 45.9 | 20 | 20 | 1.000 | 2.295 |
| 8 | 62.4 | 16.9 | 45.5 | 20 | 20 | 1.000 | 2.275 |
| 9 | 21.6 | 112.9 | 91.3 | 24 | 40 | 1.67 | 3.80 |
| 10 | 117.9 | 27.5 | 90.4 | 23 | 40 | 1.74 | 3.93 |
| 11 | 21.6 | 113.0 | 91.4 | 25 | 40 | 1.60 | 3.66 |
| 12 | 119.1 | 29.1 | 90.0 | 27 | 40 | 1.48 | 3.33 |
| 13 | 22.5 | 113.5 | 91.0 | 17.4 | 40 | 2.30 | 5.23 |
| 14 | 119.2 | 28.7 | 90.5 | 17.0 | 40 | 2.35 | 5.32 |
| 15 | 23.7 | 114.7 | 91.0 | 14.6 | 40 | 2.74 | 6.23 |
| 16 | 125.3 | 35.0 | 90.3 | 15.0 | 40 | 2.67 | 6.02 |

NOTE.—The runs are in pairs, the odd numbers being across the track and the even numbers in the return to the starting point.




FIG. 7.—Rating Curve for Small Price Meter.

A meter is rated by conducting it through still water with uniform speed (Pl. II, A) and noting the time, the number of revolutions, and the distance. The revolutions per second and the velocity in feet per second are afterward computed from these data. Many runs are made, as shown in the preceding table, the speeds varying from the least which will cause the wheel to revolve to several feet per second. The results of these runs, when plotted (Fig. 7) with revolutions per second and velocity in feet per second as co-ordinates, locate the points which define the meter rating curve, in general a straight line from which the rating table is prepared.

In making the run for the rating the time and distance corresponding to a given number of complete revolutions are recorded automatically by electric devices which are operated by the closing of the circuit in the contact head of the meter.

Theoretically, the wheel of a differential-action meter, when carried through still water, should revolve as a wheel revolves in passing over the ground. That is, in going a given distance it should make practically the same number of revolutions, regardless of speed. The rating of a great many small Price electric meters shows this number to be from 42 to 44 revolutions in going 100 ft.

Standard current meter rating tables are usually furnished by the makers of meters and when the meters are used under the same conditions under which ratings were made, the tables will usually give results within 1 or 2 per cent of the individual rating table for the meter in question. Special ratings for individual meters can be obtained, for a nominal fee, from the United States Bureau of Standards, which maintains a fully equipped rating station at Washington, D. C.

The relative ratings of various types of current meters are shown in Fig. 8.

SOUNDING APPLIANCES.

The most common sounding appliances in general use are rods and weight and line.

Rods are limited in use to depths of less than 15 feet. If over 5 feet long, they should be round in order to be easily handled and may be made either of gas-pipe or of wood. Rods under 5 feet in length should be made of flat strips of wood 3 inches by $\frac{1}{2}$ inch with one face cut to a knife edge, against which the water will not rise in swift velocities. The graduations should be as close as the desired accuracy of soundings and so marked as to be easily read. In order to avoid sinking into the bed of the stream, the bottom of the rod should be protected by a shoe 3 inches or more in diameter.



A. UNITED STATES GEOLOGICAL SURVEY CURRENT-METER RATING STATION, CHEVY CHASE, MD.



B. TYPICAL GAGING STATION FOR BRIDGE MEASUREMENT.

Weights and lines of many forms are in use and are manipulated either directly by hand or by means of a sounding-reel in case of very deep soundings. The line should be of some material which does not shrink or stretch on wetting. For reels piano or sash-weight wire is generally used. The best form of hand line for use at bridges is a combination of the show-window cord used for supporting the meter, which can be easily grasped with the hands, for the upper part, and No. 12 or 14 galvanized wire, which offers but little resistance to the current, for the lower part.




FIG. 8.—Typical Current Meter Rating Curves.

The shape of the weight should be such as to offer small resistance to the water, and the amount of weight required will depend on the depth and velocity of the current.

The line with meter and weight attached frequently is used in making soundings.

GAGES.

The gage is the instrument, graduated scale or other device, whereby the stage and changes in stage are observed or recorded. This fluctuation is measured with reference to a fixed datum which must be referred

to one or more permanent bench marks, and to which the position of the gage must maintain a constant relation. The accuracy of all records of discharge is absolutely dependent on the maintenance of this relation.

In connection with all gage height records, special care should be taken to keep a full history of each and every condition which may affect the gage records or their interpretation. These should include full notes of all matters which pertain to the gage and its installation, such as repairs and changes in datum or location, and also a history of all conditions which may affect the gage readings, such as changes in the channel or the construction of dams or other works in the vicinity.

The value of most series of gage height records increases with their length, and many long-time records have been rendered practically valueless on account of insufficient data to make possible their proper interpretation.

The many styles of gages in use all belong to two classes, non-recording and recording.

NON-RECORDING GAGES.

The various forms of non-recording gages may be grouped into (1) direct gages, consisting of fixed, graduated staffs or scale boards on which the water rises and the stage is observed directly, and (2) indirect gages, consisting of graduated scale boards located above the water surface, to which the index of the stage of the water is transferred by means of a movable chain or rod of known length operated either automatically by means of a float and counterweight or by the observer whenever a record is desired.

DIRECT GAGES.

Direct gages consist of fixed staffs which may be either vertical or inclined. If a gage of this type can be established and properly maintained, it is doubtless the most satisfactory non-recording gage that can be used. The requirements for a satisfactory gage of this class are (1) that the graduations be both clear and permanent; (2) that the gage be easily accessible to read; and (3) that it be stable. It has the advantage of certainty in datum so long as the gage is undisturbed, small first cost, and simplicity in reading, but the disadvantage of being liable to disturbance or destruction by frost action or by floating ice, logs, or drift.

Vertical staff gages.—The vertical staff is better than the inclined, when there is available, either in or over the water, an artificial or natural object having a vertical face to which the gage may be attached. Such object may be a bridge abutment or pier, a wharf, a tree, or a rock.

The best form of vertical gage consists of a base of rough 2-inch by 4-

inch or 2-inch by 6-inch plank, to which a lighter plank having the graduated face may be easily fitted and nailed, with the zero at the desired elevation. The graduated plank will be found satisfactory if made in about 5-foot sections of $\frac{7}{8}$ -inch by 5-inch pine, painted white, with graduations cut as V-shaped notches painted black. This facing and graduation is cheaply made, the graduations are reasonably permanent, the sections are convenient to carry and are easily installed.

Inclined staff gages.—The inclined staff is useful where there is no existing object to which a vertical staff may be attached. It should be made of 4-inch by 4-inch timber, or larger, supported at short intervals on posts or concrete piers firmly set in the ground, and should be graduated by level after being placed in position so as to give the readings directly. Such gages are especially liable to change of datum and should be frequently checked in elevation at several points. Plate V, A, shows a hook gage in the well and an inclined gage on the bank.

INDIRECT GAGES.

Indirect gages in common use are of three types, the hook, the weight, and the float. The essential requirements for gages of this type are: (1) a constant length of the intermediate part used for transferring the index of stage to the scale board, and (2) a permanent scale board so graduated and placed that it may be easily and accurately read. They are adapted for use where a fixed staff gage would be in danger of disturbance or can not be easily read.

Hook gages.—The hook gage invented by Boyden about 1840 is the most precise instrument known for the measurement of stage and will be found of value wherever determinations of stage to a hundredth of a foot or closer are desirable. By careful adjustment such a gage can be made to read to a thousandth of a foot. The value of such accuracy of reading is, however, dependent upon the same accuracy in the determination of the other factors affecting discharge. This gage consists of a vertical inversely graduated rod, carrying a hook at the bottom. The rod slides in fixed supports provided with a vernier for reading. The hook is submerged and by means of a tangent screw is gradually raised until the point just breaks the surface of the water so as to show the pimple resulting from capillary action.

A simple form of hook gage (Fig. 9) can be arranged by using a movable staff inversely graduated to feet only, with a hook on the bottom, sliding against a fixed scale 1 foot in length carefully graduated to fractions of a foot. In reading the stage the feet are indicated by the foot-

mark on the staff which is opposite the fixed foot scale from which the tenths and hundredths are read.

Hook gages arranged with verniers are applicable for use only in connection with experimental hydraulic work or with carefully adjusted sharp-crested weirs. The simple type of hook gage has a wider range of use and will be found advantageous in conjunction with automatic gages, in canals, and other channels connected with diversion works and, during low water periods, at many gaging stations where small changes in stage correspond to large percentage changes in discharge.

Weight gages.—The simplest form of the weight gage consists of a graduated rod or tape, which the observer uses to measure vertically down to the surface of the water from a reference mark on a bridge, vertical ledge, or overhanging tree. The record of stage obtained by this means must be adjusted to read directly from the datum.

The weight gage used by the United States Geological Survey (Fig. 10) is believed to be the most practical gage of this class. It consists of a graduated scale board, 10 feet or more in length, usually either extending from or contained in a box supporting a pulley wheel, over which runs a heavy sash chain, to which is attached at one end a weight and, near the other end, a marker. This, as a whole, is fastened in a horizontal position to a bridge or other structure, so that the weight when lowered will come in contact with moving




FIG. 9.—Simple Form of Hook Gage.

water, as the exact point of contact of the weight and water can not easily be determined by the observer above if the water is still.

Generally the scale board is graduated only for a length of 10 feet. If the range of stage is greater than that amount, provision must be made for measuring it. This is accomplished by a second and, in extreme cases, a third marker, spaced at intervals of 10 feet from the first marker.

The most satisfactory chain so far used for this form of gage is "Morton's champion metal window sash chain, No. 1 regular." Of the substitutes which have been used the best is probably some form of steel or bronze tape, which will change little if any in length but which has

been found to be liable to break, expensive to mend, and if exposed to the wind to offer considerable resistance, making it difficult to take accurate observations. Woven wire sash cord and various forms of wire are not so satisfactory as they are liable both to kink and to stretch and are not easily adjusted in length.

To read the chain gage the observer releases the chain and allows the




FIG. 10.—United States Geological Survey weight gage. *A* shows the complete boxed chain gage with the "marker" or "index" shown at *a*. *B*, *b b'* shows the part of the chain that is measured to detect elongation, and *d* shows the threaded pin and lock nut, by means of which the length of the chain is adjusted. If the zero marker reads above the 10-foot mark at high stages, a second marker is attached to the chain 10 feet below the first and the reading of the second marker is increased by 10 feet. *C* shows the chain and scale with a projecting nail at *c*, over which a link of the chain is hooked when the weight is drawn up into the down-spout. *D* and *E* show cross-sections of the box through the hasp and lock.

weight to lower until it just touches the surface of the water, in which position the stage is read on the graduated scale opposite the marker.

This gage has the advantage of stability in position, as it is above all danger from ice and drift. It has the disadvantage of possible uncertainties in the datum, on account of change in length of chain, due to wearing caused by the moving of many parts upon one another, and by changes in elevation of the structure to which it is attached. To avoid error the chain length, that is, the length from the end of the weight to the marker, must be frequently measured and adjusted to the standard length. This adjustment is made either by cutting out a link or by the adjusting device with which the chain is attached to the weight.

Float gages.—A non-recording float gage consists of a float arranged to rise and fall with the stage. The float carries either a staff or a chain passing over a pulley and kept taut by a counterweight. A marker attached to the staff or chain at a fixed distance from the float moves along a fixed graduated scale board and thus indicates the stage reading. If a staff is used on the float it may be graduated inversely and the stage observed opposite a fixed marker, or it may be arranged to read as explained for the simple form of hook gage.

This type of gage is best adapted for use in pump houses and permanent buildings erected over the water surface as, under these conditions, the float and all parts of the gage will be fully protected. When the float carries a chain, the same requirements should be observed as described for the chain on the weight gage.

ESTABLISHMENT AND MAINTENANCE OF NON-RECORDING GAGES.

In addition to the points already discussed relative to the establishment and maintenance of the various types of non-recording gages, the following conditions are generally applicable. In this connection too great emphasis can not be placed on the importance of conditions affecting the gage and its reading as the accuracy of all discharge records depends largely upon them.

Installation of gage.—The gage should be so located that it may be easily read and be without the influence of disturbing effects, such as boils, backwater, and crosscurrents. It should be graduated to read directly the elevation above the datum or zero which should be placed well below the lowest water in order to avoid negative stage readings. In order to accomplish this it is generally advisable to put the zero at the approximate elevation of the bed of the river at the lowest point in the section.

The construction and installation should be accomplished in a thorough and workmanlike manner, thus assuring the permanence of the gage and the accuracy of the results obtained by it. The scale board should be clearly graduated in accordance with the degree of accuracy expected in the observations, and each foot and tenth mark should be numbered, thereby eliminating many errors in readings. The reading of the gage should receive special consideration.

Checking gage datum.—The permanent maintenance of the datum of every gage is absolutely necessary. To accomplish this it must be referred to at least two permanent bench-marks from which it can be readily checked by means of a level.

It will be convenient if one of the bench-marks is fixed on an easily accessible part of the bridge or on an overhanging tree or rock from which the stage of the river may be directly determined by measurements made from it to the surface of the water by a staff or steel tape. Such a mark, generally known as the reference point, should be as permanent as possible and not generally any part of the gage or gage box. The other bench-marks should be placed on objects apart from the structure to which the gage is attached, out of reach of possible damage or interference and so located, if possible, that the gage can be checked with one set up of a level.

The elevation of the bench-marks should always be determined and expressed above the datum of the gage without reference to an intermediate datum.

In order that the gage heights may be readily used in flood studies and in determining slopes along the river, the datum of the gage should be, whenever possible, connected with sea level or with any city or railroad datum available.

In making the original reference and in future comparisons of the gage with its bench-marks, the level, if practicable to do so, should first be so set as to obtain directly the height of the instrument above the datum of the gage. In the case of a staff this can be accomplished by reading directly from the gage, or by setting the bottom of the level rod at some definite point on the gage. For the standard weight gage the instrument should be set below the elevation of the pulley and the gage weight lowered until its bottom is on a level with the horizontal cross-hair. The reading of the gage in this position gives directly the height of instrument.

The height of instrument should not be measured from a water surface, because the elevation of the surface of the river may vary materially within its width or within short distances up and down the stream.

In connection with the checking of indirect gages the first operation is to check and adjust, if necessary, the length of the intermediate part for transferring the index of the gage to the scale board. This having been accomplished, the datum of the gage should be compared with the bench-marks by means of a level.

If the standard chain is used, the length of the chain from the end of the weight to the marker should be measured carefully under about a 12-pound pull. In order that this measurement may be made easily the marker should be placed a few feet from the end of the chain. Nails properly spaced in the floor of the bridge will facilitate this measurement and will be serviceable in future checkings of the chain length, which should be made at each subsequent visit of the engineer to the station.

The engineer should paint or mark plainly on the inside of the cover of the gage box the length of the chain and the elevation of the reference point from which stage can be determined.

STILLING BOX.

A stilling box for eliminating wave action is desirable, and oftentimes necessary, in connection with all types of gages, especially where precise records of stage are desired, as, for example, in canals, at weirs, and at current meter stations during low water periods.


In general such a stilling box may consist of a wooden box or a metal pipe erected in the stream around the gage and extending to the bed of the stream, into which the water is admitted through small holes, or a well connected with the stream by a pipe as described for recording gages. The level of the water in the stream and in the stilling box must be frequently compared in order to eliminate errors due to the clogging of the openings to the box.

For use on staff gages, whether vertical or inclined, a special adjustable box is necessary on account of the great range of stage for which provision must be made. A wooden box that has openings through the bottom and made to slide up and down on the gage may be set at the surface of the water by the observer at the time of each observation. Frequently a tin can or pail may be utilized in a similar manner with good results. These adjustable boxes must be varied and arranged to suit particular gages.


RECORDING GAGES.

Recording gages make a record of stage either continuously by a curve, the coordinates of which indicate the time and the stage, or at stated intervals of time by a printing device. The essential parts of the recording gage are: (a) a float which rises and falls with the surface of the water, (b) a device for transferring this motion of the float to the record, either directly or through a reducing mechanism, (c) the recording device, and (d) the clock.


These gages should be used where the diurnal fluctuation of stage is so great and irregular that it is impossible to determine even approximately the mean daily gage height from a limited number of staff gage readings daily, as on streams artificially regulated for power or other purposes, or on those fed by melting snow or ice or subject to short and violent storms. Their use is also frequently necessary in connection with the division



C. FRIEZ.



B. GURLEY.
RECORDING GAGES.



A. STEVENS.

of water both in streams and canals, as well as on streams where daily observations of stage on a staff gage would be sufficient, but where observers are not available. They are also being used increasingly and with great benefit in the operation of power plants.

With each recording gage a staff or some other form of non-recording gage is necessary in order that the accuracy of the stage record may be easily and frequently checked.

CONTINUOUS-RECORD GAGES.

Various automatic gages have been built to record stage by means of a graph. These are generally similar in having a drum for carrying the record sheet, a movable arm for carrying the pencil or pen, a clock which propels either the pencil or the drum and determines the time ordinate, and a float with counterweight which propels either the drum or the pencil and determines the stage ordinate.

Of the many gages of this type that have been devised the Friez,^a Gurley, and Stevens^b (Pl. III, A and C) have been found well adapted for general use. The Friez and Gurley gages are similar in that they are operated by 8-day clocks, and the record sheets are designed to carry one-week records. The time ordinate is parallel to the axis of the drum, which carries the record sheet, and the stage ordinate is perpendicular to this axis.

The Stevens gage is operated by a weight-driven clock which can be arranged to run from 30 to 90 days by providing sufficient fall for the weight. The record sheet is furnished through a supply roll over a main drum to a receiving roll. The supply roll is arranged to carry sufficient paper for a year's record. The graph for any period of time can be removed as desired. In this gage the stage ordinate is parallel with the axis of the drum and the time ordinate perpendicular to this axis. The drum is operated by the clock, and the pencil carriage, operated by the float, is so arranged that when it reaches either limit of the gage sheet it reverses, thus recording any stage.

It is essential that continuous-record gages be arranged so that the graph will not extend beyond the limits of the record sheet. This is accomplished on the Friez and Gurley gages by having the stage ordinate pass around the drum and on the Stevens gage by the reversal of the pencil carriage.

^a Manufactured and sold by Julien P. Friez, Baltimore, Md.

^b Manufactured and sold by Leupold & Voelpel, Portland, Ore.

The scales of the record sheet will depend upon the range of stage to be recorded. The usual vertical scale for large streams is 1 to 10 and for smaller streams 1 to 5. A time ordinate of an inch to a day is usually satisfactory. The possible accuracy of a continuous-record gage is determined by the reliability of the clock and the amount of lost motion in other parts of the gage, which may introduce errors in the curve.

In the operation of the continuous-record gage, visits at regular intervals are necessary in order to wind the clock and change or remove the record sheet (Fig. 11). In changing the sheet, the exact time and




FIG. 11.—Typical Continuous-record Gage Sheet.

stage as observed on the staff gage, should be noted on the face of both the old and the new record sheets. The clock should be set, if necessary, and the amount of error in time also recorded on the old record sheet. In placing the new sheet care must be taken to start the pencil at the proper time and stage ordinates.

In addition to these regular visits, intermediate visits should be made as frequently as possible in order to insure the accuracy and continuity of the record. The exact time of such visits, together with the stage as determined by the staff gage and other pertinent notes, should be made on the face of the record sheet or in a special note book and referred to the curve by an arrow pointing to the location of the pencil point at the time of the visit. When a note book is used each entry should be numbered and dated both in the book and on the record sheet.

The continuity of a record obtained by this type of instrument does

not necessarily indicate that the record is accurate. The above precautions are therefore of importance. Full notes of all conditions which may in any way affect the record or its interpretation should be made on the record sheet or in a special note book at each and every visit of the observer.

The following sources of error are inherent in continuous-record gages of the float type:

1. Difference between elevation of water in the float well and the river.
 2. Inaccurate starting of pencil on the record sheet.
 3. Lag in the mechanism which prevents the recording pencil from responding promptly to changes in stage.
 4. Errors in the clock.
 5. Insufficient scale of both time and stage to enable accurate interpretation of the record.
 6. Imperfect printing of the record sheet.
 7. Expansion and contraction of the record sheet due to moisture.
- This can be partly eliminated by placing cubes of camphor or other absorbents in the gage box.

The mean daily gage height may be determined from the continuous record sheet in three ways:

1. By taking the average of readings at regular intervals of time, depending upon the variation in fluctuation of stage;
2. By means of an ordinary planimeter, in which case the area bounded by the curve and its base line is divided by the length of the base;
3. By the Fuller integrator, which gives the mean height directly by tracing the line.

In certain studies it may be desired to plot on the record sheet the curve of corresponding discharge or run-off, from which the mean daily discharge will be taken.

INTERMITTENT-RECORD GAGES.

The only successful automatic gage so far constructed which prints the stage and the time at regular intervals of time is the Gurley gage (Pl. III, B) which has been designed and built along lines suggested by the engineers of the Water Resources Branch of the United States Geological Survey. This gage is free from lost motion and the time and stage are printed (Fig. 12) to the nearest hundredth of a foot each 15 minutes. The gage is operated by a weight-driven clock and, with sufficient fall for the weight, will run 60 or even 90 days without wind-

ing. It is compact, small and comparatively simple in construction, and is adapted to work where the highest degree of accuracy is desired. The mechanism of the gage sets on an iron base 14 inches square and is covered with a tight metal cover about 21 inches high which protects it from both dust and moisture.

The recording mechanism consists of three parallel type wheels (behind the clock), on the face of which are raised figures and divisions. On the first of these wheels the periods of time from 1 to 12 hours are indicated at intervals of 15 minutes, for recording time.

The height is recorded by the other two wheels, one of which carries the feet-numbers to 36 feet and the other the tenths and hundredths of a foot.

The time-type wheel is controlled by a weight-driven clock, which is so constructed as to endure changes in temperature without variation in its regular operation.

The two wheels which indicate the stage of the river are actuated by a float which with its counterweight is supported by a metal band perforated at intervals to fit over the pins in the periphery of the pulley wheel attached to the height wheel over which it runs.

The record is made by the striking of a mechanically actuated cushioned hammer, every 15 minutes, against a strip of paper which is backed with a carbon strip and passed over the face of the type wheels. The record paper and carbon paper are unwound from separate spools and taken up on two other spools, after they pass over the type wheels.

Maintenance of this gage, in addition to general inspection, requires attention in regard to the following:

1. Check the relation of water in and outside the float well.
2. See that the stage-type wheel is recording correctly.
3. Check the clock.
4. If desired, remove the record printed since the last visit.
5. A history of each visit, of changes, and of work done should be made in a special note book and referred to by date and number both on the record sheet and in the book.

| | | |
|------|------|------|
| 3-45 | -.12 | -.11 |
| | | -.12 |
| 4-00 | -.12 | -.09 |
| | | -.08 |
| 4-15 | -.12 | -.07 |
| | | -.08 |
| 4-30 | -.12 | -.04 |
| | | -.05 |
| 4-45 | -.12 | -.01 |
| | | -.98 |
| 5-00 | -.11 | -.99 |
| | | -.96 |
| 5-15 | -.11 | -.96 |
| | | -.97 |
| 5-30 | -.11 | -.94 |
| | | -.90 |
| 5-45 | -.11 | -.91 |
| | | |
| 6-00 | -.11 | -.89 |
| | | -.86 |
| 6-15 | -.11 | -.87 |
| | | -.88 |
| 6-30 | -.11 | -.84 |
| | | |
| 6-45 | -.11 | -.81 |
| | | -.82 |
| 7-00 | -.11 | -.79 |
| | | -.80 |
| | | -.77 |
| 7-15 | -.11 | -.78 |

FIG. 12.—Typical Intermittent-record Gage Sheet.

X



B. CABLE TOWER AND CAR.



A. BOX SHELTER FOR RECORDING GAGE.

INSTALLATION OF RECORDING GAGES.

A large element in the satisfactory operation of any automatic gage is its proper installation, which will determine the accuracy of any recording gage record. Improper installation will deteriorate the results from the best of gages, while with an adequate installation the accuracy of the results is only limited by the construction of the gage. If the expense of an automatic gage is to be incurred, approximate results are not satisfactory and it is, therefore, essential that the installation be so thorough as to eliminate any question of the accuracy of the results. Special care and thoroughness in installation are necessary if the records are to extend over winter months and times of freshet, in order that freezing and disturbance from floating ice and débris may be eliminated.

In installing an automatic gage (Pl. V, A) it is necessary to provide a well, connected with the river, for the float; a house to shelter the gage; and staff gages with bench-marks for checking the record and maintaining its datum. Local conditions will usually determine the method and details of the installation. (Pl. IV, A.)

In the ideal installation the well and the house should be located far enough back from the river to be out of danger from floating ice or drift and to provide sufficient protection for the well and pipes to prevent freezing. The bottom of the well must be below the lowest stage and not less than $3\frac{1}{2}$ feet square. It should be provided with a permanent ladder, extending to the bottom, so that the float and intake pipe can be readily inspected, and if the gage is to be maintained for a long period of time it should be lined with concrete. Otherwise a heavy plank lining can be substituted. The float pipe should be not less than 4 inches in diameter and the intake must be well below the lowest stage of the river and provided with a screen for keeping out silt, etc. It should also be provided with a check gate as it enters the well, so that the flow can be reduced to eliminate wave action. The best material for the intake pipe is spiral-welded steel with flange unions.

The shelter for the gage should have inside dimensions of at least 5 feet square and 6 feet high, in order to provide sufficient room for the observer to conveniently look after the gage. The house should have a window and the door should be closed when the cover is removed from the gage, to keep out dust. The floor should have a trap door for entering the well and a ventilating pipe should be provided both for the house and the well, in order to eliminate the dampness. The stand for the gage should be high enough to provide for its easy inspection.

The most satisfactory material for the house is concrete with metal

covering on the roof and door which will insure the gage against destruction by fire or from being otherwise disturbed. Many automatic gages in out-of-way places have been destroyed by being used as targets for rifle shooting.

Two staff gages, referred to permanent bench-marks, should be installed with each automatic gage in order to check the readings with the stage of the river. One (preferably a hook gage) should be located in the float well to determine whether the water in the well is at the same elevation as in the river, and the other should be placed in the river and of a type best suited to the locality. The river gage should be in the same cross-section of the river as the intake pipe. It may, however, be dispensed with by the use of a reference point so located that the elevation of the water surface can be easily determined from it.

When the well is properly constructed and located back from the river, there should be no danger from frost, even in temperatures as low as 30 degrees below zero. In case there is danger from freezing, it can be prevented by arranging a floating lamp in the well, or by hanging an electric light bulb near the surface of the water. Where the float is in a tube of small diameter, freezing can be prevented to some extent by pouring oil in the well.

The best type of lamp is a floating iron kettle suspended by a counterweight. In the kettle a tight cover, carrying a burner, should be soldered a few inches from the top. Such an arrangement will provide for two or three quarts of oil, which, with an ordinary lamp burner, will burn several days.


STRUCTURES FOR MAKING DISCHARGE MEASUREMENTS.

In addition to gages, as already described, regular gaging stations must be provided with—

1. A structure to support the engineer while observing the velocity and depth, when the stream is too large to permit making measurements by wading.
2. A cable and stay line to hold the meter in the vertical when the soundings and velocity observations are made.
3. A graduated line for indicating the distances between the points of measurement.

STRUCTURE FROM WHICH MEASUREMENTS ARE MADE.

Discharge measurements will be made either (1) from an existing or specially constructed bridge (Pl. II, B), (2) from a cable carrying a car (Pls. IV, B, and V, A), or (3) from a boat held in position by a cable or guy line.



A. TYPICAL CABLE STATION WITH AUTOMATIC GAGE.



B. TYPICAL GAGING STATION FOR WADING MEASUREMENT.

BRIDGES.

When existing bridges are available in localities where the conditions of channel and current are suitable for the collection of a good discharge record, a gaging station may properly be located at such structure, and when so located it can generally be installed at a minimum cost. Ideal conditions for measurements are not usually found at existing bridges, and stations so located generally involve the sacrifice of accuracy to save expense. The selection of a gaging section without reference to existing structures makes possible the securing of better conditions of measurement. A material saving will be made thereby in maintenance if the station is to be continued through a considerable period of time, even though the first cost of the station is large, because fewer discharge measurements will be necessary for determining the station rating curve.

If the stream is not too large, a special cheap wooden or suspension bridge may often be constructed advantageously.

CABLES.*

In the absence of a bridge as a support for the engineer in making observations of velocity and depth, a cable for carrying a car may be stretched across the stream. The equipment and appurtenances for such a cable station (Pl. IV, B) consist of the cable, supports and anchorages for sustaining it, turnbuckles for regulating the sag, and a car for carrying the observer.

The cable.—Iron or steel cable of sufficient tensile strength to sustain the car and two men, in addition to the weight of the cable itself, should be used. The stress in the cable due to a vertical load will increase as the sag decreases. Consequently the cable is least safe when the sag is a minimum. In the following table the diameter is computed for a live load of 450 pounds on the cable at the center of span and an initial tension corresponding to the sag given in the table. With an ultimate strength of 80,000 pounds per square inch the factor of safety for these dimensions is about 5. The sag given in the table is the least allowable; if it is increased, the factor of safety is increased. In making connections the cable should not be bent to a shorter radius than three diameters and the turnbuckle and connections should have a safe working strength of an amount given in the last column of the table. Galvanized cable, pulley, etc., should be used, in order to delay corrosion.

* Engineering News, May 6, 1909. "The Design of Cable Stations for River Measurements," by J. C. Stevens.

Proper diameter and sag of galvanized steel cable, with live load of 450 pounds for spans of 100 to 800 feet.

| Span. | Diameter. | Sag. | Stress. |
|--------------|----------------|--------------|--------------|
| <i>Feet.</i> | <i>Inches.</i> | <i>Feet.</i> | <i>Feet.</i> |
| 100 | $\frac{1}{2}$ | 4 | 2,938 |
| 200 | $\frac{5}{8}$ | 6 | 4,167 |
| 300 | $\frac{3}{4}$ | 8 | 5,061 |
| 400 | $\frac{7}{8}$ | 10 | 6,300 |
| 500 | $\frac{1}{2}$ | 12 | 7,813 |
| 600 | $\frac{3}{4}$ | 12 | 10,125 |
| 700 | 1 | 14 | 12,626 |
| 800 | $1\frac{1}{8}$ | 15 | 16,660 |

Supports.—The nature of the supports for the cable will depend on the physical characteristics of the location. It may be supported either by some natural object, as a tree or cliff, or by some form of artificial tower.

Frequently trees are properly located to serve as supports, and when so located may be cheaply and satisfactorily used. The only objection to them arises from their swaying in the wind. Protection in the form of wooden blocks must be provided for the limbs which support the cable to insure that the motion of the tree shall not speedily cause the destruction of the support. A better way, when possible, is to pass the cable through a pulley block, which, in turn, is attached to the support. Large rocks, when available at sufficient elevation above the stream bed, make excellent cable supports, as the cable can be connected directly to the anchorage.

In case artificial supports are required the form will depend somewhat on the height necessary. For low support and a short span; a single post, 10 to 14 inches in diameter, set firmly in the ground, is sufficient. When, however, heights greater than 12 or 15 feet are necessary, "shear legs" (Pl. IV, B) are generally used. In their construction two posts (8 inches by 10 inches or their equivalent in round logs) should be set in the ground 10 to 15 feet apart at the base, inclined toward each other so that they will be 2 to 5 feet apart at the top, and connected by at least three strong pieces secured to them by bolts fitted with washers and nuts or by "drift bolts" of suitable lengths; or these posts may be set so that they will cross near their ends, and should then be fastened to each other by two or more bolts with nuts. The cable may rest on the top cross-bar in the first instance or in the crotch in the second instance, but in either case should preferably be passed through a pulley block at the end having the turnbuckle. All towers should be well guyed

so they can not move toward the stream. In crossing the shear legs the cable should make equal angles with the legs on both sides.

Anchorage.—The form of anchorage will vary with different conditions. If solid rock is available, an eye-bolt split at the lower end and driven against a wedge may be set in a drill hole, which should then be completely filled with sulphur, lead, or Portland cement grout. If no solid rock is at hand, a "deadman," made of a log 8 to 12 inches in diameter, may be buried in the ground below the limits of frost and at least 4 feet deep, the length of the log and depth in the ground depending somewhat on the span of the cable.

The anchorages should be so arranged by means of long eye-bolts embedded in concrete, or auxiliary cables attached to the "deadman," that the main cable and its connections will be exposed for inspection.

The cable should be attached at each end to two independent anchorages or supports. In case posts are used for supports the cable should be attached to them by means of a short piece of cable with clips. A support which is not set in the ground should be guyed to anchors of some kind, both forward and backward, and the cable attached to it. In still other cases it is advisable to make a second independent anchorage in the ground.

Turnbuckle.—A turnbuckle for use in taking up sag, having a capacity of 2 to 6 feet, should be inserted in the cable on the side of the river from which the engineer approaches the station. This should have right-and-left screws and not a screw at one end and a swivel at the other.

An arrangement can easily be made whereby one man alone can tighten the cable, even if a greater length than the capacity of the turnbuckle must be taken up. This is accomplished by means of an auxiliary cable, which spans the turnbuckle and is clipped to both the main cable and the anchorage. The turnbuckle having been unscrewed and in that condition clipped to the main cable, the auxiliary cable is released and the turnbuckle drawn up. If the capacity of the turnbuckle does not remove a sufficient amount of sag, the auxiliary cable must again be clipped to the main cable and the turnbuckle released, unscrewed, and slipped along the main cable to a new position and the operation repeated.

Car.—The car should be made about 5 feet by 3 feet and about 1 foot deep and attached at each end to a pulley on the cable by means of iron or steel straps or by light cable, or by wooden standards, never by manila or cotton rope. If wooden standards are used, they should be so securely attached to the car that in case of accident they will not be wrenched loose. Plate IV, B, shows an excellent type of car. The details of the iron work for this car are shown in figure 13. The car in operation is

shown on Plate V, A, and a full bill of materials necessary for its construction is given in the following table.




FIG. 13.—Details of Hangers for Cable Car.

For safety and ease in propelling the car, a puller as shown on Plate III, B, should be provided.

Ordinary cable stations for spans up to 100 feet can be installed and equipped at a cost of from \$50 to \$100.

Bill of materials for large standard gaging car.

No. of
pieces

WOODWORK (STRAIGHT GRAINED).

- 2 $1\frac{3}{4}'' \times 2\frac{3}{4}'' \times 5' 4''$ sides of bed frame.
- 2 $1\frac{3}{4}'' \times 2\frac{3}{4}'' \times 1' 6\frac{1}{2}''$ ends of bed frame.

- 2 $\frac{3}{4}$ " \times $9\frac{1}{2}$ " \times 5' $5\frac{1}{2}$ " sides of bed.
- 2 $\frac{3}{4}$ " \times $9\frac{1}{2}$ " \times 1' 10" ends of bed.
- 4 $\frac{3}{4}$ " \times $7\frac{1}{2}$ " \times 1' $9\frac{3}{4}$ " seats.
- 1 $1\frac{3}{4}$ " \times $3\frac{1}{2}$ " \times 2' 2" foot rest.
- 1 $1\frac{3}{4}$ " \times 2 " \times 5' 6" top spacing bar.
- 2 $1\frac{3}{4}$ " \times 2 " \times 4" spacing blocks.
- 2 2 " \times 2 " \times 4" split diagonally, corners.

IRONWORK.

Sheaves.

- 2 8" roller bushed sheaves, spoked.
- 2 4" \times $\frac{3}{4}$ " \times $\frac{3}{8}$ " loft sheaves.

Hangers, as shown on drawing.

- 2 $1\frac{3}{4}$ " \times $\frac{3}{8}$ " \times 11' 10" steel hangers, bent.
- 2 $1\frac{1}{4}$ " \times $\frac{3}{8}$ " \times 3' 0" steel hangers, bent and twisted.

Machine bolts, with two washers each.

- 2 $2\frac{3}{4}$ " \times $\frac{3}{4}$ " bolts with cotter pins for 8" sheaves.
- 7 $2\frac{3}{4}$ " \times $\frac{1}{4}$ " bolts for spacing blocks.
- 5 $1\frac{1}{2}$ " \times $\frac{1}{4}$ " bolts for main hangers.
- 5 $4\frac{1}{2}$ " \times $\frac{3}{8}$ " bolts for main hangers.
- 5 $3\frac{1}{2}$ " \times $\frac{3}{8}$ " bolts for foot-rest hangers.
- 2 $2\frac{1}{2}$ " \times $\frac{3}{8}$ " bolts for foot rest.
- 2 4 " \times $\frac{3}{8}$ " bolts for small sheaves.
- 2 6" galvanized line cleats with screws.

BOATS

Boat stations as ordinarily equipped are unsatisfactory on account of the difficulty in holding the boat in position, in making soundings and in operating the meter. Ferry boats operated from cables can often be advantageously used. In the measurement of large rivers, as in the work of the Corps of Engineers, United States Army, on the Niagara, St. Lawrence, and other large rivers, specially constructed catamarans* with special equipment for their control and operation, have been used with great success. Such equipment is expensive and is generally applicable only for special investigations on large streams.

* See reports of U. S. Lake Survey.

STAY LINE CABLES.

In order to hold the meter in the vertical when making measurements, all stations should be equipped with cables and stay lines (Pl. V, A). The cable need not exceed one-fourth inch in diameter and for ordinary stations a cable of No. 10 or No. 12 galvanized wire will be ample. It should be located from 30 to 100 feet above the measuring section, depending on the width and depth of the stream, and should carry a ring about 3 inches in diameter, through which a small rope is run, one end of which is connected to the upper end of the meter stem and the other end is held by the man operating the meter. In operation, the ring moves freely on the cable and the rope slides through the ring, thus enabling the observer to hold the meter in any desired position in the stream. A cable and stay line are easily installed and manipulated and are indispensable for obtaining accurate measurements when the velocities and depths are considerable.

LINES FOR INDICATING MEASURING POINTS.

In order that the measuring points at a gaging station may be easily located at the time of making measurements, and that the distance between the measuring points may be readily determined, they should be referred to a fixed initial point, and the section should be divided into regular intervals by permanent marks placed on the bridge rail or floor, in case of a bridge station; on the main cable or on a secondary tagged cable, in case of a cable station; and on a tape or tagged line stretched across the stream for measurements made from a boat or by wading. In the latter case, if it is not practicable to leave the line in place, the initial point should be so located and marked that the line can be stretched for each discharge measurement in the same position as for previous measurements.

ARTIFICIAL CONTROLS.

Streams, whose beds are changing or which offer no satisfactory section for making discharge measurements, or for collecting records of stage from which discharge may be computed, may require the building of artificial controls for maintaining a constant relation between gage height and discharge and also for improving the channel conditions so that satisfactory measurements can be made (Pl. VI).

In the construction of artificial controls care should be taken to maintain the natural conditions as nearly as possible; that is, they should con-



A. NATURAL CONTROL.



B. ARTIFICIAL CONTROL.

form closely to the natural bed of the stream and should not project into the channel, as such projection will greatly reduce the sensitiveness of the station at low stages and thus reduce the accuracy of the record. Where a reef or bar or gravel or boulders is available it may be possible to prevent scouring and change of channel by grouting with cement. In case of shifting channels in sand or silt, sheet piling can be driven across the section nearly flush with the bottom, which will tend to prevent scour, and over which the natural current may reduce the probability of silting. The effectiveness of artificial controls or of channel improvements will depend upon local conditions, and such changes should only be attempted after a careful consideration of local conditions. Any modifications of a crosssection or alignment of a stream which will change the conditions of equilibrium already established by nature may be expensive to maintain and should always be carefully considered and closely watched.

INSTRUMENTS FOR DETERMINING CLIMATOLOGICAL DATA.

In the study of the hydrology of a given area the engineer will often need to consider the climatological conditions which affect the quantity and distribution of the water supply. In such studies it may be necessary to collect data in regard to:

1. Precipitation in the form of rain.
2. Precipitation in the form of snow.
3. Evaporation.
4. Temperature.
5. Relative humidity.
6. Wind movements.

The methods and instruments of the United States Weather Bureau, representing the best practice for the collection of all climatological data, have been fully described in special bulletins of that bureau, from which they may be obtained upon application.

CHAPTER III.

VELOCITY-AREA STATIONS.

Velocity-area gaging stations are divided, according to the method by which the velocities are measured, into current-meter, float, and slope stations. Current-meter stations are further divided, with respect to the facilities for making the observations, into bridge, cable, boat, and wading stations.

The data necessary for continuous records of stream-flow at velocity-area stations are, first, results of measurements of discharge, and, second, records of mean daily stage. The collection of such data requires four distinct procedures:

1. Selection of a site for the gaging stations,
2. Establishment and maintenance of the station,
3. Measurement of discharge, and
4. Observation of stage.

SELECTION OF SITE.

REQUISITE CONDITIONS.

Conditions that determine the desirability of a site for a velocity-area station comprise, first, conditions that insure good measurements of discharge and stage, second, those that affect the computation of flow at times when measurements of discharge are not made, and, third, those that affect the cost of obtaining the records.

Conditions pertaining to measurements of flow and stage.—The measurement of discharge by current meter requires a fairly smooth bed and a measurable and uniform velocity of current. The velocity of the current should be uniformly distributed throughout the section, which should show no marked eddies, cross currents, or boils, and its mean should not be less than 0.5 foot per second at low stages. Measurements to be made by floats or by determinations of slope require also a straight stretch of channel, 200 to 1,000 feet long, through which the cross-section and velocity are reasonably uniform.

The site should be so selected that the gages for measuring stage may be economically installed and may be readily accessible for reading.

Conditions pertaining to computation of flow.—The essential conditions affecting the computation of flow are permanency of the relation of stage to discharge and the sensitiveness of this relation.

The elevation of the water surface of a stream flowing in an open channel is regulated from point to point by certain features that may conveniently be referred to as control sections. A control section may be a dam or weir, the crest of rapids or abrupt falls, a bar extending across the river, or, where the slope is uniform throughout, a long stretch of the river bed itself. The slope of the water surface above each control section is determined by the height of water at the control section. Computations of daily discharge are based on the assumption that the discharge of a stream for any given stage is unchanged so long as the character of the river at the control section remains unchanged, and that it varies with the stage according to some law. This relation between stage and discharge makes practicable the construction of a rating curve from a few measurements of discharge made at times which cover the range of stage. This rating curve is, therefore, the graphic representation of the formula for computing the discharge over or past the control section, and by its use the flow can be computed from records of stage at times when discharge measurements are not made. Any change in conditions at the control section will modify the relation between stage and discharge and make necessary the construction of a new rating curve; if, however, the conditions are permanent, measurements made in different years will define a curve that may be applied to a record of gage height extending over an indefinite time to obtain estimates of discharge.

A permanent control is, therefore, of prime importance for a gaging station maintained for the determination of daily discharge, as otherwise it is necessary to construct new rating curves after each shift, and if shifting is continuous, as in many streams in the Southwest, one or more discharge measurements a week may be required.

Attention is particularly called to the fact that permanence of flow past the gage is the essential condition, because the records of gage heights and the rating table pertain to the section at the gage and not necessarily to the section in which discharge measurements are made. This involves the requirement that the bed and banks at the control section shall be permanent. The shifting of a bar of sand or gravel in the channel below the gage may make a decided change in the relation between discharge and gage height, even though the cross-section at the point of the measurement remains unchanged. On the other hand, a permanent reef or ledge extending across the stream a short distance below the gage will control the relation between gage height and discharge, even though

the bed at the measuring section or at the gage may change. Stations established under such conditions of control give excellent records.

The relation between stage and discharge may be disturbed by various modifying conditions even when the natural control is permanent, and care should be taken in the selection of a site for a station to avoid those conditions, which may occur in the backwater from a dam as a result of intermittent diversions, or result from the choking of the river with flood water discharged from a tributary below, or from the temporary accumulation of ice, logs, or other drift.

For a given stream the shape and size of the control will govern the magnitude of change in stage resulting from a change in discharge. This relation is referred to as the sensitiveness of the station, and the station should be selected so as to give as large a change in stage as is possible for a given change in discharge. Estimates of flow at non-sensitive stations which have relatively small fluctuations in stage, are liable to large errors on account of lack of refinement in the determination of mean daily stage.

Conditions pertaining to cost of records.—Three principal factors enter into the cost of obtaining stream-flow records—the character of the records, the position and character of the gaging station, and the instruments and equipment to be used.

1. The character of the records will depend on the use for which the data are needed and the length of time that the observations are to be continued.

2. The position and character of the gaging station will depend on the characteristics of the regimen of the stream, the accessibility of the station, the availability of gage readers, and the permanency of the control, which determines the number of discharge measurements necessary for computing daily discharge.

3. The instruments and equipment for collecting the data will depend on the necessity for a recording gage, the availability of structures or equipment by means of which velocity and depth may be measured, and, in the absence of a suitably located bridge, conditions of bank favorable to anchorages and support for a cable.

RECONNAISSANCE.

A gaging station should be established only after a thorough reconnaissance has been made of the section of the river in which the station is to be placed. As the object of this reconnaissance is to find the best site to furnish the desired results, it should be made, if possible, during a low stage of the river and, if feasible, should be supplemented by

an inspection at a high stage. At low stages the bed can be carefully examined, and the minimum velocity can be determined, and a fair estimate of conditions at high stages can also be made. At medium and high stages it is generally impossible to examine the bed or to make any estimate of velocity at low stages.

Careful notes and sketches should describe the conditions at the localities examined, as the position of the station can not be finally chosen until all possible sections of the stream have been inspected. The notes should be complete in all details and should include negative as well as positive information.

In making the reconnaissance consideration should be given to the three requisite conditions that have been described, and the recorded information should include the following subdivisions of these topics:

1. Conditions pertaining to measurements of flow and stage, including (a) the type, dimensions, and location of the gage or gages; (b) the velocity and distribution of the current of water; (c) the bed—whether rough or smooth, permanent or shifting, and (d) the section of river available for determinations of slope when measurements of discharge are to be made by the slope method, estimated length, curvature, slope, obstructions, facilities for measurements of cross-sections, etc.

2. Conditions pertaining to computations of flow, including (a) the location and character of the control section; (b) the proximity of dams or tributaries above or below the section and their probable effects at the station and (c) the banks—shifting or permanent, wooded or clear, high or low, etc.

3. Conditions pertaining to cost of records, including (a) the accessibility of the site; (b) the availability of gage readers and their qualifications; (c) the estimated cost of establishment of the station; (d) the estimated annual cost of maintenance, and (e) the structures available for supporting the engineer in making measurements, or, in the absence of such structures, the span, supports, and anchorages necessary for a cable, with a statement whether or not all flood water passes under the structure or cable.

The selection must be determined largely by the facilities afforded for obtaining an accurate record of stage and for measuring precisely the area of cross-section and the velocity of the current.

In general it has been found economical, in the end, to establish a gaging station where conditions are good, even though the cost of installation may be relatively great, as the cost of operation and maintenance will probably be less and the records will be more satisfactory than at stations where conditions are poorer.

ESTABLISHMENT AND MAINTENANCE OF STATIONS.

The site for the gaging station having been selected, the routine of establishment and maintenance will depend on the equipment necessary, that is, on (1) gages, (2) structures for making measurements, and (3) controls. The character of the equipment and the manner of its installation will in large measure determine the accuracy and cost of the records. Money expended in the initial installation will generally materially reduce the cost of operation and maintenance, and thus reduce the cost of the records.

Gages.—The type of gage to be used will depend on the physical conditions at the site, the availability of a gage reader, the importance of the station, and the number of readings necessary for the proper determination of the mean daily stage. In general the gage or gages, with the necessary bench marks, will be first installed in the manner described on pages 23 to 36.

The determining factor in the use of a staff gage will be the availability of a reliable gage reader, lack of which will render the use of a recording gage necessary, even though other conditions may be favorable for a non-recording gage. The accuracy of the records of stage will depend largely on the ease with which the observations can be made; therefore the gage should be so placed as to be readily accessible, and the convenience and even the comfort of the person reading and caring for the gage should be insured by facilities provided in the vicinity of the gage.

If the gage is not located in the section in which meter measurements are made, an auxiliary gage or, preferably, a reference point should be placed in the measuring section, in order that a standard cross-section may be used for determining the area factor of the discharge.

It should be borne in mind that the rating curve of discharge applies to the cross-section of the river in which the gage is located. Therefore the location of the gage, once decided upon, should not be changed without good reason, as relocation will require the development of a new rating curve. If it is considered necessary or desirable to replace a gage, the new one if installed in the same section should be made to read from the same datum as the old one, unless there is some excellent reason to the contrary. Furthermore, secondary gages should be avoided except where necessary for determining slopes or the areas of cross sections at the measuring section. This precaution is necessary because, for a given change in discharge, the stage will vary differently at different cross-sections because of differences in condition of channel.

Structures for making measurements.—General discussion of structures

for making measurements appears on pages 36 to 41, but two important considerations, the safety of the equipment and the ease with which it can be used, are here mentioned. As the lives of the men who are to make the measurements will depend on the strength of these structures, liberal factors of safety should be employed and the materials used should be durable.

Controls.—As stated on page 45, a permanent control section is one of the fundamental requisites for a satisfactory gaging station. If the site to be used lacks a permanent natural control, an artificial control may be provided by grouting the bed or by building a low weir as described on pages 42 and 43.

Description of station.—A complete description of the gaging station is necessary, covering the following topics:

1. The location referred to the nearest post office, railway station, dwelling, and tributary streams above and below, and if in a public-land State, to the smallest legal subdivision.
2. Date of establishment.
3. Name of person who established the station.
4. Name, post office address, and rate of compensation of observer.
5. Gage or gages and their bench marks.
6. Equipment from which measurements are made.
7. The control section.
8. Channel and other conditions which may affect measurements of discharge or stage.
9. Conditions which may affect estimates.

The description of each station should be accompanied by a general sketch showing the situation of the station with reference to topographic features, the observer's house, roads, towns, tributary streams, dams, and diversions. A detail sketch showing conditions at the gaging section may often be desirable.

THE MEASUREMENT OF DISCHARGE.

The discharge at velocity-area stations is obtained by measuring the area of the cross-section, and the velocity of the moving water. The area of the cross-section is determined by soundings. The velocity of the moving water is measured either directly—by observing the time of passage of a float over a measured course—or indirectly—by noting the revolutions of the wheel of a current meter or by measuring slope and using slope formulas. Discharge measurements are classed in accordance with these three methods of measuring velocity.

In making the measurement by means of a current meter or floats the area of the gaging section (Pl. II B) that is perpendicular to the thread of the current of the stream is divided into partial areas, for each of which the discharge is determined independently by multiplying its mean velocity by its area. The total discharge is the sum of the partial discharges. This computation of partial discharges eliminates the application of results obtained for conditions existing in one part of the channel to parts in which they do not apply.

AREA OF CROSS-SECTION.

The area of cross-section of a stream, the first factor in measuring discharge, depends on the contour of the bed, which is determined by soundings, and on the stage of the river, which is observed on the gage. The methods used in its determination will be the same regardless of the methods used for measuring the velocity. For current-meter stations the area of only the measuring section is required. For float and slope stations the average area throughout the portion of the river used for the observations must be obtained.

Soundings.—Soundings are made either by a graduated rod or by weight and line.

Sounding rods are limited in use to depths of less than 15 feet and are best adapted for use at wading and boat stations, where the depths and velocities are relatively small, but may occasionally be used at bridge stations where the bridge is not high above the water.

The weight and line are used in making soundings in water of greater depth than 15 feet, and from bridges or cables which are high above the water. Soundings from a bridge or cable with weight and line are most readily taken as follows: Lower the weight and line until the weight rests on the bed of the river directly underneath the measuring point. With the line taut, mark a point on it opposite a fixed point on the bridge or car; then raise the weight until it just touches the surface of the water and measure the length of the sounding line that passes the fixed point mentioned above. The depth is most readily measured by placing the end of a linen or metallic tape opposite the fixed starting point on the sounding line, grasping both the line and the tape in the hands, and drawing up the line and tape without permitting them to slip on each other until the weight rests on the surface of the water. The length of line thus drawn up, representing the depth of the water, can then be read directly from the tape. This measurement may usually be made by one person even when the depth is 10 to 12 feet. Where meter measurements are made from a bridge or cable, the meter

cable, with meter and lead attached, is generally used for sounding if the depths and velocities are small but care must be taken that the meter is not damaged.

The greatest and most common errors in measurements of discharge are caused by erroneous soundings. Errors in soundings by weight and line are due to the weight being carried downstream, so that it does not fall immediately below a point perpendicularly beneath the measuring point, or, sometimes, to the bowing of the line. Both these causes make the soundings too great. Errors in soundings with rods are due to the rod not being perpendicular, to the water rising on the rod, and to the rod sinking in the bed.

Standard cross-section.—For gaging stations on streams whose beds are permanent or nearly so, a standard cross-section should be constructed from careful soundings. This cross-section should be referred to the zero of the gage, so that the depths for any stage can be found by adding the gage height to the depth below the zero of the gage. Standard cross-sections have three uses: (1) They serve as checks on future soundings; (2) they indicate changes which may occur in the bed of the stream; and (3) they may be used in determining the area for measurements taken at times when it is impossible to make soundings on account of high water or other conditions.

VELOCITY.

Velocity of flowing water, indicated by V , is generally expressed in feet per second, and depends principally upon (1) surface slope of the stream, (2) roughness of the bed, and (3) hydraulic radius.

The surface slope is the fall divided by the distance in which that fall takes place, and is represented by s . It depends on the slope of the bed, the channel conditions, and the stage. It is greater for a rising than for a falling stage.

The coefficient of roughness of the bed varies for different streams and stages of the water and is expressed by n .

The hydraulic radius or hydraulic mean depth is the area of the cross-section divided by the wetted perimeter. It is usually represented by R , and can be determined for all stages from a single complete measurement of permanent cross-section.

The mean velocity of a stream is the average rate of motion of all the filaments of water in the cross-section. It is not a directly measurable quantity, being usually found by dividing the total discharge by the area of the cross-section at a given stage. Its use is generally limited to purposes of comparison.

LAWS GOVERNING VELOCITY.

A systematic study of the flow of streams shows that mean velocity is in general a function of the stage and that the distribution of velocity through the cross-section follows well-defined laws which pertain to all streams flowing in open channels and which are in the main independent




FIG. 14.—Distribution of Velocity in Open Channel, Zumbro River, Zumbro Falls, Minn.

of the stage (figs. 14, 15, 16). These laws make possible the determination of the velocity factor of the discharge measurement by comparatively few properly distributed observations of velocity. Upon them also depend the methods for determining the regimen of the stream.

These laws have been studied both mathematically and graphically

by means of vertical velocity-curves (figs. 15 and 16) which show graphically the distribution in a vertical line of the horizontal velocities of the filaments of water from the surface to the bottom of the stream.

Vertical velocity-curve.—A vertical velocity-curve is determined by a series of velocity observations taken at regular intervals in a vertical




FIG. 15.—Groups of Vertical Velocity-Curves, Chenango River at Binghamton, N. Y.

from the surface to the bottom of the stream, usually from 0.5 to 1 foot apart. The results of these observations, when plotted with the velocities as abscissas and the depths as ordinates, define the curve.

Studies by Humphreys and Abbot^a on the Mississippi, by General Ellis^b on the Connecticut, and by the United States Geological Survey^c on many streams under various conditions of depth, velocity, and

^a Physics and Hydraulics of the Mississippi, 1851, p. 234.

^b Report of the Chief of Engineers, U. S. Army, 1878, Part I, p. 259.

^c Water-Supply and Irrigation Papers Nos. 95, 109, 187, and others.

roughness of bed, show that these vertical velocity-curves have approximately the form of the parabola whose axis, coinciding with the filament of maximum velocity, is parallel with the surface and is in general situated between the surface and one-third of the depth of the water. From the maximum the velocity decreases gradually upward to the surface and downward nearly to the bottom, where it changes more rapidly on account of the friction on the bed. As the depth and velocity increase, the curve approaches a vertical line as its limiting position.

Distribution of velocity in the vertical.—If, as stated above, the velocities in a vertical line vary as the ordinates of a parabola, it may be shown mathematically that (1) a filament of water which has the same velocity as the mean of the velocities in that vertical occurs at a point between .5 and .7 of the depth measured from the surface of the stream, and (2) that the mean velocity equals the mean of the velocities occurring at .2114 and .7886 of the depth.

The demonstration^a of the location of the filament of mean velocity is based on the theory of mean values, using the fundamental equation,

$$y = ad + d \sqrt{\frac{1}{3}(a^3 + b^3)},$$

in which d equals the total depth of water; a , the depth of maximum velocity below the surface; b , the unitary complement of a ; y , the depth of the thread of mean velocity.

By assigning values to a between 0 and $\frac{1}{3}d$ and substituting them with simultaneous values of b in the above equation, there results the following table, showing the depth of the mean ordinate for parabolic curves with various positions of depth to the maximum ordinates.

| <i>Depth of maximum ordinate.</i> | <i>Depth of mean ordinate.</i> |
|---------------------------------------|------------------------------------|
| When $a = 0$ | $y = 0.58d$ |
| $a = 0.10d$ | $y = 0.59d$ |
| $a = 0.15d$ | $y = 0.60d$ |
| $a = 0.20d$ | $y = 0.62d$ |
| $a = 0.25d$ | $y = 0.63d$ |
| $a = 0.30d$ | $y = 0.65d$ |
| $a = 0.33d$ | $y = 0.67d$ |

The maximum ordinate in streams that are neither very shallow nor very deep usually lies at or above one-third depth (see table, pp. 56, 57).

^a Engineering News, Vol. LV, p. 47.

If it lies above one-fourth depth, the ordinate at 0.6 depth is very closely the mean ordinate. If the stream is very deep the maximum thread lies generally at a greater proportional depth, and the thread of mean velocity therefore lies at a greater depth. If a stream is shallow and has in addition a rough bed, the frictional effect on the flow is so large that the vertical velocity-curve is no longer parabolic near the bottom and the thread of mean velocity may be near mid-depth.

A study of vertical velocity-curves shows that the mean velocity in the vertical equals from 85 to 95 per cent of the surface velocity, and it also equals one-fourth the sum of the velocity near the surface plus twice the velocity at mid-depth plus the velocity near the bottom.

That these properties generally hold in nature has been proved by hundreds of vertical velocity-curves made on a large number of streams having a wide range in conditions of depth, character of beds, and magnitude of velocity. Fig. 14 shows the form of a number of typical vertical velocity-curves and the table on pages 56-57 gives a summary of results of a large number of vertical velocity-curves.

A study of these measurements, together with many others which are not available for publication, shows the general applicability in nature of the foregoing laws upon which depend the common methods of measuring discharge by floats and current meters.

METHODS OF DETERMINING MEAN VELOCITY IN A VERTICAL.

In the application of the laws of the distribution of velocity there have been developed the following methods of determining mean velocity in the vertical: (1) Vertical velocity-curves; (2) .6 depth; (3) surface; (4) .2-.8 depth; (5) three-point; (6) integration.

Measurements of velocity are therefore generally made by one of the above-mentioned methods, each of which has its special advantages and limitations. Their essential use is to determine the mean horizontal velocity in a vertical line and not features of measurement or computation that involve other factors.

As a discharge measurement contains a large number of velocity determinations the error introduced in the result by an individual erroneous measurement of velocity is generally inappreciable.

The application of the methods and the relative accuracy obtained by each, as determined by a comparative study of all available vertical velocity-curves, are discussed in the following paragraphs:

Vertical velocity-curve method.—By the vertical velocity-curve method measurements of horizontal velocity are usually made just under the

| | | | | | | | | | |
|----------------------------------|--------------------------|-----|-----------|-----------|----|------|----|-------|------|
| Susquehanna | McCall Ferry, Pa. | 73 | 3.3-30.0 | 1.21-5.80 | 68 | 94 | 92 | 1.07 | |
| Susquehanna | McCall Ferry, Pa. | 68 | 5.0-36.0 | 1.40-9.70 | 73 | 97 | 90 | | |
| Susquehanna | Harrisburg, Pa. | 20 | 3.2-8.0 | 1.52-2.71 | 61 | 1.01 | 85 | 1.08 | |
| Susquehanna | Binghamton, N. Y. | 36 | 2.5-8.1 | 80-4.86 | 61 | 99 | | 1.06 | |
| Chenango | Binghamton, N. Y. | 34 | 2.1-7.4 | 46-3.38 | 62 | 1.02 | 83 | | |
| Catskill Creek | South Cairo, N. Y. | 47 | 2.1-7.0 | 27-3.91 | 58 | 1.02 | 82 | | |
| Delaware (E. Br.) | Hancock, N. Y. | 6 | 2.1-4.8 | 75-4.12 | 59 | 1.02 | 83 | | |
| Esopus Creek | Kingston, N. Y. | 12 | 1.7-4.2 | 1 67-4.45 | 58 | 1.02 | 88 | | |
| Esopus Creek | Oliverbridge, N. Y. | 53 | 0.9-14.0 | 65-5.04 | 62 | 1.01 | 69 | | |
| Fishkill Creek | Glenham, N. Y. | 68 | 1.0-5.0 | 42-7.62 | 58 | 1.04 | 79 | | |
| Housatonic | Gaylordsville, Conn. | 22 | 2.1-5.0 | 26-1.75 | 59 | 1.01 | 83 | | |
| Rondout Creek | Rosendale, N. Y. | 36 | 1.1-6.2 | 67-3.66 | 58 | 1.01 | 84 | | |
| Schoharie Creek | Prattsville, N. Y. | 21 | 4.4-8.2 | 35-2.55 | 61 | 1.01 | 80 | | |
| Wallkill | Dover Plains, N. Y. | 11 | 1.1-6.6 | 52-3.20 | 58 | 1.01 | 80 | | |
| Tenmile | Newpaltz, N. Y. | 33 | 1.8-7.3 | 24-2.15 | 61 | 99 | 88 | | |
| Wappinger Creek | Newpaltz, N. Y. | 52 | 3.3-17.3 | 18-4.72 | 64 | 96 | 85 | | |
| Wappinger Creek | Wappinger Falls, N. Y. | 17 | 2.5-4.7 | 58-2.11 | 58 | 1.03 | 78 | | |
| Appomattox | Mattoax, Va. | 8 | 2.5-4.4 | 92-2.30 | 62 | 1.01 | 81 | 1.11 | |
| James | Cartersville, Va. | 6 | 3.0-4.4 | 1 82-2.37 | 60 | 1.01 | 88 | 1.06 | |
| Roanoke | Roanoke, Va. | 8 | 1.8-3.3 | 87-1.96 | 61 | 99 | 81 | 1.01 | |
| Staunton | Randolph, Va. | 42 | 2.0-6.0 | 1 35-3.11 | 66 | 96 | 95 | 1.12 | |
| Dan | Madison, N. C. | 20 | 3.5-9.0 | 73-3.00 | 62 | 99 | 96 | 1.01 | |
| Dan | South Boston, Va. | 13 | 1.7-2.5 | 90-2.41 | 64 | 1.02 | 90 | 1.09 | |
| Reddie | North Wilkesboro, N. C. | 33 | 2.7-6.4 | 1 62-2.01 | 58 | 1.02 | 83 | 1.12 | |
| Yadkin | North Wilkesboro, N. C. | 10 | 3.1-11.3 | 1 20-3.16 | 66 | 1.06 | 91 | 1.06 | |
| Catawba | Salisbury, N. C. | 39 | 1.9-5.0 | 96-3.23 | 59 | 1.02 | 81 | 1.04 | |
| Catawba | Morgantown, N. C. | 2 | 6.3-7.0 | 74-2.84 | 61 | 1.00 | 88 | 1.08 | |
| Catawba | Mount Holly, N. C. | 2 | 3.5-7.0 | 49-74 | 58 | 1.01 | 80 | 1.05 | |
| Wateree | Belmont, N. C. | 1 | 12.3-17.7 | 1 54 | 59 | 1.01 | 90 | 1.13 | |
| Broad | Camden, S. C. | 4 | 5.0-8.9 | 1 33-1.83 | 58 | 96 | 89 | 1.22 | |
| Saluda | Alston, S. C. | 4 | 3.0-8.5 | 2 79-4.00 | 65 | 97 | 82 | 1.03 | |
| Watauga | Waterloo, S. C. | 3 | 2.6-5.3 | 1 76-2.01 | 62 | 98 | 82 | 1.07 | |
| South Fork Holston | Elizabeth, Tenn. | 10 | 1.9-4.1 | 34-1.01 | 61 | 1.02 | 80 | 1.05 | |
| Nolichucky | Bluff City, Tenn. | 13 | 1.6-5.1 | 1 08-6.77 | 62 | 1.02 | 80 | 1.02 | |
| French Broad | Greeneville, Tenn. | 22 | 4.2-8.0 | 49-2.69 | 59 | 1.02 | 86 | 1.07 | |
| Pigeon | Oldtown, Tenn. | 9 | 4.4-11.6 | 53-2.18 | 62 | 99 | 91 | 1.15 | |
| Tuckasegee | Newport, Tenn. | 4 | 3.5-8.6 | 82-1.14 | 61 | 99 | 93 | 1.09 | |
| Little Tennessee | Bryson City, N. C. | 36 | 2.7-6.0 | 50-3.39 | 64 | 1.03 | 83 | 1.06 | |
| Mean of 910 curves | Judson, N. C. | 11 | 36.0 | 3 84-7.45 | 59 | 1.03 | 85 | 1.07 | |
| Highest | | | 1.1 | 9.70 | 73 | 1.04 | 95 | 1.22 | |
| Lowest | | | | 0.18 | 58 | 94 | 78 | 96 | |
| Shallow streams with rough beds. | | | | | | | | | |
| St. Mary | Dam Site, Mont. | 24 | 1.8-4.2 | 2 60-6.36 | 60 | 1.00 | 93 | 1.01 | |
| Swiftcurrent Creek | Babb, Mont. | 16 | 1.6-3.2 | 3 28-6.81 | 57 | 1.03 | 96 | 1.004 | |
| South Fork Shoshone | Marquette, Wyo. | 20 | 1.8-3.6 | 3 61-6.79 | 58 | 0 | 93 | 1.016 | |
| Ana | Sumner Lake, Oreg. | 6 | 1.8-2.4 | 1 83-3.37 | 63 | 10 | 92 | 1.00 | |
| Tieton | North Yakima, Wash. | 14 | 1.8-4.5 | 4 42-6.04 | 56 | 0 | 96 | 1.00 | 98 |
| Wallawa | Wallawa, Oreg. | 4 | 2.2-2.9 | 4 16-4.93 | 58 | 0 | 94 | 1.004 | |
| Kruganapa | Salmon Lake, Alaska | 108 | 1.6-3.6 | 1 43-4.70 | 64 | 23 | 91 | 1.004 | 99 |
| Small streams | Seward Peninsula, Alaska | 27 | 1.7-2.5 | 2 15-3.47 | 61 | 14 | 93 | 1.004 | 1 00 |
| Mean of 219 curves | | | 4.5 | 8.04 | 60 | 7 | 92 | 1.005 | 99 |
| Highest | | | 1.6 | 1.43 | 64 | 23 | 96 | 1.016 | |
| Lowest | | | | | 56 | 0 | 91 | 1.00 | |

surface, at .5 foot below the surface, and at each fifth to each tenth of the depth from the surface to the bed of the stream. These measured velocities, when plotted, define for each such observation point the vertical velocity-curve from which the mean velocity in that vertical is determined.

In computing the mean velocity from vertical velocity-curve measurements, the velocity observations are plotted on cross-section paper with depths as ordinates and velocities as abscissas. A mean curve (fig. 16) is drawn through these points and extended to the surface and to the bed of the stream. The mean velocity is the mean abscissa of this curve and may be determined in three ways as follows:

(1) Determine the area bounded by the curve and its axis with the planimeter and divide by the depth.

(2) Divide the area into any number of sections of equal depth, usually ten, and take the mean of the velocities at mid-point of each of these sections as the mean velocity.

(3) Divide the area into sections of convenient depth which will be equal except for the bottom section, which may have an odd depth. Take the mean of the middle ordinates of each section for the mean velocity. In case the bottom section is an odd depth, multiply its mean velocity by the ratio of its depth to that of the other sections, and add the product to the sum of the middle ordinates of the other sections and divide by the




FIG. 16.—Typical Vertical Velocity-curve.

number of sections, thus taking into consideration the proportionate size of the odd section.

The advantage of the third method over the second is that it enables the selection of sections corresponding in depth to a given number of divisions of the cross-section paper on which the curve is plotted. The determination of middle velocity is thus rendered much simpler than when the sections do not correspond to the divisions of the cross-section paper.

For purposes of study vertical velocity-curves are sometimes plotted with per cent of mean velocity as abscissas and corresponding depths expressed as percentages of the total depth as ordinates.

The vertical velocity-curve method is valuable as a basis for comparison of all other methods, for determining coefficients to be used in reducing values obtained by other methods to the true value, for use under new and unusual conditions of flow, and for measurements under ice. The method is not, however, in general use for making observations of velocity for routine discharge measurements, because the increased accuracy thereby obtainable is frequently overbalanced by errors arising from changes in stage of the stream during the longer time required for the measurement.

In making observations of velocity for the construction of vertical velocity-curves, velocities should also be measured at .2, .6, and .8 depth, in order that the mean velocity determined by methods in which these depths are used can be directly compared with that determined by the vertical velocity-curve method.

Vertical velocity-curves should be constructed for all stations at different stages in order to determine whether coefficients should be applied to the results obtained by the other point methods. Such application of coefficients should be made, however, only on unquestionable evidence furnished by a large number of vertical velocity-curves. The coefficient deduced from a single curve is rarely applicable to the entire cross-section of the stream.

The coefficients as determined by vertical velocity-curves for reducing the velocity by either of the other point methods to mean velocity may be plotted with stage as the other ordinate and thus determine a curve which may define the coefficient to be used at any stage.

The .6 depth method.—In practical measurement of stream discharge it is necessary to determine the horizontal velocity in a large number of verticals. Therefore, a method must be used which requires not more than three velocity observations in each vertical. If one point is used it is desirable that it be in such position that the use of a coefficient is not necessary to determine the mean velocity. The foregoing theory

shows that such a point lies approximately at .6 depth of the stream. The preceding table shows that the thread of mean velocity lies between 56 per cent and 73 per cent of the depth, with an average of 61 per cent. The error resulting from the use of .6 depth is very small, ranging from —6 per cent to +4 per cent, with a mean of 0 per cent. Therefore, in the .6 depth method it is assumed that the velocity at .6 depth is the mean velocity in the vertical and the meter is held at that point in this method.

Although this method is intended to be used without coefficients it may be found by vertical velocity-curve measurements that a coefficient is necessary in some instances to reduce the observed velocities to the mean. The method is applicable over a wide range of conditions, is easy of execution, and is reasonably accurate for normal flow in the straight reaches of all streams except very deep and very shallow ones.

The surface method.—The surface method is used in the measurement of velocities of swift streams, especially at times of freshet, when it is impracticable to sink the meter much below the surface. Therefore the observation of velocity is made at a point near the surface, but far enough below to eliminate any disturbance from wind or waves. The point of observation in this method should be from .5 foot to 1 foot below the surface, its location depending on the depth of the stream. The measured velocity must, however, be multiplied by a coefficient to reduce it to the mean. This coefficient, as shown in the preceding table, varies between 78 and 98 per cent, depending upon the depth of the stream and the magnitude of the velocity. For average streams a coefficient of about 90 per cent will generally give fairly accurate results.

The two-point method.—The two-point method is used on streams in which the location of the point of mean velocity is uncertain, or when greater accuracy is desired than can be obtained by the .6 depth method. As noted in the foregoing theory, the mean of the velocities at .2 and .8 depth gives nearly the mean velocity in the vertical. The preceding table shows that this theory holds very closely in nature. Therefore in this method the meter is held at .2 and .8 depth of each vertical.

Observations of velocity near the surface and near the bottom of the stream have in the past been used in the two-point method. Both the theory and the tables show that .2 and .8 depth should be used. This method is recommended for general stream-gaging.

The three-point method.—The three-point method approaches more nearly the vertical velocity-curve and is used for obtaining greater accuracy than is possible by the one- and two-point methods. In this method the meter should be held at .2, .6, and .8 depth. The mean velocity is then obtained by dividing by 4 the sum of the velocities measured at .2 and .8 depth plus 2 times that at .6 depth.

In this method the observations have in the past been frequently taken at top, bottom, and mid-depth, but both theory and experience show that .2, .6, and .8 depth are the proper points for such observations.

The integration method.—The integration method is used both for obtaining the mean velocity in the vertical and also the mean velocity in the entire cross-section of the stream.

In determining the mean velocity in the vertical the meter is moved at a uniform speed from the surface of the water to the bed of the stream and return, and the revolutions and time are observed. The meter thus passes successively through all velocities in that vertical and the resulting observations determine the mean in that vertical. The method is valuable for checking other methods, but generally requires the service of at least one more man to observe time, as the engineer must be occupied with the movements of the meter. It is consequently not so commonly used as the point methods. The Price meter is not suited to observations by this method, as the vertical motion of the meter causes the wheel to revolve. The Haskell and Fteley meters, on the other hand, may be moved vertically with little or no effect on the wheel.

In determining the mean for the entire section the meter is moved with uniform speed throughout the section, usually in a zigzag path extending from surface to bottom and from side to side of the section.

CURRENT-METER MEASUREMENTS.

PROCEDURE.

In making a current-meter measurement the cross-section (Pl. II, B) is divided into partial areas, varying in width from 2 to 20 feet, depending on the size of the stream. These partial areas are bounded by perpendiculars terminating at points in the surface known as measuring points, because they indicate where the observations of depth and velocity are taken. They should be so spaced as to show any irregularities either in the cross-section or the velocity. When measurements are made at bridge or cable stations, the measuring points should be permanently marked on the bridge rail or floor, or on the cable, and used for successive measurements of discharge. When measurements

are made at boat and wading stations the points will be indicated by the graduations on a tape or tagged line, which is generally stretched at the time of each measurement.

The procedure in the measurement will vary somewhat, depending on the sounding appliance. If the meter and cord are used for sounding, observations of depth and velocity will be made at each measuring point successively across the stream. If other sounding apparatus is used, soundings will be made at all measuring points prior to taking the velocities.

In making velocity observations, one of the methods described on pages 55-61 should be used, the method chosen depending upon the conditions at the station. Care must be taken to place the center of the meter wheel at the points called for by the method. This is best accomplished by measuring the required depth on the meter line with the wheel in the surface of the water, and then lowering the meter into position. Special attention is called to the requirement, both in sounding and in placing the meter in position for observing velocity, that a tagged line should not be used for measuring depth. Such distances should be determined by means of a tape line, as indicated on page 50. In making the observations a stop-watch is desirable but not indispensable. In general, time should be noted at the click of the receiver, or at the start or finish of the buzz. The time is then observed for a given number of revolutions. The number will depend on the velocity and should be sufficient to make the time interval at least 30 seconds, as shown on the sheet of current meter notes given on pages 66 and 67. This method is preferable to observing the number of revolutions for a given time as it eliminates the error due to fractional revolutions. With a stop-watch time can be observed to half or fifth seconds.

If the velocity of the current makes other than a right angle with the measuring section the deviation from the right angle must be observed and a coefficient applied to reduce the velocity to the normal. This coefficient can usually be applied to the final completed discharge. If, however, the angle varies throughout the cross-section, it is necessary to apply appropriate coefficients to the various observed velocities. The angle can readily be determined by holding the meter just below the surface of the water and placing the notebook perpendicular to the cross-section of the stream and drawing a line parallel to the meter. This line should be divided into ten arbitrary divisions and projected upon a line normal to the gaging section. The length of this projection will be the coefficient to be used.

If the current-meter measurement of discharge is made at a regular

gaging station established for obtaining a record of discharge, a certain routine should be followed, consisting of the steps indicated below in consecutive order.

1. Check gage datum if facilities are available.
2. Set up meter, using precautions described on page 18.
3. Read the gage.
4. Make the observations necessary for the measurement of discharge by one of the methods described on preceding pages.
5. Read the gage. (If the stream is fluctuating notably the gage should be read frequently and at regular intervals during the measurement.)
6. Check the notes to make certain that all records have been made.
7. Dismantle and pack meter, using precautions described on page 18.
8. Be careful to note under "remarks" changes in stage, backwater, wind, and other conditions knowledge of which may be of future value.
9. If possible, see the gage reader and his record, and call his attention to any lack of interest or apparent discrepancies in his work.

Each of the above observations is essential to the reliability of the record at a station. On each visit of the engineer the stage of the river should also be determined by observing the distance to the surface of the water from a reference point, as a check on the gage record.

Either temporary or permanent changes in channel conditions which affect the rating of the station should be noted and recorded in as great detail as possible. Such conditions include changes in channel in the vicinity of the station, the building of dams below, the formation of jams of logs or drift, and the extent, character, and thickness of ice. Gage readers should receive written instructions in regard to reports to be made concerning such conditions; otherwise they may make no record of the time or extent of such changes.

If the engineer can reach a gaging station in time of flood, he should as a rule remain and make measurements of discharge at each foot of stage as the river rises or falls. Observation of a single freshet may thus enable him, with a minimum expenditure, to rate the station for practically all except low stages.

In addition to the general procedure described above, special precautions and methods are necessary in connection with low water and wading measurements, high-water measurements, measurements of ice-covered streams, and measurements in artificial channels, as described on pages 69 to 75.

COMPUTATIONS.

The computations of current-meter measurements are usually made to determine: (a) the total area of cross-section; (b) the mean velocity, and (c) the total discharge of the stream. The observed data from which these computations are made consist of (a) soundings at known intervals across the stream, (b) the velocity determinations in the vertical at each sounding point, and (c) the distance between the points of measurement (see table, pp. 66 and 67).

The mean velocity, area, and discharge are computed independently for each partial area included between perpendiculars drawn from successive measuring points. The total discharge is the sum of the partial discharges thus computed. The computation of the partial discharges eliminates errors which would arise from the distribution of conditions existing in one part of the cross-section to parts in which they do not apply. The mean velocity is determined by dividing the total discharge by the total area of the cross-section.

The formulas used in connection with computations of discharge may, in general, be classed as rectilinear and curvilinear—depending on the assumption that the bed of the stream and the horizontal velocity-curve are made up of straight lines or of curves between the measuring points. A comparison of the computation of discharge measurements by various formulas has been prepared by J. C. Stevens, Member Am. Soc. C. E.^a In this discussion it is shown that the following rectilinear formula gives the most accurate results and is readily used:

$$D = l_1 \left(\frac{d_0 + d_1}{2} \right) \left(\frac{v_0 + v_1}{2} \right) + l_2 \left(\frac{d_1 + d_2}{2} \right) \left(\frac{v_1 + v_2}{2} \right) + \dots + l_n \left(\frac{d_{n-1} + d_n}{2} \right) \left(\frac{v_{n-1} + v_n}{2} \right)$$

In this formula, $d_0, d_1, d_2, \dots, d_n$ and $v_0, v_1, v_2, \dots, v_n$ are the depths and velocities at the respective measuring points, $a_0, a_1, a_2, \dots, a_n$, which are spaced at the distances $l_1, l_2, l_3, \dots, l_n$ (fig. 17). The area between the perpendiculars drawn from any two successive measuring points is equal to the mean of the depths at such points multiplied by the distance between them. Similarly, the mean velocity for the area between the two perpendiculars is equal to the mean of the velocities observed at the two perpendiculars. The product of this area by its mean velocity gives the discharge for the partial area included between the two perpendiculars. The sum of these partial areas and discharges gives the total area and total discharge. The tables on

^a Engineering News, June 25, 1908.

pages 66 and 67 show the field notes and computations for a typical current-meter measurement.

The velocities at the respective observation points, as shown in column 6, are determined from the current meter rating table, and the mean velocity in the verticals is the mean of the velocities taken at the respective measuring points. In computing the measurement, it is not usually warranted to carry the velocity computations to more than two decimal places and the partial areas and discharges to more than one decimal place.




FIG. 17.—Cross-section of Stream to Illustrate Discharge Measurement Computation.

LOW-WATER AND WADING MEASUREMENTS.

At low stages of a river when the velocity is small it is advisable to find a section near by in which conditions of channel are suitable for a discharge measurement and a meter measurement may be made by wading (Pl. V, B). Low-water measurements should preferably be made by the .2-.8 depth method, except where the depth is less than 2 feet, when the .6 depth method should be used. Meters hung on rods are best adapted for use in measurements by wading.

In making the measurements a graduated line is stretched across the stream to mark the points of measurement. For this purpose a steel or metallic tape may be used. If, however, the stream is wide, an oil-silk fish line or Barbour's Irish flax salmon thread, conveniently graduated, is more satisfactory as it offers less resistance to wind. When the steel tape is not used special care must be taken to check graduations to eliminate the possibility of errors due to stretching or shrinking of the line.

The engineer making velocity observations should stand below the graduated line and preferably to one side of the meter, in order not to disturb the current of the water flowing past the meter. Three-eighths-

Typical current meter notes *Boise River, Dowling, Idaho. March 28, 1914.*

Date March 28, 1914 No. of Meas. 35
Boise River at Dowling, State of Idaho
 Width 250 Area 827 Mean Vel. 3.31 Cor. M. G. H. 4.56
 Party A. B. Purton Disch. 2,740

Staff gage, checked with level and found No level available

Chain length checked with steel tape, 12-lb. pull, found _____ ft.

" " changed to _____ ft. at _____ o'clock. Correct length _____ ft.

" " corrected on basis of level to _____ ft. at _____ o'clock.

| Gage | Time | Station | Meas. began | ended |
|-------------|-------------------|------------|---|----------------|
| <u>4.57</u> | <u>8:00 A.M.</u> | <u>33</u> | <u>8 A.M.</u> | <u>10 A.M.</u> |
| <u>4.56</u> | <u>9:00 A.M.</u> | <u>160</u> | Meter No. <u>898 (S.P. head)</u> | |
| <u>4.55</u> | <u>10:00 A.M.</u> | <u>283</u> | Date rated <u>Aug. 12, 1912</u> | |
| | | | Method of meas. <u>2-8 depth</u> | |
| | | | No. meas. sec's <u>18</u> Coef. <u>---</u> | |
| | | | Av. width sec. <u>15</u> Av. depth <u>3.3</u> | |

Weighted mean G. Ht. 4.56 ft.

Correct " " " 4.56 ft.

G. Ht. change (rate per hr.) .01

_____ % error by _____ rating table.

Meas. from cable, ~~bridge, boat, wading~~. Meas. at 75 ft. above, below gage.

~~It is~~ at regular section ~~note location~~ and conditions Good

Area from soundings (date) 3/28/14

Method of suspension Wire Stay wire No Approx. dist. to W. S. 8'

Arrangement of weights and meter; top hole _____; middle hole 1 lb.; bottom hole 20

Gage inspected, found Solid Cable inspected, found O.K.

Distance apart of measuring points verified with steel tape and found _____

Wind Light upstr., downstr., across: Angle of current +

Observer seen and book inspected Yes

Examine station locality and report any abnormal conditions which might change relation of G. Ht. to disch., e. g., change of control; ice or debris on control; back-water from; condition of station equipment Conditions apparently normal and results should be good

Sheet No. 1 of 2 sheets.

~~If insufficient space, use back of sheet.~~

Typical current meter notes Boise River, Dowling, Idaho. March 28, 1914
(continued).

| Dist. from initial point | Depth | Depth of ob- servat. | Time in sec- onds | Rev- olu- tions | VELOCITY | | | Area | Mean Depth | Width | Discharge |
|-----------------------------------|-------|----------------------------|-------------------------|-----------------------|-------------|--------------------------|-------------------------|------|---------------|-------|-----------|
| | | | | | At point | Mean in ver- tical | Mean in sec- tion | | | | |
| E.W. 3.3 | 0 | — | — | — | — | 0 | | | | | |
| | | | | | | | 1.35 | 15.0 | 1.25 | 12 | 20.2 |
| 45 | 2.5 | .5 | 49.0 | 70 | 3.18 | 2.70 | | | | | |
| | | 2.0 | 50.0 | 50 | 2.23 | | 2.96 | 43.5 | 2.9 | 15 | 128.8 |
| 60 | 3.3 | .65 | 49.8 | 90 | 4.03 | 3.23 | | | | | |
| | | 2.65 | 55.0 | 60 | 2.43 | | 3.38 | 51.8 | 3.45 | 15 | 175.1 |
| 75 | 3.6 | .7 | 52.8 | 100 | 4.22 | 3.53 | | | | | |
| | | 2.8 | 47.0 | 60 | 2.84 | | 3.58 | 53.2 | 3.55 | 15 | 190.5 |
| 90 | 3.5 | .7 | 52.6 | 100 | 4.23 | 3.62 | | | | | |
| | | 2.9 | 52.0 | 70 | 3.00 | | 3.66 | 53.2 | 3.55 | 15 | 194.7 |
| 105 | 3.6 | .7 | 51.4 | 100 | 4.33 | 3.70 | | | | | |
| | | 2.9 | 50.8 | 70 | 3.07 | | 3.72 | 55.5 | 3.7 | 15 | 206.5 |
| 120 | 3.8 | .75 | 54.5 | 100 | 4.08 | 3.74 | | | | | |
| | | 3.05 | 52.2 | 80 | 3.41 | | 3.64 | 56.2 | 3.75 | 15 | 204.6 |
| 135 | 3.7 | .75 | 55.2 | 100 | 4.04 | 3.54 | | | | | |
| | | 2.95 | 51.4 | 70 | 3.04 | | 3.58 | 54.8 | 3.65 | 15 | 196.2 |
| 240 | 3.2 | .65 | 66.0 | 100 | 3.38 | 2.86 | | | | | |
| | | 2.55 | 47.6 | 50 | 2.35 | | 2.74 | 45.0 | 3.0 | 15 | 123.3 |
| 255 | 2.8 | .55 | 56.8 | 80 | 3.13 | 2.62 | | | | | |
| | | 2.25 | 53.0 | 50 | 2.11 | | 2.36 | 36.0 | 2.4 | 15 | 85.0 |
| 270 | 2.0 | 1.2 | 53.0 | 50 | 2.11 | 2.11 | | | | | |
| | | | | | | | 1.06 | 13.0 | 1.0 | 13 | 13.8 |
| E.W. 283 | 0 | — | — | — | — | 0 | | | | | |
| Totals | | | | | | | 826.8 | | | | 2,738.9 |

inch iron rods, 3 or 4 feet long and having a slit in the top, are convenient for supporting the tape.

If the water is shallow or accurate determinations of small flows are desired, it may be necessary to instal sharp-crested weirs to confine the flow to a small channel in which depth and velocity will be measurable.

When convenient the soundings across the stream may be made before the observations of velocity. In making the soundings a thin, flat, graduated wooden rod should be used on which the water will not pile up, as in low-water measurements sounding errors may be relatively large. The round rods on the meter are not generally adapted to soundings. Measurements can not be made by wading if the product of depth times velocity is greater than 8.

The stage of zero flow should be determined if possible for each gaging station. This stage will be the elevation of the lowest point of the control section and should generally be determined by a level. Its great value arises in determining the position of the lower end of the station rating curve for use in estimating discharges for stages below the lowest current-meter measurement of discharge.

HIGH-WATER MEASUREMENTS.

Measurements made at high stages generally consist of observations of surface velocity only. Areas must be computed from a standard section or from soundings made at a lower stage. Under these conditions extra precautions must be taken to secure data from which a reliable estimate of the flow can be made. The great velocity and the presence of drift or of cakes of ice may render good meter measurement practically impossible. Meter observations 10 to 30 seconds long may, however, frequently be obtained when there is considerable drift, but great care must be exercised that the meter is not damaged. If a weight of more than 30 pounds is required to submerge the meter, a secondary line must be used in conjunction with the insulated cable for supporting the meter, and a stay line will often greatly assist in holding the meter in position.

When there is much drift it is generally advisable to use the float method, the drift serving as floats. Or it may be practicable to determine the slope of the river for a considerable distance and compute the discharge by means of the slope formula. If a level is not at hand marks may be made by which the slope may be determined at some future visit. When possible two of these methods may be used and a check thus obtained on the work.

When it is impossible to obtain flood measurements the discharge

may be computed as the product of the area and mean velocity, determined by extensions of the area and mean velocity curves. In such computations the area above the level of the flood plain, if any, should include only the section above the ordinary channel or channels of the stream, as the mean velocity curve usually applies only to this channel and not to the overflow channel. The discharge on the flood plain will generally be a comparatively small part of the total flow and may usually be estimated with such accuracy that the error introduced by it into the total discharge will not be great.

MEASUREMENTS OF ICE-COVERED STREAMS.^a

The general parabolic law of the distribution of velocity in a cross section of a stream with open channel holds also for a stream under ice.

The table on pages 70 and 71, giving a summary of the results of many vertical velocity-curves, shows that there are two points in which the thread of mean velocity occurs under ice. These points are at about .1 and .71 depth below the bottom of the ice, varying between 0 and .22 for the upper and .63 and .79 for the lower. It is thus seen that they lie very nearly at .2 and .8 of the depth. As seen in the table the .2 and .8 depth method gives the mean velocity within a small percentage of error, and in making measurements under ice this method should be used.

If it is desired to make measurements having a high degree of accuracy, or for the purpose of checking results made by the two-point method, the whole measurement may be made by vertical velocity-curves (fig. 18).

When it is necessary to make observations at mid-depth a coefficient should be determined for reducing the velocity to the mean. If the river is not deep enough to get vertical velocity-curves a coefficient may be obtained at a number of stations by comparing the average of the velocity at the .2 and .8 depth with that observed at the mid-depth. See tables, pages 70 and 71, giving coefficients to reduce mid-depth velocity to mean.

In measuring an ice-covered stream the procedure is in general the same as for a stream with open channel, except that provision must be made to eliminate interference due to ice and frost. The equipment necessary for making the measurement includes the ordinary current-meter outfit, ice chisel, axe, and shovel for cutting away and removing the ice, and an ice measuring stick for determining the thickness of the ice.

The meter should be operated on a rod if the depth will permit. If,

^a See Water-Supply Papers Nos. 187 and 337, U. S. Geol. Survey.

RIVER DISCHARGE.

Summary of vertical velocity curves under ice cover.

SMOOTH ICE COVER.

| River. | Station. | Number of curves. | Gage height to water surface. | Depth under ice. | Ice thickness. | Mean velocity. | Depth of threads of velocity. | | | Coefficient to reduce to mean velocity. | | Bed of stream. |
|---|--|-------------------|-------------------------------|------------------|----------------|----------------------|-------------------------------|-------------|----------|---|-----------------------------------|---|
| | | | | | | | Upper mean. | Lower mean. | Maximum. | 0.5 depth. | $\frac{0.2+0.8 \text{ depth}}{2}$ | |
| Catakill..... Chenung..... Connecticut..... | South Cairo, N. Y..... Chenung, N. Y..... Orford, N. H..... | 4 | Feet. 2.82 | Feet. 2.7 | Feet. 0.98 | Ft. per sec. 0.44 | 0.06 | 0.70 | 0.31 | 0.80 | 0.98 | Gravel. Coarse gravel. Gravel and sand. |
| | | 4 | 2.85 | 2.7 | 1.57 | 0.64 | .16 | .79 | .46 | .86 | 1.02 | |
| | | 18 | 4.16 | 4.0 | 1.97 | 1.04 | .11 | .69 | .35 | .85 | 1.00 | |
| | | 12 | ± 4.1 | 4.1 | 1.91 | 1.82 | .07 | .63 | .25 | .83 | .99 | |
| Esopus..... | Kingston, N. Y..... | 6 | 5.6 | 7.3 | 7.3 | 1.80 | .12 | .73 | .37 | .87 | .99 | Sand and gravel. |
| | | 2 | 5.28 | 5.8 | 10 | .94 | .16 | .74 | .52 | .87 | .97 | |
| | | 8 | 5.60 | 3.4 | 58 | .80 | .03 | .63 | .24 | .76 | .85 | |
| | | 12 | 6.6 | 4.9 | 10 | 1.19 | .07 | .69 | .29 | .82 | .98 | |
| Fish..... | Wallagrass, Me..... | 8 | 7.0 | 5.0 | 1.26 | .90 | .08 | .67 | .36 | .86 | .98 | Gravel. |
| | | 8 | 3.91 | 2.5 | 1.40 | .90 | .07 | .70 | .36 | .88 | .99 | |
| | | 8 | 5.00 | 3.5 | 1.45 | 1.25 | .14 | .77 | .43 | .84 | .96 | |
| | | 20 | 5.9 | 3.8 | .54 | 1.62 | .07 | .67 | .24 | .80 | .85 | |
| Genesee..... Genesee..... | Mount Morris (Jones Bridge), N. Y..... Rochester, N. Y..... | 11 | 1.42 | 6.6 | 45 | .45 | .09 | .72 | .44 | .84 | .99 | Coarse gravel. Do. |
| | | 19 | 1.55 | 3.8 | .43 | .80 | a.01 | .70 | .33 | .82 | .87 | |
| | | 4 | 3.40 | 2.7 | 2.27 | 1.17 | .04 | .63 | .19 | .82 | .91 | |
| | | 12 | 3.48 | 2.6 | 1.30 | 1.17 | .04 | .66 | .30 | .87 | .91 | |
| Kennebec..... | North Anson, Me..... | 15 | 3.55 | 1.6 | 2.15 | 1.87 | .18 | .77 | .45 | .81 | .92 | Gravel. |
| | | 19 | 4.17 | 2.5 | 1.91 | 1.30 | .07 | .69 | .34 | .86 | .90 | |
| | | 10 | 4.70 | 3.0 | 2.04 | 1.32 | .10 | .71 | .37 | .87 | .99 | |
| | | 9 | 4.77 | 2.9 | 2.34 | 1.33 | .08 | .76 | .32 | .87 | .90 | |
| Mohawk..... Requette..... Rondout Creek..... Wallkill..... | Utica, N. Y..... Massena Springs, N. Y..... Rosendale, N. Y..... Newpatz, N. Y..... | 23 | 5.30 | 3.2 | 2.00 | 1.61 | .12 | .70 | .42 | .83 | .86 | Earth, very smooth. Coarse gravel. Rock. Clay and coarse gravel. |
| | | 13 | 16.2 | 10.1 | .50 | 1.00 | .21 | .78 | .47 | .82 | .84 | |
| | | 17 | 9.6 | 9.2 | 1.00 | 3.24 | .17 | .74 | .43 | .90 | .98 | |
| | | 3 | 9.5 | 6.7 | .75 | .55 | (c) | .65 | .24 | .80 | .89 | |
| | | 11 | 7.3 | 6.0 | ± 1.2 | .83 | .11 | .70 | .40 | .83 | .87 | |
| | | 4 | 7.78 | 7.9 | 1.05 | 1.29 | .22 | .76 | .46 | .82 | .90 | |
| | | 14 | 8.95 | 7.2 | 1.00 | 1.57 | .10 | .71 | .36 | .84 | .89 | |
| | | 13 | 11.2 | 9.5 | 1.85 | 2.35 | .11 | .71 | .38 | .85 | .89 | |
| | | 10 | 17.33 | 18.2 | .52 | 3.54 | .16 | .79 | .43 | .89 | .91 | |
| | | | | | | | | | | | | |

* Upper thread of mean velocity for 1 curve only.

* Below reference point.

* Upper thread of mean velocity at 4 curves only.

Summary of vertical velocity curves under ice cover—Continued.

SMOOTH ICE COVER—Continued.

| River. | Station. | Number of curves. | Gage height to water surface. | Depth under ice. | Ice thickness. | Mean velocity. | Depth of threads of velocity. | | | | Coefficient to reduce to mean velocity. | | | Bed of stream. |
|-------------------------|-----------------------------|-------------------|-------------------------------|------------------|----------------|----------------|-------------------------------|-------------|----------|----------|---|------------|-----------------------------------|----------------|
| | | | | | | | Upper mean. | Lower mean. | Maximum. | Maximum. | Maximum. | 0.5 depth. | $\frac{0.2+0.8 \text{ depth}}{2}$ | |
| West Canada Creek..... | Twin Rock Bridge, N. Y..... | 9 | 3.8 | 2.5 | 1.50 | 1.82 | 0.04 | 0.65 | 0.34 | 0.86 | 0.91 | 0.91 | 1.02 | Coarse gravel. |
| Winooki..... | Richmond, Vt..... | 26 | 5.5 | 1.6 | 2.10 | 2.12 | .12 | .72 | .40 | .80 | .83 | .83 | 1.02 | Gravel. |
| Mean of 332 curves..... | | | | | | | .12 | .71 | .37 | .839 | .878 | .878 | 1.002 | |
| Highest..... | | | | | | | .22 | .79 | .52 | .90 | .92 | .92 | 1.04 | |
| Lowest..... | | | | | | | .00 | .63 | .19 | .76 | .82 | .82 | .98 | |

ROUGH ICE COVER.

| | | | | | | | | | | | | | | |
|------------------------|----------------------|----|------|-----|------|------|------|------|------|------|------|------|-------|------------------|
| Connecticut..... | Orford, N. H..... | 7 | 5.59 | 4.6 | 1.71 | 1.08 | 0.08 | 0.70 | 0.37 | 0.86 | 0.93 | 0.93 | 1.00 | Gravel and sand. |
| | | 7 | 6.00 | 4.9 | 1.11 | 1.11 | .09 | .70 | .39 | .64 | .86 | .86 | 1.00 | |
| Des Moines..... | Kossauqua, Iowa..... | 21 | 6.70 | 5.8 | 1.66 | 1.23 | .14 | .74 | .42 | .86 | .88 | .88 | 1.00 | Gravel. |
| Maumee..... | Sherwood, Ohio..... | 5 | 2.45 | 4.8 | .46 | 1.58 | .13 | .73 | .40 | .86 | .88 | .88 | 1.01 | Do. |
| Mean of 51 curves..... | | 11 | 3.34 | 2.5 | .58 | .78 | .11 | .68 | .34 | .92 | .95 | .95 | 1.002 | |
| Highest..... | | | | | | | .11 | .71 | .38 | .868 | .894 | .894 | 1.01 | |
| Lowest..... | | | | | | | .14 | .74 | .42 | .92 | .95 | .95 | 1.00 | |

VERY ROUGH ICE COVER, BROKEN AND TILTED.

| | | | | | | | | | | | | | | |
|------------------------|----------------------|---|------|------|------|------|------|-------|------|------|------|------|------|-------------------------|
| Rondout Creek..... | Rosendale, N. Y..... | 4 | 7.0 | 5.3 | 0.45 | 0.74 | 0.27 | +0.88 | 0.56 | 0.80 | 0.85 | 0.85 | 1.04 | Rock. |
| Walkill..... | Newpaltz, N. Y..... | 4 | 13.7 | 14.6 | 1.40 | 2.98 | .27 | .88 | .56 | .84 | .85 | .85 | 1.00 | Clay and coarse gravel. |
| Winooki..... | Richmond, Vt..... | 5 | 5.52 | 6.2 | ±2.5 | 1.99 | .22 | .81 | .52 | .74 | .76 | .76 | 1.02 | Sand and gravel. |
| Mean of 13 curves..... | | | | 8.7 | 1.45 | 1.90 | .25 | .86 | .55 | .79 | .82 | .82 | 1.02 | |

• No lower mean thread of velocity for 1 curve.

however, a cable is used, it should be tagged at foot intervals, beginning at the center of the meter for convenience in sounding and placing the meter at the proper depth.

The most satisfactory ice chisel yet found is the Guifford Wood, No. 477. This chisel has a narrow plate made of rather soft steel, so that it




FIG. 18—Distribution of Velocity under Ice Cover, Cannon River, Welch, Minn.

can be easily sharpened with a hand file. The handle is solid steel, has a ring in the top, and may be joined, if desired, for convenience in carrying. This chisel weighs 14 pounds and is as light as can be satisfactorily used.

The measuring stick should be made of 1 by 1-inch material, graduated to tenths of a foot, and with a 3-inch angle fastened to the zero end. In use this angle is brought against the under surface of the ice and the thickness read at the top surface on the graduated stick.

The accuracy of discharge measurements depends largely on the comfort of the engineer while making the measurement, therefore he should give careful attention to his clothing.

Winter-measurement observations are taken by one of the following methods or by a combination of them:

1. From a bridge or cable, when the stream is clear or not frozen hard enough to support the observer.

2. Through holes cut in the ice.

3. By wading in a section from which the ice has been cleared.

Measurements from a cable or bridge in a section without ice cover are made in the same manner as open-water measurements, except that the meter should not be taken from the water unless absolutely necessary until the measurement is completed. The soundings can be taken by lowering the weight until it touches the bottom and then raising it until the head of the meter is just under the surface of the water, adding to this depth the distance from the top of the meter to the bottom of the weight. If it is necessary to remove the meter temporarily from the water, on its return it should be permitted to run for a period before the revolutions are recorded, as the warmer river water will tend to thaw out any slight congealing in the meter. If the meter is out of the water until it becomes practically rigid it should be thawed and thoroughly dried near a fire, care being taken that it does not become so hot as to melt the rubber connections or the solder on the cups.

The first operation in measurements under ice cover is the cutting of the holes through the ice. The holes should be spaced 5 to 10 feet apart, the interval depending on the width of the stream. On very small streams, where measurements of velocities are desired at many points close together, an entire section may be cut out, thus preventing the greater part of the vertical pulsations of the water. The position of the holes need not be accurately determined before cutting; they should, however, be placed in a straight line and as near as possible at right angles with the current. Round or oblong holes are easier to cut than square holes, and the larger diameter should be parallel to the current. They should be large enough to permit the meter to be easily raised and lowered. A shovel will be found almost essential in clearing away snow from the ice in the vicinity of the holes and removing the chopped ice from the holes. The first 3 or 4 inches of the ice can be cut more quickly with a sharp ax than with the ice chisel, but with the chisel an ax is not necessary. The ice should be cut only at the circumference of the circle, as large cakes can be taken out with less shoveling than the small ones that are made

when the entire cross-section of the hole is chopped. Care should also be taken not to cut through the ice into the water until a few rapid blows of the chisel will clear the entire section. By working carefully holes can be chopped through ice 1 to 3 feet thick with very little splash; if, however, water is standing or flowing on the ice to depths of 1 or 2 inches it is almost impossible to chop holes without getting wet.

As a rule it is advisable to chop one hole through the ice in the center of the section in order to detect the presence of frazil or floating anchor ice. If the hole so cut can not be kept clear from the finer particles of frazil, the measurement will probably give inaccurate results, and the engineer should endeavor to find a better section.

When the holes are cut and cleared of the chopped ice the distances between them should be measured with a steel tape and recorded in the notebook, leaving sufficient space between the recorded measurements for the record of velocities in the vertical. As the winter flow is likely to be fairly uniform, the soundings may be taken independently from the measurements of velocity. The gage height to the water surface should then be read and the soundings taken either with the rod or with the weight and cable. At each hole should be recorded (a) the thickness of the ice, (b) the distance from under surface of ice to water surface, and (c) the total depth of the water. From these data can be computed the depth at which the meter must be placed in each hole in order that it may be at the 0.2, 0.8, or 0.5 position beneath the ice. Thus—

$$0.2 \text{ depth} = (c-b) \times 0.2 + b$$

$$0.5 \text{ depth} = (c-b) \times 0.5 + b$$

$$0.8 \text{ depth} = (c-b) \times 0.8 + b$$


The notation and a form for recording the data are illustrated in figure 19.

The information collected regarding the total thickness of the ice need not enter into the measurement.

When holes are cut through the ice a vertical pulsation, which may amount to nearly half a foot, is often noticed in the water. In measuring the depth of the water, care should be taken to determine the mean. If the depths beneath the ice are greater than 2.5 feet, the measurement should be made by the 0.2 and 0.8 point method; for depths between 1.5 feet and 2.5 feet velocities should be observed at 0.2 and 0.8 and 0.5 depth; for depths less than about 1.5 feet the mid-depth method should be used.

The depths at all measuring points should be measured and the depths at which the meter is to be placed computed before the meter is assembled.

The meter should be so held in the hole that the head is as far upstream as possible to avoid the effect of the vertical pulsations. If



| OBSERVATIONS | | | | | |
|-----------------------------|--------------------------------|-----------------------|-----------------------------------|-----------------|-------------|
| Distance from initial point | Thickness of ice | Total depth of water | Depth of meter from water surface | Time in seconds | Revolutions |
| | Water surface to bottom of ice | Effective water depth | | | |
| 0 | | | | | |
| 10 | a | c | (c-b) x .2 + b | | |
| | b | c-b | (c-b) x .5 + b | | |
| | | | (c-b) x .8 + b | | |
| 15 | | | | | |

FIG. 19.—Diagram showing factors used in making discharge measurements and new form proposed.

measurement may be completed without having the meter in the air long enough for the water on it to congeal.

The section for winter measurements should preferably be chosen during the open season to insure favorable conditions. If the presence of frazil or of floating anchor ice at a section affects more than 10 per cent of the total cross-section, the measurements should, if possible, be made at another section where such conditions do not exist. Sections

a rod is used, the meter can be kept in position by holding the rod against the upstream side of the hole; if a cable, the meter can be held at one position more easily by standing on the cable than by holding it in the hand. The number of revolutions and the time are recorded as in open-water measurements. After the complete data for each observation have been recorded while the meter is still in the water, the meter can be carried quickly to the next hole and the observations continued. In this way, if no frazil is present, the entire

at rapids, where the velocities are high enough to carry the ice away quickly, may be most satisfactory, even if the other conditions are not so desirable, and the measurements made at them will be more accurate than those made at a section which is partly clogged with frazil.

MEASUREMENTS IN ARTIFICIAL CHANNELS.

Flow in artificial channels should be studied with especial care on account of the disturbances resulting from the operation of gates and water wheels in power canals and of checks, intakes, and outlets in irrigation canals.

In an irrigation canal the effect of such disturbance usually appears in the control section as a change which destroys the relation of gage height to discharge. Though the conditions may remain satisfactory for making current-meter measurements, estimates of discharge can not usually be made from records of stage and a rating curve.

Changes similar to those in irrigation canals occur also in headraces of power canals. In tailraces the relation of stage to discharge will probably be reasonably permanent, but conditions for measurements of discharge are unsatisfactory, as the distribution of the velocity in the cross-section of the channel is usually not normal and is likely to change with considerable rapidity. Furthermore, the agitation of the water may interfere with the proper action of the meter or other measuring device. Special studies should therefore be made of the conditions existing in each artificial channel to be gaged, and special arrangements of instruments or of channels may be necessary in order to get satisfactory measurements of discharge, particularly measurements in connection with tests of water wheels in place.

FLOAT MEASUREMENTS.

The determination of the discharge of a stream by the float method is comparatively simple and easy, as no delicate instrument is necessary for measuring velocity. The results, however, will not generally be so accurate as those obtained by the current meter.

The first step in making a float measurement is to select and measure the "run" over which the floats are to pass. This run should be 50 to 500 feet long, should be located in a stretch of the stream having a straight and uniform channel, and its ends should be definitely marked on one or both banks by range poles or signals or by tagged lines across the stream.

Floats are placed in the stream above the upper end of the run and allowed to pass over the run, the time in seconds required for their

passage being noted. The quotient obtained by dividing the length of the run in feet by the time of passage in seconds is the velocity in feet per second of that part of the stream traversed by the float. A stop-watch is necessary for the satisfactory determination of the time required by the floats to pass over the course.

The type of float used will depend upon local conditions of channel and current. Tube floats are generally limited in use to artificial channels. Subsurface floats are but little used and only in deep streams. Surface floats are adapted for general use under all conditions.

In an ordinary discharge measurement by this method a number of velocity determinations are made at varying distances from the shore, and the mean of the velocities thus obtained, reduced by a coefficient, is taken as the mean velocity for the cross-section. The magnitude of the coefficient will vary between .85 and .95, the variation depending on the stage and character of the stream.

In more accurate work the distance of the float from the bank will be noted and the mean velocity of the whole section can be determined by plotting the mean position of each float, as indicated by its average distance from the bank, as an ordinate, and the corresponding time of the run as an abscissa. A curve through the points so located shows the mean time of run at any point across the stream. Velocities for each partial area of cross-section are scaled from this curve, reduced to feet per second, and multiplied each by its area to determine partial discharge. The sum of the partial discharges is the total discharge. The coefficient for reducing surface velocity to mean velocity may be applied either to each determination of velocity or to the computed discharge.

The area used in float measurements is the effective area of the section of the river over which the runs are made and is determined by averaging the areas of cross-section of the stream measured at the ends and at intermediate points.

SLOPE MEASUREMENTS.

The mean velocity of a stream has been expressed in the Chezy formula as $V = c \sqrt{Rs}$, in which c is the coefficient combining the total effects of roughness of the bed and all other conditions which may affect the velocity, except the slope and hydraulic radius. This formula has long served as a nucleus about which slope data have been collected, and has been used as a basis for work by Kutter,^a who developed the following expression for the value of the coefficient c in terms of s , R , and n .

^a See "The flow of water in rivers and other channels" by Ganguillet and Kutter.

$$c = \frac{41.6 + \frac{.00281}{s} + \frac{1.811}{n}}{1 + \left\{ 41.6 + \frac{.00281}{s} \right\} \sqrt{\frac{n}{R}}}$$

This, when introduced into the original formula, gives

$$V = \left\{ \frac{\frac{1.811}{n} + 41.6 + \frac{.00281}{s}}{1 + \left\{ 41.6 + \frac{.00281}{s} \right\} \sqrt{\frac{n}{R}}} \right\} \sqrt{Rs.}$$

In measurements of discharge by the slope method it is necessary to determine (1) the mean area of cross-section, (2) the slope of the surface of the stream, and (3) data in regard to the roughness of the bed, from which to estimate the proper value of n .

In making a measurement by this method a straight channel, 200 to 1000 feet long, must first be selected and measured for the course or "run." In this course the slope and cross-section should be reasonably uniform and the conditions of bed and banks should also preferably be permanent. The slope must be sufficiently large to be measured without a large percentage of error. The effective area of cross-section throughout the run is obtained as the mean of the cross-sections of its ends and intermediate points. The determinations of these cross-sections may be made once for all at a low stage of the stream, if the bed and banks are permanent, or as often as may be necessary for good work if the conditions are changing.

The slope of the surface of the stream is obtained by simultaneous readings of gages placed at the ends of the run, and as it is the important factor in this method, the position of the gages by which it is to be measured should receive careful consideration. Theoretically the gages should be set in the current of the stream, which may, at high stages, be several tenths of a foot higher than water in the same cross-section near the banks. Such location of gages in the current is impossible unless bridges are available to which gages may be attached, and in this case the effect of bridge piers may be sufficient to vitiate the observations. Gages attached directly to bridge piers are not suitable for measurements of slope because of the disturbance of the water around the pier. In locating gages on the banks the exposure should be the same for all gages to be utilized in conjunction for the determination of slope;

otherwise the piling of water against one bank or its recession from another may incorrectly indicate the slopes.

At least two and preferably three gages should be placed in position at the ends (and in the center if three gages are used) of the course in which the slope is to be measured. The datum of each gage must then be accurately referenced by means of a permanent and easily accessible bench mark, and all gages must be connected by levels. As the gages should be read to hundredths, the effect of wave action should be eliminated by the use of some form of stilling box.

The accuracy of the estimates will depend largely on proper placing of the gages, precision in the gage readings, and care in setting the gages to read from the same datum. If the course is not designed for continuous use for slope measurements, reference points from which the elevation of the water may be determined by a single vertical measurement may be used instead of gages.

In collecting data for determining the value of n it should be borne in mind that this factor includes not only the effect of roughness of bed but also that of all obstructions that may retard the water. In general n is larger for the overflow part or parts of the stream than for the channel proper; hence these parts should be treated separately in computing the discharge. For the higher stages of the stream n for the channel proper generally decreases as the stage increases. The engineer must rely largely on judgment and experience in this matter.

The following table gives the ranges of value of n for various types of channels, both natural and artificial. The values for artificial channels are taken from the results of investigations by the Office of Experiment Stations, Department of Agriculture, and by the United States Reclamation Service, and are based on actual conditions of canals in operation. In general, much lower values are found for artificial channels when first constructed than for the same channels after they have been in operation for some time. The values apply for sections on tangents and should be increased if used for curves.

Values of n in Kutter's formula.

| <i>Character of channel.</i> | <i>Value of "n."</i> |
|------------------------------|----------------------|
| Artificial channels. | |
| Cement, surfaced | .012 to .015 |
| Cement, rough | .015 to .018 |
| Wood, surfaced | .011 to .015 |
| Wood, rough | .015 to .020 |

| | |
|-------------------------------------|--------------|
| Earth, smooth | .017 to .025 |
| Earth, rough | .025 to .030 |
| Cobble | .030 to .035 |
| Vegetation | .035 to .050 |
| Natural channels | |
| Smooth, sandy, and fine gravel beds | .020 to .025 |
| Rough beds | .030 to .035 |
| Overflow banks with vegetation | .040 to .055 |

For simplicity in computation, tables giving the values of V and c for various conditions have been published. Among these is Table XV, page 175. Diagrams (Pl. VII) are also used to advantage in this connection.

The slope method is commonly used for estimating flood discharge, often after the crest of the flood wave has passed and when the only data available are the slope and the area of cross-section, as determined from marks along the banks, and a knowledge of the general conditions. Another important present use of Kutter's formula is in the design of canals, for which the slope must be determined in order that the channel may carry a certain quantity of water at a given velocity.

The results obtained by this method are in general only approximate, owing to the difficulty in obtaining accurate measurements of slope and the other necessary data and the uncertainty of the value of n to be used in Kutter's formula.

OBSERVATIONS OF STAGE.


In the collection of records of daily stage of a stream for use with discharge measurements to obtain daily flow, care must be taken to eliminate errors due to the following causes:

1. Change in gage datum.
2. Lack of refinement in gage readings.
3. Inaccuracies of observation by the gage observer.
4. Insufficient readings to give the true daily mean.

The permanence of the original installation of the gage will largely determine the errors due to change in datum. If the gage is properly installed and the gage datum is frequently checked by a level errors from this cause should seldom occur. They are, however, cumulative and therefore specially serious. The importance of the maintenance of gage datum and the precautions in connection therewith have been fully discussed on pages 23 to 36.

| | Find. | Procedure. |
|----|-------|--|
| 15 | c | Locate point where radial line $n = .026$ cuts slope curve $s = .00015$; join this point with point on hydraulic radius scale $R = 4.5$. This line cuts the vertical scale of coefficients in $c = 75$. |
| 15 | R | Locate point $n = .026$, $s = .00015$; join this point with $c = 75$. The prolongation of this line cuts hydraulic radius scale in $R = 4.5$. |
| | s | Join $R = 4.5$ with $c = 75$; prolong this line to cut radial line $n = .026$. This intersection falls on slope curve $s = .00015$. |
| 15 | n | Join $R = 4.5$ with $c = 75$; prolong this line to cut slope curve $s = .00015$. This intersection falls on radial line $n = .026$. |
| 15 | V | Find, as in Ex. 1, $c = 75$; draw line joining $R = 4.5$ with $s = .00015$ on vertical slope scale. A line through $c = 75$ parallel to this one cuts velocity scale in $V = 1.95$. |
| 15 | n | Join $R = 4.5$ with $s = .00015$ on vertical slope scale. A line through $V = 1.95$ parallel to this one cuts scale of coefficients in $c = 75$. As in Ex. 4, find $n = .026$. |
| 15 | R | Assume $R = \text{say, } 5$; with $R = 5$, find, as in Ex. 5, $V = 2.10$ —showing that assumed R is too large; try $R = 4$, and interpolate. That value of R which makes $V = 1.95$ is the true value. |
| | s | Assume $s = \text{say, } .001$; with $s = .001$, find, as in Ex. 5, $V = 5.0$ —showing that assumed s is too large. Try $s = .0001$, and interpolate. That value of s which makes $V = 1.95$ is the true value. |

taking
slope
radii as





The refinement to which the gage must be read will depend on the sensitiveness of the station. For ordinary stations, equipped with staff gages, readings to the nearest quarter tenth are usually sufficiently accurate and can be readily obtained by the average observer; for canals and small streams it may be necessary to read to hundredths; for large streams, readings to half tenths or tenths may be sufficiently close. Errors due to refinement of readings are generally compensating, but they may be cumulative for considerable periods when the stage is constant. The refinement to which gage heights must be read and used for determining daily discharge depends on the station rating curve and is discussed on pages 104 to 107.

Errors due to inaccuracies of observation by the gage reader may be either compensating or cumulative. They will depend on the honesty and intelligence of the available gage reader and can be guarded against only by careful instructions and close inspection. In many localities it is necessary to install automatic gages on account of the incompetence of available observers. When the automatic gage is used special care must be taken in placing the record sheet, as any errors in setting will introduce cumulative errors in the discharge.

The number of observations to be taken daily in order to obtain the true mean daily gage height will depend on the characteristics of the stream and should be determined for each gage station by a series of hourly gage readings, taken at various times throughout the year, as the errors due to this cause may enter only at certain seasons. Errors of this kind will usually be cumulative although under some conditions they may be compensating. For streams whose flow is regulated either naturally or artificially the mean daily stage can be obtained only by an automatic gage; for unregulated streams two gage readings a day will, as a rule, give the mean stage with sufficient accuracy except during flood periods, when additional readings should be taken.

The accuracy of the gage readings will depend largely on the type and character of the gage. All direct-reading gages should be plainly graduated, either to tenths, half tenths, or hundredths, the graduation depending on the refinement to which the gage is to be read, and they should be so placed that they are easily accessible to the observer.

CHAPTER IV.

WEIR STATIONS.

In a broad sense a weir is any artificial structure placed in a stream for the purpose of raising the surface of the water. A weir for measuring discharge must have a well-defined form and a reasonably level crest of permanent shape and elevation, and must not allow a large percentage of the water to pass through, beneath, or around it.

Weirs may be used for measuring the quantity of water in streams because water flows over them in accordance with known, definite laws. They become available for such measurement by the use of formulas in which the quantity of discharge is expressed in terms of the dimensions of the weir and the head of water on its crest, and by coefficients which have been determined by experiments.

Weirs may be divided into two classes—(1) sharp-crested, or standard weirs, and (2) broad-crested weirs or dams, the distinction depending on whether the water in passing over them comes in contact with the crest on a line or a surface. Either of these two classes may be submerged or may have a free overfall—that is, the elevation of the water on the downstream side of the weir may be above or below its crest. Weirs of either of these classes may be vertical or inclined. Usually measurements of flow are made only at vertical weirs having a free overfall, and the following discussion is limited to that class.

In considering the establishment of a weir station, choice must generally be made between a velocity-area station, the use of an existing dam, or the construction of a sharp-crested weir to be used exclusively for obtaining a record of flow. The choice between these types of stations will be governed largely by conditions relating to the cost and accuracy of the records.

SHARP-CRESTED WEIRS.

Sharp-crested weirs used under heads of not to exceed 5 feet offer the best facilities known for determining the flow of stream discharges are too great to be weighed or measured in a calibrated

The coefficients for use in formulas for such weirs have been carefully determined for heads under 5 feet, and have a small range in value.

The use of sharp-crested weirs is generally limited by their cost to comparatively small streams or to streams of which very accurate records of flow are desired. They are most commonly employed to divide water among several users, especially for irrigation, and the principal requisite for their location is a site at which the weir can be economically constructed so that there will be no percolation or leakage.




FIG. 20.—Cippoletti Weir, with Water Register in Place.
(Mead, Bulletin 86, Experiment Stations, Department of Agriculture.)

Sharp-crested weirs may be either rectangular or trapezoidal in form and must have a crest of such dimensions and height that the water will have free fall over it with provision for the admission of air under the overfalling water.

As commonly arranged, the weir projects sharply from both sides and the bottom into the channel conducting the water, thus making the dimensions of the cross-section over the weir less than those of the

channel of approach. This reduction in the cross-section of the channel causes a contraction of the water at the bottom and the ends as it passes over the weir. If both end and bottom contractions exist the weir is called a *contracted* weir. This contraction may be prevented by arranging the channel of approach so that the water is guided both on the bottom and ends directly to the crest of the weir, making what is called a *suppressed* weir. In many weirs the end contractions only are suppressed, when the weirs are said to be partially contracted.

End contractions cause a virtual decrease in the length of crest of the weir. For rectangular weirs this effect is provided for in the formulas. The Cippoletti weir (fig. 20), which is the most common form of trapezoidal weir, is constructed with the outward slope of each end 1 horizontal to 4 vertical. This causes an increase in effective length as the head increases, thus very nearly compensating for end contraction.

In sharp-crested weirs the channel of approach, fore bay, hydrant, or stilling box from which the water flows over the weir must either be sufficiently large to eliminate velocity of approach to the weir, or a correction must be made for such effect in the computations. The structure will therefore vary in size and arrangement for the accommodation of different quantities of water.

BROAD-CRESTED WEIRS.*

Weir stations on large streams will usually be located at existing dams which are constructed for purposes of power or navigation, and selection must be made between several available dams or between a dam and a velocity-area station. In either case the advantages and disadvantages of each locality must be carefully considered, as the value of the resulting record of discharge will depend largely upon the possibilities of the station. As compared with velocity-area stations dams may have the advantage of continuity of record through the period of ice but the disadvantage of uncertainty of coefficients to be used in the weir formulas and complications due to diversion and use of water.

In investigating the availability of a dam for gaging purposes, observations must be made concerning certain conditions which are necessary to insure good records. These conditions may be divided into two classes—(1) those relating to the physical characteristics of the dam itself, and (2) those relating to the diversion and use of water around and through the dam.

*Stations at broad-crested weirs are fully discussed in U. S. Geol. Survey Water-Supply Papers Nos. 200 and 180.

The physical requirements are as follows: (a) Height of dam such that backwater will not interfere with free fall over it; (b) absence of leaks of appreciable magnitude; (c) topography or abutments which confine the flow over the dam at high stages; (d) level crests which are kept free from obstructions caused by floating logs or ice; (e) crests of a type for which the coefficients to be used in $Q = cLH^{\frac{3}{2}}$ or some similar standard weir formula are known; (f) either no flash boards or exceptional care in reducing leakage through them and in recording their condition.

Preferably there should be no diversion of water through or around the dam. Generally, however, part or all of the water is diverted for uses of power or navigation. Such water must be measured and added to that passing over the dam. To insure accuracy in estimates the water diverted must be reasonably constant in quantity, and so utilized that it can be measured either by a weir, a current meter, or through a simple system of water wheels which are of standard make or have been rated as water meters under working conditions and so installed that the gate openings, heads under which they work, and their angular velocities may be accurately observed.

The combination of physical conditions and uses of the water should be such that the estimates of flow will not involve, for a critical stage of considerable duration, the use of a head on a broad-crested dam of less than 6 inches. Moreover, when all other conditions are good, a careful observer is still essential in order to obtain reliable results.

The field work for the establishment of a station at a dam must be sufficient to provide for obtaining the records of gage height, and must also include the surveys and the collection of information which will make possible the correct interpretation and application of these records in the computation of discharge. It must consist, therefore, of the establishment of a gage for determining the head on the dam, and, if water is diverted through a head race and used through wheels or wasted through gates or over weirs, the establishment of sufficient other gages for determining the effective head on such turbines, gates, or weirs. Provision must be made for the systematic reading of these gages as well as for recording the conditions of wheel-gate openings, speed of wheels, elevations of crests of adjustable waste weirs, openings of waste gates, and elevation and conditions of flash boards. The gages must each be referenced by a convenient bench mark and all connected by a line of levels. An instrumental survey of the dam must be made to determine the length, profile, and cross-section of the crest. Cross-

sections of the channel of approach to the dam should also be measured in order to estimate the velocity of approach. Usually special forms for records and computations must be prepared for each such station.

WEIR FORMULAS ^a

The discharge over a weir is the product of the area of effective cross-section of the vein of water passing over it, the mean velocity in this area, and a coefficient determined experimentally, which varies with the form of the weir. The area of cross-section is determined approximately by the length of the crest and the head or the depth of water on it. The velocity is determined approximately by the head. These two quantities, length of crest and head, together with the coefficient, are therefore factors entering all weir formulas. They must, however, be modified for differences in forms of weirs, conditions of contraction, and velocity of approach.

The effects of end contraction and velocity of approach are allowed for in the formula by modifying the length of the crest and head respectively, or in the coefficient. The coefficient to be used in any instance must have been determined for that particular formula.

FUNDAMENTAL FORMULAS.

The fundamental formula for rectangular weirs may be derived by the calculus as follows:

$$\begin{array}{c}
 \boxed{\begin{array}{c} \text{---} \\ y \\ \text{---} \\ \text{---} \\ l \end{array}}
 \end{array}
 H \quad Q = c \int_0^H \sqrt{2gy} \, l dy = \frac{2}{3} c l \sqrt{2g} H^{\frac{3}{2}} \quad (1)$$

in which l represents the length of the weir; H , the head of water on the weir; y , the head on any horizontal strip of differential width, dy ; g , the acceleration of gravity; and c , coefficient that must be determined experimentally and that varies with different conditions of crest, channel of approach, etc. In the integral expression, $\sqrt{2gy}$ is the theoretical velocity of the water in the strip whose area is $l dy$. The integration between the limits 0 and H of the products of the infinitesimal areas by the velocities through them gives the total discharge, Q .

Modifications are made necessary, as previously explained, by reason

^aSee Hydraulics, by Hamilton Smith, jr.

of velocity of approach, variations in contraction of the water as it passes the weir, or variations in form of weir. If the end contraction is perfect, it causes at each end of the weir a shortening of the effective length by approximately $.1 H$.

If allowance is made for such end contraction, formula (1) becomes

$$Q = \frac{3}{4} c (l - .2H) \sqrt{2g} H^{\frac{3}{2}} \quad (2)$$

The same results are also accomplished in a different way by modifying properly the coefficients used in formula (1).

The velocity of approach " V " causes a virtual increase in head. The magnitude of such increase is the head corresponding to that velocity, is represented by h , and equals $\frac{V^2}{2g}$. Such velocity of approach may be

obtained approximately as the quotient by dividing the discharge by the area of cross-section of the channel of approach. The result so obtained should, however, be multiplied by a coefficient greater than unity (usually assumed to be between 1 and 1.5). Since the amount of the discharge is the quantity to be determined, the approximate value of V must be found from an approximate determination of Q by an application of the weir formula, neglecting the velocity of approach.

The correction for velocity of approach may be effected by adding h directly to the measured head in formula (1), as follows:

$$Q = \frac{3}{4} c l \sqrt{2g} (H + h)^{\frac{3}{2}} \quad (3)$$

or the correction may be applied before integration as follows:

$$Q = c \int_0^H \sqrt{2g (y + h)} dy = \frac{3}{4} c l \sqrt{2g} \left[(H + h)^{\frac{3}{2}} - h^{\frac{3}{2}} \right] \quad (4)$$

Formulas (3) and (4) are both in common use.

The formulas already explained—(1), (2), (3) and (4)—serve as bases for the formulas of all free overfall rectangular weirs, whether sharp or broad-crested. Values of c have been determined for use in each of these formulas for various types of weirs. Many sets of coefficients are therefore available, but each is applicable only to its formula.

RECTANGULAR WEIRS.

The formulas shown above, or slight modifications of them, are in general use for rectangular weirs. Of the modifications in common use, the *Francis formula* (5) is the simplest in form and application.

Francis determined that for a suppressed weir, without velocity of approach, c had an average value of 0.62. The product of the three constants of formula (1), 0.62, $\frac{3}{4}$, and $\sqrt{2g} = 3.33$, thus making

$$Q = 3.33 \, l H^{\frac{3}{2}} \quad (5)$$

The discharge per foot of length as determined by this formula is given in Table II, pages 162, 163.

When modified to allow for end contractions and velocity of approach, formula (5) becomes

$$Q = 3.33 (l - .2H) [(H + h)^{\frac{3}{2}} - h^{\frac{3}{2}}] \quad (6)$$

If there is no velocity of approach formula (6) becomes

$$Q = 3.33 (l - .2H) H^{\frac{3}{2}} \quad (7)$$

Table I, pages 160, 161, shows the discharge determined by formula (7).

In the use of formulas (5), (6), and (7), the dimensions must always be expressed in feet, because that unit has been introduced in the value of g , which appears in the coefficient.

Other formulas in common use were devised by *Bazin*, among which is the following, which gives the discharges for a sharp-crested weir without end contractions:

$$Q = \left(0.405 + \frac{.00984}{H} \right) \left(1 + 0.55 \frac{H^2}{(p + H)^2} \right) l H \sqrt{2gH} \quad (8)$$

in which H = observed head in feet; p = height of weir in feet; l = length of crest in feet; Q = discharge in second-feet.

Table IV, pages 166-168, shows the discharge as computed from formula (8).

TRAPEZOIDAL WEIR.

The trapezoidal weir is unimportant, except the Cippoletti weir (fig. 20), in which the outward slope of the ends (p. 83) counteracts the decrease in length due to end contractions. Ordinary formulas for suppressed weirs are therefore approximately applicable to it. Table II may be used for the Cippoletti weir with an error of about 1 per cent, giving results too small by that amount. Special determinations of coefficients for this weir have, however, been made and the resulting formula for discharge without velocity of approach is

$$Q = 3.3\frac{3}{4} \, l H^{\frac{3}{2}} \quad (9)$$

BROAD-CRESTED WEIRS.

Coefficients for several types of broad-crested weirs have been determined by Bazin, in France, and under the direction of Prof. Gardner S. Williams at the Cornell University Testing Laboratory, for the United States Deep Waterways Commission, by Mr. John R. Freeman and by members of the United States Geological Survey. The results of all of these experiments have been brought together by Mr. R. E. Horton in Water-Supply Paper No. 200, United States Geological Survey.

In this paper it is shown that within certain limits of head the discharge over several types of broad-crested weirs may be found by the use of formula.

$$Q = 2.64 LH^{\frac{3}{2}}. \quad (10)$$

This formula is applicable to broad-crested weirs of any width of cross-section exceeding 2 feet within such limit of head that the nappe does not adhere to the downstream face of the weir for low heads nor tend to become detached from the crest with greater heads. If the latter condition exists, the coefficient increases to a limit near the value which applies for a thin-edged weir, a point being finally reached where the nappe breaks entirely free from the broad crest and discharges in the same manner as for a thin-edged weir. Formula (10) may be applied safely to any weir having a crest width exceeding 2 feet and with heads from 0.5 foot to 1.5 or 2 times the breadth of weir crest. Table III, pages 164-165, shows the discharge as determined by this formula.

From the experiments mentioned above Mr. E. C. Murphy has developed multipliers to be used in connection with Bazin's formula for discharge over a sharp-crested weir to find the discharge over a broad-crested weir. Tables V, VI, and VII, pages 169-171 and fig. 38 show these multipliers and the forms of weirs to which they pertain. These tables are to be used in connection with Table IV, which has been made the basis in their computation.

COMPUTATIONS.

In the computation of discharge over a weir, whether sharp or broad-crested, a rating table is first prepared which gives the discharge for the various heads occurring during the period of observation. This rating table is computed by substituting values of head, dimensions of weir, and coefficients depending upon the type of weir under consideration in the formula applicable to such weir.

Many dams, unless built of solid masonry, have irregular crests due to unequal settlement. Such a dam must be divided into parts, each of which has a uniform elevation of crest, the formula applied to each part independently, and the results combined to form the rating table.

If any fixed condition of flash boards or other modification of the crest of the dam exists for a considerable period of time, a similar rating table should be made also for such condition. In the same way it will be found to be economical to compute rating tables for any fixed waste weirs in the head-race and for the usual condition of waste gates, wheel gates, etc., which are sufficiently constant to warrant such computations.

With rating tables at hand as above described, the computations of daily discharge are made by entering each rating table for the partial discharge through or over the structure for which that table has been made. The partial discharges so obtained are summed to give the total rate of flow. Discharges at stages and for conditions which are not covered by the rating tables must be computed independently.

These rating tables are as a rule instrumental in saving time in the computations, but their principal value arises from the fact that errors are much less likely to appear in the results than if each discharge is computed independently from a formula. For the same reason tables are more satisfactory than diagrams.

CHAPTER V.

DISCUSSION AND USE OF DATA.

COMPUTATION OF DAILY FLOW.

Certain analyses and computations must precede full use of field data in regard to stream flow. The first step in such analyses is the determination of the daily flow, which is computed in terms of second-feet and is the basis for all future deductions and discussions.

The daily discharge of a stream may be computed in various ways, the method to be chosen depending on the method used in making the discharge measurements—whether by weir or by the velocity-area method. Computations for weir stations are described in Chapter IV.

The base data necessary for the computation of daily flow for velocity-area stations are:

- (1) The results of occasional discharge measurements,
- (2) Records of gage height, and
- (3) Descriptions of conditions at the gaging station.

The methods adopted depend on the control section (see pages 45 and 46)—whether permanent, shifting, or affected by ice as described on the following pages.

GAGING STATIONS WITH PERMANENT CONTROL.

For stations on streams with permanent beds it is possible to prepare, from the data collected, station rating tables, each of which gives for its station the discharge which corresponds to any stage of the stream, and which, when applied to the daily gage heights, gives the daily discharge. The basis for a station rating table is a rating curve which shows graphically the discharge corresponding to any stage of the stream and is usually constructed by plotting the results of the various discharge measurements with gage heights as ordinates and discharges as abscissas. These points define the curve, which is then drawn by use of French curves. The rating table is then determined from the rating curve by tabulating the discharges for each tenth change in stage, adjusted by taking first and second differences.

If accurate and well-distributed discharge measurements covering the range of stage are available, the station rating curve can be readily constructed. Frequently, however, the measurements are more or less discordant and do not cover all stages. As a result special studies are necessary to determine the relative accuracy of the measurements and the position of the curve.

Since the discharge is the product of two factors—the area and mean velocity—any change in either factor will produce a corresponding change in the discharge. The curves of area and mean velocity furnish, therefore, valuable assistance in studying the accuracy of the measurements and in determining the true position of the rating curve. These curves are defined by plotting gage heights as ordinates, and area and mean velocity, respectively, as abscissas.

Curves of area and mean velocity can be constructed only when the channel, both at the control and the measuring section, is permanent. If the control remains permanent, the rating curve for the station will be well defined, even though shifts at the measuring section may make the construction of curves of mean velocity and area impossible. If the control is permanent the effect of changes in area will be counteracted by changes in velocity, thus making no change in the rating curve.

AREA CURVE.

The curve of area shows the relation between the gage height and the area of the cross-section of the stream. This area must include both moving and still water in order to be useful for comparison. Two factors, the width and depth, or gage height, govern the form and position of the curve, which is normally concave to the X axis but may, under special conditions, be straight. For ordinary conditions, where the width increases with the stage, the curve may be assumed to be a series of parabolic arcs whose parameters vary with the slope of the banks. If the banks are vertical the increment is constant and the curve becomes a straight line. It is never concave to the Y axis unless the unusual condition of overhanging banks exists.

The area curve can always be definitely drawn from a careful series of soundings, which should be taken at low water, during the period over which the discharge curve is to apply, and be developed to high water by use of a level. The curve can be constructed easily, and generally with sufficient accuracy, by determining the area only at those gage heights at which the slopes of the banks change. If extreme accuracy is desired the area should be computed for each half-foot of

gage height. High-water soundings and those made in deep streams in which the velocity is great are liable to large errors, and areas computed from them should be carefully scrutinized. Such soundings have been more prolific of sources of error in discharge measurements than all other factors combined.

Since for an infinitesimal change in stage the increase in area equals the product of the width at that stage by the difference in gage height, it follows that the width equals the quotient of the increase in area divided by the difference in gage heights, which ratio is the tangent of the angle that the area curve makes at that stage with the vertical; therefore the direction of the area curve for any stage is determined by




FIG. 21.—Typical Area Curves, Illustrating Their Form.

plotting from the vertical the angle whose tangent is the width at that stage. As most area curves are distorted by magnifying the vertical scale, the principle is utilized by laying off unity on the vertical or gage-height axis to the scale of gage heights, and the width on the horizontal or area axis to the scale of area (fig. 21).

Such curves when referred to origins of coordinates at the elevation of the lowest point in the cross-section exhibit the following useful characteristics: (a) For all sections except those with flat bottoms the area curve becomes tangent to the Y axis at the origin; (b) if the bottom is flat the curve cuts the Y axis at the origin at an angle whose tangent is the width of the bottom (a, fig. 21); (c) if the banks are vertical the

increment is constant and the curve proceeds in a straight line (fig. 21); (d) the area curve is permanent in curvature for all gage heights above the plane below which all shifts occur.

The accuracy of the areas as measured at the time of discharge measurement may be quickly tested by plotting them and drawing through each a straight line whose direction is tangent to the curve at that gage height and is determined by the width of the stream, as explained above. The curve should then be drawn from mean low water and kept parallel to the tangents at each point. Errors and discrepancies are at once




FIG. 22.—Typical Area Curves, Illustrating Their Construction.

apparent (fig. 22). The abscissas between the plotted points and the curve show the error resulting from the combination of errors in computation and soundings, and from changes in channel.

At stations where the banks of the stream are practically permanent, changes in section, if any, take place usually below the low-water line. If the area of such a section changes, the part of the curve above low water, which has been accurately constructed, may be shifted a proper distance horizontally to the right or left and be made to show accurately the areas of the new cross-section (fig. 21). The constant abscissa length between the old and new position of the curve is the algebraic sum of the changes in the area of the section, + for gain in area by

scour and — for loss in area by fill. A single determination of area at any gage height above low water therefore determines the new position of the curve, c (fig. 21).

MEAN VELOCITY CURVE.

As stated in Chapter III, the mean velocity of the stream is the average rate of motion of all the filaments of water of the cross-section and depends principally upon (1) the surface slope of the stream, (2) the roughness of the bed, and (3) the hydraulic radius, and has been expressed in the Chezy formula as $V = c \sqrt{R s}$, in which the coefficient c has been expressed by Kutter in terms of s , R , and n .

Since slope is the most important factor affecting velocity, when the rate of change in the slope is rapid the velocity tends to follow such change. When the slope becomes constant, changes in the velocity are controlled by the other two factors, the hydraulic radius and the coefficient of roughness.

The curve of mean velocity shows the relation between the gage height and the mean velocity of the current in the measured section. It is located by means of points which are determined by plotting the gage heights and corresponding mean velocities as coordinates. If sufficient measurements have been made to define the curve throughout the range of stage, no further investigation of its properties will be necessary. It frequently happens, however, that the curve must be constructed from limited or discordant values of velocity. To do this intelligently and satisfactorily a knowledge of the properties of the curve under various conditions of flow is essential, and in such cases it is advisable to develop the curves of R and s .

For usual conditions of natural flow in which the stage of no flow is the lowest point in the measured section, the mean velocity curve has approximately the form of a parabola with axis vertical and origin at or below the bed. It approaches a straight line, however, for the higher stages.

When the gaging section is in a stretch of the stream where zero flow occurs with ponded water at the section of the gage, the mean velocity curve will reverse at low stages and approach zero convex to the gage axis. The degree of curvature and the point at which the curve reverses are apparently governed chiefly by the amount of ponded water at the gage, the roughness of the bed, the form of the controlling bar, and other channel conditions. If the stream is small and shallow the change in direction is more abrupt. This peculiar reversal is probably

due to the rapid rate of change of the slope at extreme low flow. At zero flow the slope is of course zero. The least flow causes a slope of the surface and this slope increases with the stage, up to a certain point.

Three methods of extending the mean velocity curve from medium stages to high water have been employed: (1) Extend the curve as a tangent from the last observed value; (2) extend the curve as a hyperbola, i. e., approaching the straight line as its asymptote; (3) assume the slope constant or increasing slightly over the intermediate stages and compute the value of the velocity from the formula $V = c \sqrt{Rs}$, using the most probable value of the coefficient of roughness.




FIG. 23.—Typical Rating Curve, Showing Low-Water Extension.

The curve should be extended into low water with the greatest care. A slight variation from the true direction of the curve means a large percentage of error in the resulting estimate of minimum discharge. All conditions at the station should be studied. The curve must always be drawn to intersect the Y axis at the gage height of zero flow. If the point of zero flow is not known its true position will lie between the gage height of the bottom of the channel and the point where the tangent to the discharge curve at its lowest known value cuts the Y axis, as between *a* and *b*, fig. 23). If the mean velocity curve intersects the axis above the gage height of the bed of the stream—that is to say, if




Fig. 24.—Discharge, Mean Velocity, and Area Curves, Potomac River at Point of Rocks, Md.

there is ponded water—the curve will be convex to the Y axis; if it cuts the axis at the gage height of the bed of the stream the curve will be concave to the Y axis (fig. 23).

When measurements are not made at the gage—for example, when low-water measurements are made by wading—the discharge should be divided by the area of the section at the gage and the resulting velocity plotted on the velocity-curve. Points so found are useful in extending the velocity-curve into low water.


When the current is diagonal to the measured section the observed velocities should be reduced to velocities at right angles to the measured section, but the area should not be reduced. The area is a measured quantity, while the angle of the current is usually estimated and often varies with the stage.

STATION RATING CURVE.

Station rating curves which show graphically the discharge corresponding to any stage of the stream may be plotted either on ordinary or logarithmic cross-section paper. When ordinary cross-section paper is used the measurements of discharge are plotted either with discharge and gage heights as coordinates or with discharge and $A\sqrt{d}$ as coordinates, in which A is the area and d is the mean depth of the cross-section. When logarithmic cross-section paper is used, discharges and gage heights are the coordinates.

Ordinary cross-section paper with discharge and gage height as coordinates.—The usual method of constructing a rating curve for a gaging station is to plot the results of the discharge measurements on ordinary cross-section paper with gage heights and corresponding discharges as coordinates (fig. 24). The points so located define the position of a curve which is drawn among them. The horizontal and vertical scales will be so chosen that the curve may be used within the limits of accuracy for the work, and in its critical portions will make, as nearly as may be, angles of 45° with each axis. The discharge curve under natural special conditions, due to change in control, it may reverse at high stages and become concave to the gage axis.

If a sufficient number of accurate discharge measurements are available and are distributed throughout the range of stage, the discharge curve may be readily and accurately constructed. When such measurements are not available curves of reasonable accuracy may frequently be constructed by use of area and mean velocity curves or by one of the other methods of plotting.



In order to determine the accuracy of the individual measurements used in locating the station rating curve it is necessary to plot, as a function of the gage height, not only the discharge but also the mean velocity and area for each measurement. In this plotting the same gage-height scale should be used. The true area curve and approximate curves of discharge and mean velocity are then drawn through the points. The relation of the plotted points of discharge to the rating curve will show any discordant measurements. Whether the discord is due to erroneous area or velocity determinations will be shown by the relation of these respective points to the area and velocity curves, and the cause of any discrepancies in either factor can then be investigated. Such discrepancies may arise from error of observation or of computation.

The relative accuracy of the various plotted discharges having been determined, the rating curve can then be drawn, due weight being given to the various measurements. Points for portions of the curve not defined by actual discharge measurements can be determined by multiplying the area by the mean velocity as measured from the curves of area and velocity. For extending the rating curve either above or below the limits of the measurements the mean velocity and area curves may be constructed, as previously described, to the stages for which the discharge curve is desired, and the discharge curve found by taking the product of the two curves.

Whatever the method adopted in drawing the rating curve it should always be checked by computing the curve of mean velocity from the curves of area and discharge. If the curve of mean velocity so determined is not consistent with conditions at and near the station the discharge curve should be revised.

The discharge at a given stage of a rapidly rising stream is larger than for a falling or stationary stream at the same stage, as the surface slope, and hence the velocity, is greater for the first condition. This effect is but little noticed except during periods of extreme high water. At such times the water passes down the stream in a flood wave, and after the crest is passed a retarding effect may be caused which may reduce the slope practically to zero.

The curves shown in fig. 25 illustrate this. They are based upon the table of measurements on page 101. Therefore, in studying the plotted measurements, the fact whether the stream is rising, falling, or stationary should be considered. Inasmuch as rising stages are of much shorter duration than falling or stationary stages, more weight should

be given to measurements made on falling or stationary than on rising stages.

Discharge measurements of Ohio River at Wheeling, W. Va. Made in 1905 by E. C. Murphy.

| No. | Date. | Area of section. | Mean velocity. | Gage height. | Change of stage.* | Discharge. |
|-----|----------|------------------|----------------|--------------|-------------------|------------|
| | | Sq. ft. | Ft. per sec. | Feet. | Feet. | Sec.-ft. |
| 5 | March 20 | 38,890 | 5.89 | 28.2 | + .68 | 229,200 |
| 6 | " 20 | 42,750 | 6.13 | 30.8 | + .60 | 261,900 |
| 7 | " 21 | 54,780 | 6.23 | 38.9 | + .37 | 341,100 |
| 8 | " 21 | 57,360 | 6.18 | 40.7 | + .20 | 354,400 |
| 9 | " 22 | 59,580 | 6.07 | 42.05 | + .05 | 361,600 |
| 10 | " 22 | 60,510 | 6.05 | 42.5 | + .05 | 365,700 |
| 11 | " 23 | 58,830 | 5.73 | 41.6 | — .20 | 336,900 |
| 12 | " 23 | 56,790 | 5.60 | 40.3 | — .27 | 318,100 |
| 13 | " 24 | 49,250 | 5.20 | 35.2 | — .35 | 255,800 |
| 14 | " 24 | 45,550 | 4.99 | 32.7 | — .40 | 227,300 |
| 15 | " 25 | 37,660 | 4.95 | 27.2 | — .23 | 196,100 |
| 16 | " 25 | 35,050 | 4.80 | 25.5 | — .14 | 168,100 |
| 17 | " 27 | 30,830 | 4.83 | 22.44 | — .05 | 149,100 |

* Rate of rise or fall per hour; rising +; falling —.

As the mean velocity and area curves, which are factorial curves in making the station rating curve, do not under ordinary conditions follow any mathematical law, the discharge curve will not generally be a mathematical curve. For ordinary streams it is made up of a series of parabolas. For many streams it approaches very nearly the form of a single parabola. Some engineers construct the rating curve by mathematical treatment, by use of least squares. In ordinary practice, however, this is not considered practicable, as the graphic method can be used with greater ease and speed and gives results as close as the data will justify.

If the engineer is familiar with the conditions in the channel at and near the station, a few careful measurements, well distributed, may serve to define the curve of mean velocity. If slope observations are taken and the point of zero flow is determined, a very good approximate rating can be made from two or three measurements.

Ordinary cross-section paper, with discharge and $A\sqrt{d}$ as coordinates.— In the construction of a rating curve based on a limited number of measurements, it is evident that it is much safer to extend a straight line than a curve. Investigations have consequently been made of the component parts of the discharge curve for a quantity which is readily measurable, and to which the discharge is approximately proportional, for use in conjunction with the discharge as a coordinate for plotting the discharge curve. The area times the square root of the mean depth of the stream, $A\sqrt{d}$, has been found by J. C. Stevens to be such a quantity.

or Chezy's?

From Kutter's formula $Q = Ac_1/\bar{R}s$ may be written $Q = (A_1/\bar{R})(c_1/s)$. If (c_1/s) is constant or approximately so, then Q varies directly as (A_1/\bar{R}) , and consequently when these two quantities are plotted as coordinates the result is a straight line. c is a function of s, R , and n . R increases with the stage. It is also a matter of observation that s in general increases with the stage, the relative change being small for high stages. For comparatively large slopes the effect of s on c is insignificant, or, to quote Trautwine, "for slopes greater than .01 the coefficient c is the same as for that slope." For flat slopes s has an appreciable effect on c . For a value of R greater than 3.28 feet or 1 meter, c




FIG. 26. —Rating Curve showing Discharge as a Function of $A_v d$.

and s vary inversely, while c is of itself a decreasing function of s and an increasing function of R . Hence the product of c_1/\bar{s} may remain practically constant for a given set of conditions, but for values of R less than 3.28 feet, c is an increasing function of both s and R , and hence the product of c_1/\bar{s} is not a constant. The value of this method lies chiefly in making estimates for the higher stages and is not so generally applicable to shallow streams.

Based on the above conditions and assumptions, discharge curves may be plotted with Q and A_1/\bar{R} as coordinates. It has been found, however, that d , the mean depth of cross-section, can be substituted

for R and give practically the same results in plotting. It is also easier to determine d than R .

In the application of this method (fig. 26) plot the elevation of the bed of the stream above gage datum and thereby obtain a cross-section. From the cross-section prepare a table giving widths, areas, mean depths and values of $A\sqrt{d}$ for each foot or half-foot of gage heights. Widths may be scaled directly from the cross-section. The table of areas is quickly prepared by first computing the area for one gage height about midway of the range of stage. For increasing gage heights add successively the areas of trapezoids formed by the widths and gage-heights interval. For decreasing gage heights subtract these successive areas.

After the table of areas has been prepared the quantities $A\sqrt{d}$ (or $A\sqrt{\frac{A}{w}}$), where w = width, can be read directly with a slide rule. On

cross-section paper draw the curve of $A\sqrt{d}$, using gage heights as abscissas, as shown in the diagram. After this curve is drawn the values of $A\sqrt{d}$ are no longer required. Lay off a scale of discharge as abscissas. To plot a discharge measurement project from the horizontal scale of gage heights to the curve of $A\sqrt{d}$, thence horizontally to intersect the given discharge as indicated by dotted line. Points so plotted will generally conform to a straight line.

The illustration (fig. 26) also shows the station rating curve, in which the same scale of discharges is used with gage heights as ordinates, shown on the left.

The straight line marked "discharge as a function of $A\sqrt{d}$ " does not pass through the origin for reasons elsewhere stated as to the effect on the coefficient c of the rapidly changing slope at this stage. Therefore, when but a single measurement is at hand the line should be drawn to intersect the scale of $A\sqrt{d}$ at some point above the origin. This point has been found to correspond approximately to the gage height at which the mean depth of flowing water is between 1 and 2 feet.

In the case, frequently encountered, where there is ponded water at the gage height of zero discharge, the corresponding value of $A\sqrt{d}$ should be subtracted from the tabular values of this quantity before plotting. The gage height for which the discharge is zero can be determined by a careful examination, with levels or soundings, of the bed below the gaging section. Even in this case the straight line discharge curve will pass above the origin and should be treated as above outlined for conditions where ponded or dead water does not exist.

Logarithmic cross-section paper.—Cross-section paper graduated logarithmically may also be used in plotting the rating curve. On this

paper discharges and gage heights are plotted as coordinates. The curve resulting from the points so plotted is practically a straight line and has a corresponding advantage for extension. Logarithmic paper may give reliable results in the hands of an experienced operator, but if it is not properly and intelligently used large errors may arise. It is best used for channels with uniform conditions of cross-section and flow. The use of logarithmic cross-section paper is fully discussed on pages 129 to 137.

RATING OR DISCHARGE TABLE.

After the station rating curve has been constructed the next step in the computation of daily discharge is to prepare the station rating table, which gives the discharge of the stream at any stage. This table (see page 108) will be constructed either for tenths, half-tenths, or hundredths of gage height, according to the readings of the gage to which it is to be applied. The table is made by first taking the discharges for various gage heights directly from the station rating curve. These discharges are then so adjusted that the differences for successive stages shall be either constant or gradually increasing, but never decreasing unless the control of the station has changed.

The station rating table so obtained is applied to the gage heights to obtain the corresponding discharges.

APPLICATION OF RATING TABLE TO GAGE HEIGHTS.

The first step in using records of daily gage readings in connection with a rating table to compute the flow of a stream, is to ascertain the degree of refinement necessary to give a sufficiently accurate determination of discharge. In general the refinement will vary inversely with the stage and is determined by a study of the discharge rating table.

Gages are usually read to hundredths, quarter tenths, half tenths, or tenths. The resulting absolute error of observation in individual readings are shown by the following table:

Absolute errors for individual gage readings.

| | Maximum error. | Average error. | |
|--------------------------------------|----------------|----------------|--|
| | <i>Foot.</i> | <i>Foot.</i> | <i>Fractional parts of Tenths of a foot.</i> |
| Readings to hundredths | 0.005 | 0.0025 | $\frac{1}{40}$ |
| Readings to quarter-tenths | .012 | .006 | $\frac{1}{16}$ |
| Readings to half-tenths | .025 | .012 | $\frac{1}{8}$ |
| Readings to tenths | .05 | .025 | $\frac{1}{4}$ |

For staff and chain gages 2 per cent has been selected, more or less arbitrarily, as the limit of allowable average error in a daily discharge due to errors in the mean daily gage height. The table indicates that the maximum error for any one day is twice the average error, so that the maximum error for any one day may be 4 per cent. According to the principles of least squares, for fluctuating stages the average error in the monthly mean discharge resulting from a 2 per cent average error in mean daily discharge is about one-third of 1 per cent.

The refinement to which the mean daily gage-height records must be used—whether to hundredths, half tenths, or tenths—in order to obtain this limit of accuracy of discharge at any given stage, will depend on the percentage of difference in discharge for such least differences in gage readings at that stage, as shown by the rating table.

In determining this refinement proceed as follows and enter the results in a table of the form given below, in which the Potomac at Point of Rocks, which is read twice daily to tenths, is used as an example.

Limits of accuracy in the use of gage readings.

| Station | Present Readings | | Minimum Gage Height | Minimum discharge | Error in discharge due to error of .10 ft. in the gage at minimum discharge | Use gage heights to— | | |
|------------------------------------|------------------|------|---------------------|-------------------|---|----------------------|---------------------|--------------|
| | Per day | To | | | | Hundredths below | Half tenths between | Tenths above |
| | No. | Foot | Feet | Sec. ft. | Per cent | Feet | Feet | Feet |
| Potomac River, Point of Rocks, Md. | 1 | 0.1 | 0.50 | 900 | 21 | 1.0 | 1.0-2.0 | 2.0 |

Enter in column 1, the name of station; in column 2, the number of readings per day; in column 3, smallest subdivision used in reading gage; in column 4, the minimum known gage height; in column 5, minimum discharge as taken from the discharge rating table or curve; and in column 6, the percentage of error in the minimum discharge due to an error of .10 of a foot in gage height. The discharge rating table (p. 108) shows that the minimum discharge is 900 second-feet and occurs at gage height .50 foot. The difference per tenth between gage heights .50 and .60 is 190 second feet, or 21.1 per cent of the minimum discharge.

The limits of stage between which it is necessary to use mean daily gage heights to hundredths, half-tenths, and tenths, respectively, in order not to introduce an average error of over 2 per cent in the daily discharge are shown in columns 7, 8 and 9 and are determined by trial by testing values from the discharge rating table (p. 108) at selected half-foot intervals as follows:

(a) Testing at the 2-foot gage height for gage records to tenths. The difference between the discharges at 2.00 feet and 2.10 feet is 360 second-feet. The average error of a mean daily record to tenths is one-fourth tenth (see table, p. 104). Therefore at gage height 2.00 feet the average error for such record, expressed in second-feet, is $\frac{360}{4} = 90$ second-feet, which is 1.8 per cent of 5,020 second-feet, the discharge at the 2-foot stage. Therefore, it is not necessary to use gage-height records closer than .10 foot above the 2-foot stage, as above this stage the average error is less than 2 per cent, which is the allowable error.

(b) Testing at the 1.5-foot gage height for gage records to tenths. The difference at this stage is 300 second-feet per tenth. $\frac{300}{4} = 75$ second-feet, which is 2.2 per cent of 3,400 second-feet, the discharge at the 1.5-foot stage. Therefore all gage-height records below 2.00 feet should be used closer than tenths.

(c) Testing at the 1.5-foot gage height for gage records to half-tenths. The difference at this stage is 300 second-feet per tenth. The average error of a mean daily record to half-tenths is $\frac{300}{8} = 38$ second-feet, which is 1.1 per cent of 3,400 second-feet, the discharge at 1.5 foot stage. Therefore all gage-height records between 1.5 and 2.00 feet should be used to half-tenths.

A continuation of this analysis shows that in order to keep the discharge error resulting from lack of refinement in gage readings, below 2 per cent, the gage at Point of Rocks should have been read to hundredths at all stages and used to hundredths below the 1-foot stage, to half-tenths between 1.0 feet and 2.0 feet, and to tenths above 2.0 feet, instead of to tenths for all stages, as shown in the table of daily gage heights, page 108.

An analysis of the gage readings for each station, as thus outlined, is essential if accurate and consistent results are to be obtained. It will show, not only the limits of accuracy to which gage records should be used, but also the refinement to which gage heights should be observed. In order to avoid confusion in reading, all observations should be made to the greatest refinement required for any stage, and in the computations the hundredths should be discarded as described above.

For automatic gage records the same procedure is followed except that the allowable error should be 1 per cent.

For stations with shifting channels the methods of analysis above described can be used only in a general way.

In practice the limits of use of gage heights can be readily determined by the following rules:

Find the stage at which the difference in discharge per tenth is 8 per cent of the discharge at that stage. Gage heights above this stage should be used to tenths.

Find the stage at which the difference in discharge per tenth is 16 per cent of the discharge at that stage. Gage heights below this stage should be used to hundredths.

Gage heights between the first and second stages should be used to half-tenths.

The following tables and figs. 24 and 26 illustrate the method of determining daily discharge of streams with permanent beds:

Discharge measurements of Potomac River at Point of Rocks, Md., in 1902-7.

| Date. | Hydrographer. | Area of section. | Mean velocity. | Gage height. | Discharge |
|----------|-------------------------------|------------------|---------------------|--------------|-----------------|
| 1902 | | <i>Sq. ft.</i> | <i>Ft. per sec.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> |
| June 22 | Newell and Paul..... | 2,897 | 1.01 | 1.25 | 2,921 |
| Sept. 2 | E. G. P..... | 2,356 | .73 | .87 | 1,717 |
| 1903 | | | | | |
| Mar. 12 | E. C. Murphy..... | 6,600 | 2.86 | 4.84 | 18,880 |
| Apr. 17 | Hoyt and Paul..... | 17,250 | 5.01 | 13.70 | 86,420 |
| Apr. 17 | Hoyt and Stokes..... | 16,500 | 4.88 | 13.10 | 80,520 |
| Apr. 18 | Hoyt and Stokes..... | 12,180 | 4.44 | 9.60 | 54,080 |
| Sept. 14 | Paul and Sawyer..... | 2,950 | 1.28 | 1.50 | 3,770 |
| Nov. 9 | W. C. Sawyer..... | 2,590 | .83 | 1.12 | 2,140 |
| 1904 | | | | | |
| July 11 | Hoyt and Grover..... | 5,500 | 2.50 | 3.87 | 13,750 |
| 1905 | | | | | |
| Mar. 13 | Tillinghast and Comstock..... | 8,000 | 3.33 | 6.56 | 28,640 |
| June 20 | Grover and Lyman..... | 2,727 | 1.10 | 1.29 | 2,997 |
| Oct. 30 | G. F. Harley..... | 3,532 | 1.38 | 2.05 | 4,889 |
| Nov. 9 | G. F. Harley..... | 2,703 | .94 | 1.20 | 2,531 |
| Nov. 9 | Harley and Stewart..... | 2,703 | .91 | 1.20 | 2,467 |
| 1906 | | | | | |
| May 30 | R. Follansbee..... | 3,351 | 1.16 | 1.70 | 3,892 |
| Dec. 7 | R. H. Bolster..... | 3,180 | 1.40 | 1.76 | 4,450 |
| 1907 | | | | | |
| Mar. 15 | R. H. Bolster..... | 21,460 | 5.31 | 16.95 | 114,000 |

RIVER DISCHARGE.

Rating table for Potomac River at Point of Rocks, Md., from April 1, 1902, to December 31, 1906.

| Gage height. | Dis-charge. | Difference. | Gage height. | Dis-charge. | Difference. | Gage height. | Dis-charge. | Difference. |
|--------------|-----------------|-----------------|--------------|-----------------|-----------------|--------------|-----------------|-----------------|
| <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Sec.-ft.</i> |
| 0.50 | 900 | | 2.40 | 6,520 | 390 | 4.60 | 17,430 | 1,160 |
| .60 | 1,090 | 190 | .50 | 6,920 | 400 | .80 | 18,610 | 1,180 |
| .70 | 1,295 | 205 | .60 | 7,330 | 410 | 5.00 | 19,820 | 1,210 |
| .80 | 1,515 | 220 | .70 | 7,750 | 420 | .20 | 21,060 | 1,240 |
| .90 | 1,750 | 235 | .80 | 8,180 | 430 | .40 | 22,300 | 1,240 |
| 1.00 | 2,000 | 250 | .90 | 8,620 | 440 | .60 | 23,560 | 1,260 |
| .10 | 2,260 | 263 | 3.00 | 9,070 | 450 | .80 | 24,840 | 1,280 |
| .20 | 2,530 | 270 | .10 | 9,530 | 460 | 6.00 | 26,140 | 1,300 |
| .30 | 2,810 | 283 | .20 | 10,000 | 470 | .20 | 27,460 | 1,320 |
| .40 | 3,100 | 290 | .30 | 10,480 | 480 | .40 | 28,780 | 1,320 |
| .50 | 3,400 | 300 | .40 | 10,970 | 490 | .60 | 30,100 | 1,320 |
| .60 | 3,700 | 300 | .50 | 11,470 | 500 | .80 | 31,460 | 1,360 |
| .70 | 4,010 | 310 | .60 | 11,980 | 510 | 7.00 | 32,820 | 1,360 |
| .80 | 4,330 | 320 | .70 | 12,490 | 510 | .50 | 36,340 | 3,520 |
| .90 | 4,670 | 340 | .80 | 13,010 | 520 | 8.00 | 39,980 | 3,640 |
| 2.00 | 5,020 | 350 | .90 | 13,530 | 520 | .50 | 43,740 | 3,760 |
| .10 | 5,380 | 360 | 4.00 | 14,070 | 540 | 9.00 | 47,600 | 3,860 |
| .20 | 5,750 | 370 | .20 | 15,150 | 1,080 | .50 | 51,560 | 3,960 |
| .30 | 6,130 | 380 | .40 | 16,270 | 1,120 | 10.00 | 55,600 | 4,040 |

NOTE: The above table is applicable only for open-channel conditions. It is based on discharge measurements made during 1902 to 1907. It is well defined between gage heights 1.0 foot and 17.0 feet. Above gage height 10 feet the rating curve is a tangent, the difference being 830 per tenth.

Daily gage heights and discharges of Potomac River at Point of Rocks, Md., for July to December, 1904.

| Day. | July. | | August. | | September. | | October. | | November. | | December. | |
|----------|--------------|-----------------|--------------|-----------------|--------------|-----------------|--------------|-----------------|--------------|-----------------|--------------|-----------------|
| | Gage height. | Dis-charge. | Gage height. | Dis-charge. | Gage height. | Dis-charge. | Gage height. | Dis-charge. | Gage height. | Dis-charge. | Gage height. | Dis-charge. |
| | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> |
| 1 | 1.4 | 3,100 | 1.4 | 3,100 | 0.9 | 1,750 | 0.6 | 1,090 | 0.6 | 1,090 | 0.8 | 1,515 |
| 2 | 1.3 | 2,810 | 1.3 | 2,810 | .8 | 1,515 | .6 | 1,090 | .6 | 1,090 | .8 | 1,515 |
| 3 | 1.3 | 2,810 | 1.2 | 2,530 | .8 | 1,515 | .6 | 1,090 | .7 | 1,295 | .8 | 1,515 |
| 4 | 1.3 | 2,810 | 1.2 | 2,530 | .8 | 1,515 | .6 | 1,090 | .7 | 1,295 | .8 | 1,515 |
| 5 | 1.2 | 2,530 | 1.2 | 2,530 | .9 | 1,750 | .6 | 1,090 | .7 | 1,295 | .8 | 1,515 |
| 6 | 1.5 | 3,400 | 1.2 | 2,530 | 1.0 | 2,000 | .6 | 1,090 | .7 | 1,295 | .8 | 1,515 |
| 7 | 1.5 | 3,400 | 1.3 | 2,810 | .9 | 1,750 | .6 | 1,090 | .7 | 1,295 | .8 | 1,515 |
| 8 | 1.6 | 3,700 | 1.4 | 3,100 | .8 | 1,515 | .6 | 1,090 | .7 | 1,295 | .8 | 1,515 |
| 9 | 1.6 | 3,700 | 1.5 | 3,400 | .7 | 1,295 | .5 | 900 | .7 | 1,295 | .8 | 1,515 |
| 10 | 1.7 | 4,010 | 1.4 | 3,100 | .7 | 1,295 | .5 | 900 | .7 | 1,295 | .9 | 1,750 |
| 11 | 2.9 | 8,620 | 1.3 | 2,810 | .7 | 1,295 | .5 | 900 | .7 | 1,295 | .9 | 1,750 |
| 12 | 2.6 | 7,330 | 1.3 | 2,810 | .8 | 1,515 | .6 | 1,090 | .7 | 1,295 | .9 | 1,750 |
| 13 | 3.4 | 10,970 | 1.2 | 2,530 | 1.0 | 2,000 | .7 | 1,295 | .7 | 1,295 | .9 | 1,750 |
| 14 | 3.1 | 9,530 | 1.2 | 2,530 | .9 | 1,750 | .7 | 1,295 | .8 | 1,515 | .9 | 1,750 |
| 15 | 3.0 | 9,070 | 1.1 | 2,260 | .9 | 1,750 | .6 | 1,090 | .8 | 1,515 | .9 | 1,750 |
| 16 | 2.8 | 8,180 | 1.1 | 2,260 | 1.0 | 2,000 | .6 | 1,090 | .8 | 1,515 | .9 | 1,750 |
| 17 | 2.4 | 6,520 | 1.1 | 2,260 | 1.0 | 2,000 | .5 | 900 | .7 | 1,295 | .9 | 1,750 |
| 18 | 2.0 | 5,020 | 1.0 | 2,000 | .9 | 1,750 | .5 | 900 | .8 | 1,515 | .9 | 1,750 |
| 19 | 1.8 | 4,330 | 1.0 | 2,000 | .8 | 1,515 | .5 | 900 | .8 | 1,515 | .9 | 1,750 |
| 20 | 1.6 | 3,700 | 1.0 | 2,000 | .7 | 1,295 | .6 | 1,090 | .8 | 1,515 | 1.0 | 2,000 |
| 21 | 1.4 | 3,100 | 1.0 | 2,000 | .8 | 1,515 | 1.0 | 2,000 | .7 | 1,295 | 1.0 | 2,000 |
| 22 | 1.4 | 3,100 | .9 | 1,750 | 1.0 | 2,000 | .9 | 1,750 | .7 | 1,295 | 1.0 | 2,000 |
| 23 | 1.3 | 2,810 | .9 | 1,750 | .9 | 1,750 | .8 | 1,515 | .7 | 1,295 | 1.0 | 2,000 |
| 24 | 1.3 | 2,810 | 1.0 | 2,000 | .8 | 1,515 | .7 | 1,295 | .7 | 1,295 | 1.0 | 2,000 |
| 25 | 1.3 | 2,810 | 1.0 | 2,000 | .8 | 1,515 | .7 | 1,295 | .7 | 1,295 | 1.1 | 2,260 |
| 26 | 1.4 | 3,100 | 1.2 | 2,530 | .8 | 1,515 | .7 | 1,295 | .7 | 1,295 | 1.4 | 3,100 |
| 27 | 1.4 | 3,100 | 1.1 | 2,260 | .7 | 1,295 | .7 | 1,295 | .7 | 1,295 | 1.5 | 3,400 |
| 28 | 1.4 | 3,100 | 1.1 | 2,260 | .7 | 1,295 | .7 | 1,295 | .7 | 1,295 | 1.8 | 4,330 |
| 29 | 1.5 | 3,400 | 1.0 | 2,000 | .7 | 1,295 | .6 | 1,090 | .8 | 1,515 | 1.8 | 4,330 |
| 30 | 1.5 | 3,400 | 1.0 | 2,000 | .7 | 1,295 | .6 | 1,090 | .8 | 1,515 | 1.9 | 4,670 |
| 31 | 1.5 | 3,400 | .9 | 1,750 | | | .6 | 1,090 | | | 2.0 | 5,020 |
| Total... | | 139,670 | | 74,200 | | 47,760 | | 36,080 | | 40,200 | | 68,245 |
| Mean... | | 4,505 | | 2,394 | | 1,592 | | 1,164 | | 1,340 | | 2,201 |

Monthly discharge of Potomac River at Point of Rocks, Md., for 1904.

| Month. | Discharge in second-feet. | | | | Run-off. | |
|-----------------|---------------------------|----------|-------|-------------------------|------------------|------------|
| | Maximum. | Minimum. | Mean. | Second-feet per sq. mi. | Depth in inches. | Acre-feet. |
| July..... | 10,970 | 2,530 | 4,505 | 467 | 538 | 277,300 |
| August..... | 3,400 | 1,750 | 2,394 | 248 | 286 | 147,200 |
| September..... | 2,000 | 1,295 | 1,592 | 165 | 184 | 94,730 |
| October..... | 2,000 | 900 | 1,164 | 121 | 140 | 71,570 |
| November..... | 1,515 | 1,090 | 1,340 | 139 | 155 | 79,740 |
| December..... | 5,020 | 1,515 | 2,201 | 228 | 263 | 135,300 |
| The period..... | 10,970 | 900 | 2,199 | 228 | 1.556 | 805,840 |

GAGING STATIONS WITH CHANGEABLE BEDS.

The determination of the daily discharge of streams with changeable beds is more difficult than of those with permanent beds. The method used varies with the rapidity of the changes. The base data for such determinations are the same as those used for permanent beds, but more frequent discharge measurements are necessary, as otherwise the results obtained are only roughly approximate.

PERIODICALLY CHANGING BEDS.

For stations with beds which shift slowly or are changed only during floods, station rating curves can be prepared as above described for periods between changes, and satisfactory results can be obtained with two or three measurements a month, provided measurements are taken soon after such changes take place.

CONSTANTLY CHANGING BEDS.

For streams with continually shifting beds, as the Colorado and Rio Grande, discharge measurements should be made every two or three days and the discharge for the intervening days estimated by interpolation, modified by the gage heights for these days. There are two methods of making these interpolations, the Stout and the Bolster methods, known by the names of their inventors.

Stout method.—In the Stout method an approximate station rating curve and rating table are prepared from the discharge measurements and applied to modified or so-called corrected daily gage heights. The gage heights are corrected by means of a curve (fig. 27) determined by plotting as ordinates the differences between the actual gage heights at the time of the various discharge measurements and the gage height

corresponding on the approximate curve to the respective measured discharges, and as abscissas the corresponding days of the months. Through these points an irregular curve is drawn, from which can be found the correction for days other than those on which measurements were made. The correction is positive if the discharge is greater than that given by the station rating curve, negative if less. Each daily gage height is then corrected by the amount indicated on the correction curve, and the discharge corresponding thereto is taken from the approximate rating table.

Bolster method.—In the Bolster method the discharge measurements for the entire year are first plotted with discharges as abscissas and gage heights as ordinates. The points so plotted are considered chronologically and, even though scattered, will usually locate one or more fairly well-defined curves, called standard curves (fig. 27). In general the number and position of these standard curves is determined by the radical changes in the stream bed due to floods.

When beds change very rapidly it is necessary to change the position of the rating curve from day to day, making practically a new curve daily. This daily curve is of the same form as the standard curve and is parallel to it with respect to ordinates. For a day when a measurement is made the rating curve passes through such plotted measurement. In order to locate a rating curve for other days a line connecting consecutive measurements is drawn and divided into as many equal parts as there are days intervening between the measurements, on the assumption that the change in conditions of flow between any two consecutive measurements is uniform from day to day. The daily rating curve will then pass through these points of division, and the discharge is read directly from these curves by applying to them the observed daily gage heights.

In order to facilitate the use of the method and to make it as rapid in application as the common method for permanent stations the standard curve or curves, together with a vertical line of reference, should be transferred from the original station sheet to tracing cloth, which can be readily shifted vertically to any desired position by always keeping the two reference lines coincident with each other.

In applying and modifying this method judgment must be used for long time intervals of no measurements, or for radical changes in the stream bed caused by sudden floods. The tables on pages 112-113 and figure 27 illustrate the Bolster and the Stout methods of obtaining daily discharge.



List of measurements to illustrate the Stout and the Bolster methods of determining daily discharge.

| No. | Date. | Gage height. | Discharge. |
|-----|--------|--------------|-----------------|
| | | <i>Feet.</i> | <i>Sec.-ft.</i> |
| 1 | June 1 | 2.55 | 3700 |
| 2 | 6 | .55 | 500 |
| 3 | 14 | 1.4 | 1200 |
| 4 | 22 | 1.2 | 800 |
| 5 | July 2 | 1.5 | 500 |
| 6 | 18 | 3.8 | 6460 |
| 7 | 20 | 2.2 | 2330 |
| 8 | 22 | .4 | 200 |
| 9 | 31 | .9 | 150 |

Daily gage heights and discharges to illustrate the Stout and the Bolster methods of determining daily discharge.

| Day. | June. | | | | July. | | | |
|---------|------------------------------|----------------------------------|-------------------------------|--------------------------------|------------------------------|----------------------------------|-------------------------------|--------------------------------|
| | Observed gage heights. | Discharge, Bolster method. | Corrected gage heights. | Discharge, Stout method. | Observed gage heights. | Discharge, Bolster method. | Corrected gage heights. | Discharge, Stout method. |
| | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> |
| 1 | 3.0 | 4870 | 3.3 | 4970 | 1.5 | 530 | .85 | 520 |
| 2 | 2.5 | 3580 | 2.8 | 3650 | 1.5 | 500 | .85 | 520 |
| 3 | 2.0 | 2490 | 2.3 | 2530 | 1.5 | 570 | .85 | 520 |
| 4 | 1.5 | 1610 | 1.8 | 1640 | 1.6 | 730 | .95 | 605 |
| 5 | 1.0 | 930 | 1.3 | 960 | 1.6 | 780 | 1.0 | 650 |
| 6 | .4 | 390 | .65 | 365 | 1.8 | 1050 | 1.25 | 905 |
| 7 | .6 | 510 | .85 | 520 | 1.7 | 970 | 1.2 | 850 |
| 8 | .6 | 490 | .85 | 520 | 1.7 | 1020 | 1.25 | 905 |
| 9 | .7 | 550 | .95 | 605 | 1.9 | 1320 | 1.55 | 1280 |
| 10 | .8 | 620 | 1.0 | 650 | 2.0 | 1510 | 1.7 | 1490 |
| 11 | 1.0 | 800 | 1.2 | 850 | 2.2 | 1890 | 2.0 | 1970 |
| 12 | 1.5 | 1400 | 1.65 | 1420 | 2.6 | 2720 | 2.45 | 2850 |
| 13 | 1.4 | 1240 | 1.55 | 1280 | 3.0 | 3700 | 2.9 | 3900 |
| 14 | 1.4 | 1200 | 1.5 | 1210 | 3.6 | 5440 | 3.5 | 5550 |
| 15 | 1.3 | 1020 | 1.35 | 1020 | 3.7 | 5850 | 3.65 | 6000 |
| 16 | 1.1 | 760 | 1.15 | 800 | 3.5 | 5370 | 3.5 | 5550 |
| 17 | 1.0 | 620 | 1.0 | 650 | 3.2 | 4610 | 3.2 | 4690 |
| 18 | 1.0 | 580 | .95 | 605 | 3.7 | 6150 | 3.7 | 6150 |
| 19 | 1.1 | 640 | 1.0 | 650 | 4.0 | 7080 | 4.0 | 7080 |
| 20 | 1.2 | 690 | 1.05 | 700 | 3.0 | 4160 | 3.0 | 4160 |
| 21 | 1.2 | 650 | 1.0 | 650 | 1.8 | 1640 | 1.8 | 1640 |
| 22 | 1.3 | 690 | 1.05 | 700 | .8 | 480 | .8 | 480 |
| 23 | 1.5 | 850 | 1.2 | 850 | .3 | 120 | .3 | 150 |
| 24 | 1.8 | 1170 | 1.45 | 1140 | .3 | 100 | .25 | 130 |
| 25 | 1.7 | 990 | 1.3 | 960 | .4 | 110 | .35 | 175 |
| 26 | 1.6 | 830 | 1.15 | 800 | .4 | 90 | .3 | 150 |
| 27 | 1.6 | 780 | 1.1 | 750 | .6 | 130 | .4 | 200 |
| 28 | 1.6 | 740 | 1.05 | 700 | .7 | 150 | .45 | 230 |
| 29 | 1.6 | 700 | 1.0 | 650 | .8 | 170 | .45 | 230 |
| 30 | 1.6 | 660 | .95 | 605 | .9 | 180 | .4 | 200 |
| 31 | | | | | 1.0 | 200 | .4 | 200 |
| Totals. | | 33050 | | 33400 | | 59320 | | 59930 |
| Means. | | 1102 | | 1113 | | 1914 | | 1933 |

Rating table to illustrate the Stout method of determining daily discharge.

| Gage height. | Dis-charge. | Gage height. | Dis-charge. | Gage height. | Dis-charge. | Gage height. | Dis-charge. | Gage height. | Dis-charge. |
|--------------|-----------------|--------------|-----------------|--------------|-----------------|--------------|-----------------|--------------|-----------------|
| <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Feet.</i> | <i>Sec.-ft.</i> |
| 0.00 | 60 | 1.00 | 650 | 2.00 | 1970 | 3.00 | 4160 | 4.00 | 7080 |
| .10 | 80 | .10 | 750 | .10 | 2150 | .10 | 4423 | | |
| .20 | 110 | .20 | 850 | .20 | 2330 | .20 | 4690 | | |
| .30 | 150 | .30 | 960 | .30 | 2530 | .30 | 4970 | | |
| .40 | 200 | .40 | 1080 | .40 | 2740 | .40 | 5260 | | |
| .50 | 260 | .50 | 1210 | .50 | 2960 | .50 | 5550 | | |
| .60 | 330 | .60 | 1350 | .60 | 3180 | .60 | 5850 | | |
| .70 | 400 | .70 | 1490 | .70 | 3410 | .70 | 6150 | | |
| .80 | 480 | .80 | 1640 | .80 | 3650 | .80 | 6460 | | |
| .90 | 560 | .90 | 1800 | .90 | 3900 | .90 | 6770 | | |

ICE-COVERED STREAMS.^a

Ice occurs in rivers in three forms—surface ice, anchor ice and frazil. Surface ice may occur as a complete cover, supported by the water, or bridged from bank to bank, free from or partly supported by the water, as in ice jams due to piling up of ice, or as alternate layers of ice and water. Anchor ice may be attached to the bed of the river where it has been formed, or it may be floating in suspension. Frazil usually occurs floating in suspension.

The presence of ice in a stream in any form may destroy the open-water relation of discharge to stage by causing backwater and thus increasing the stage for a given discharge. Therefore discharge measurements of a stream in which ice is present will always plot either at the left of or on the open-water curve. Under no circumstances will they plot to the right provided the measurement represents the correct flow.

It is not necessary that ice be present at the measuring section or at the normal control section to destroy the relation of stage to discharge. The existence of ice far below the control section may establish a temporary control which will affect the station rating.

The data necessary for computing flow during periods of ice are—

1. Measurements of discharge made during the period.
2. Records of stage read to the surface of the water in a hole cut through the ice.
3. Records of temperature and precipitation.
4. Full notes in regard to the ice.

The complex manner in which ice may form and the varying conditions presented by streams preclude the formulation of any method that can be universally employed to determine winter flow. In general the following methods may be used:

^a See Water-Supply Paper No. 337, U. S. Geo'l. Survey.

1. The readings of gage heights to the water surface may be directly applied to the open-water rating curve.

2. The observed gage heights may be applied directly to a special rating curve based on winter discharge measurements and gage heights to water surface.

3. Discharge measurements may be used in connection with gage heights and with data showing climatic conditions and the occurrence of ice. This method may be applied either by the eye or graphically, as will be explained, for determining corrections to the gage heights necessary for making the open-channel rating curve applicable.

FIRST METHOD.

The use of the first method to determine the daily discharge of a frozen stream—the application of water-surface gage readings to the open-water rating curve—is advisable only when the stream is open at the control section and no backwater exists at the gage.

If the control section is entirely free from ice the relation between slope, stage, and discharge will not be appreciably changed even by complete ice cover between the control section and the gage.

In using this method the engineer should closely inspect the gage-height records and compare them with temperature records to detect the presence of backwater. If discharge measurements made in several winters have shown that ice rarely occurs at the control section and that the regular open-water curve is applicable fewer measurements are needed with this method than with any other. An open-control section, however, with ice above, implies as a rule that the control section is at rapids at which anchor ice is likely to form. In order to detect the presence of anchor ice during extremely cold periods the gage should be read twice a day. Readings higher in the morning than in the afternoon indicate the presence of anchor ice, and care must be taken to read the gage soon after the point of maximum daily temperature, when the control section is likely to be clear.

SECOND METHOD.

The conditions favorable to the use of the second method—in which observed gage heights are applied directly to a special rating curve based on winter discharge measurements and gage heights to the water surface—are most likely to be found on the larger rivers, where the slope and cross-section may be fairly uniform for long stretches. In general, however, this method should be used with great care and the period of

applicability of the curve should be closely determined by discharge measurements.

On a large stream that freezes uniformly and that varies little in flow all discharge measurements made when the ice has reached its permanent condition may plot on a curve, but it is evident that this curve will not correctly represent the relation of stage to discharge in the period of transition from open water to solid ice, and vice versa. It will also not represent conditions if between the times of measurement the character of the ice cover has changed greatly as a result of changes in temperature.

If backwater is caused by a combination of anchor and surface ice, discharge measurements made at certain times might give a smooth curve that would in reality not apply except on the days of measurement.

This method should be used only when many discharge measurements have been found to plot on a smooth curve and when conditions of temperature and ice are stable for long periods.

THIRD METHOD.

Eye method.—The method most commonly employed at the present time to determine the flow of streams either partly or completely covered with ice is that which utilizes the discharge measurements and data regarding climatic conditions and the occurrence of ice in connection with observed gage heights by means of eye-inspection of records of temperature, precipitation, and gage heights, estimating the daily discharge for the period between times of measurement, and adjusting the determinations by comparing with results obtained at near-by stations. The monthly mean of such determinations is also compared with monthly means at adjacent stations in order that any large error may be detected.

The accuracy of this method depends largely on the uniformity of stream flow between times of measurements, the number of measurements, and the engineer's knowledge of general conditions. Care must be taken that the discharge, as estimated, is not greater than would be given by the application of gage heights to the open-water rating curve. In general this method should give more accurate results than the second method, because it considers the time and temperature factors.

The method will give good results at stations in localities where temperatures are fairly constant over long periods of time and where the flow is affected by surface rather than by anchor ice. Under such conditions fewer measurements and gage readings are required than at

stations situated where climatic conditions are irregular. Temperature records from the nearest Weather Bureau station are generally sufficient.

The disadvantage of this method is that it is impossible to check its results, as no record is left of steps employed.

Graphic method.^a—As ice causes backwater it is only necessary to determine the magnitude of the backwater effect in order to find the true flow at a given stage. Since the formation of ice is due entirely to temperature, the amount of backwater will in general vary with temperature.

The magnitude of the backwater effect at any given time can be determined by measurements of discharge. If such measurements are made at stated intervals during the winter the backwater effect between times of measurement can be determined by constructing a curve of backwater. In constructing this curve (see fig. 28) proceed as follows:

1. Plot the observed daily gage heights.
2. Plot the mean daily temperatures.
3. Plot the daily precipitation.
4. Plot on the curve of observed daily gage heights the gage heights corresponding to the measured discharges as determined from the open-water rating table. The differences between these gage heights and the observed gage heights measure the backwater effects for the days in question.
5. Plot the backwater effects as determined under 4 and through these plotted points construct a backwater curve, following the same general shape as the inverted temperature curve, taking into account the daily precipitation (if rain), ice jams, and other unusual conditions that may affect the records of stage.
6. From the backwater curve construct the curve of corrected gage heights, from which the true discharge can be obtained by applying the open-water rating table.

Aside from giving more accurate results, this method has an advantage over any other method in furnishing a complete record of all the steps taken, thus making it possible for a second person to review or check the estimates. The accuracy of the results obtainable by this method will depend on the frequency of the discharge measurements. When winter conditions are comparatively constant, fewer measurements will be required, as the principal uncertainties occur during transition periods from cold to warm weather.

A special form, see fig. 29, is desirable for use in computing winter flow.

^aThe graphic method was first proposed by W. G. Hoyt, Assoc. M. Am. Soc. C. E., Eng. News Vol. 69, pp. 725-727, Apr. 10, 1913.




FIG. 28.—Gage height, backwater, temperature and precipitation curves. Rainy River, International Falls, Minn.

This method follows somewhat the Stout method (pp. 109-110) of determining the flow in shifting channels in using a single rating curve and correcting the observed gage heights to apply to the curve. In the

COMPUTATION OF FLOW DURING WINTER PERIOD OF _____ RIVER
AT _____
NEAR _____ Month of _____ 191__

| DAY | Observed | | | | | | | Computed | | | |
|-----|----------------------|---------------------|----------------|-------------|-----|------|---------|----------------|-----------------------------------|-----------------------|----------------------------------|
| | Water height at gage | | | Temperature | | | Weather | Ice at control | Results of discharge measure made | Effective gage height | Estimated discharge, second-feet |
| | Morning Time | Afternoon Height | Mean Height | High | Low | Mean | | | | | |
| 1 | | | | | | | | | | | |
| 2 | | | | | | | | | | | |
| 3 | | | | | | | | | | | |
| 4 | | | | | | | | | | | |
| 5 | | | | | | | | | | | |
| 6 | | | | | | | | | | | |
| 7 | | | | | | | | | | | |
| 8 | | | | | | | | | | | |
| 9 | | | | | | | | | | | |
| 10 | | | | | | | | | | | |
| 11 | | | | | | | | | | | |
| 24 | | | | | | | | | | | |
| 25 | | | | | | | | | | | |
| 26 | | | | | | | | | | | |
| 27 | | | | | | | | | | | |
| 28 | | | | | | | | | | | |
| 29 | | | | | | | | | | | |
| 30 | | | | | | | | | | | |
| 31 | | | | | | | | | | | |

| | | |
|----------------|----------|-------------|
| Mean discharge | Sec. ft. | Total |
| to | | Mean |
| to | | Computed by |
| Maximum | | Checked by |
| Minimum | | |

FIG. 29.—Proposed computation sheet.

Stout method the correction is based almost entirely on discharge measurements; in this ice method time and temperature are factors, as well as discharge measurements.

Application of graphic method.—Many streams in the northern and western States are not completely covered with ice throughout the winter months. At many places the ice on a stream may extend but a short distance from the banks, leaving an open channel in the center; at others the current may be so swift that the channel remains entirely open throughout the winter. Such conditions are common in hilly or mountainous regions, where stream gradients change rapidly, and may exist in the vicinity of gaging stations to such an extent as to make it impossible to estimate discharge by methods that are applied to streams

that are completely ice covered. For example, the channel may be open at the gage or at the control below, but the stage may be materially affected by the presence of anchor ice; or, if complete ice cover exists below the natural control sections, ice jams may form, creating a temporary ice control which produces backwater at the gage. If the stream is frozen along the banks at the gage and at the control below, but is open in the center, the gage readings are affected by ice jams at the control and by changes in the conditions along the banks.

If a stream is deep and sluggish and under complete ice cover for a considerable distance above a gage located at a riffle, the gage readings may not be affected by ice because the water coming from beneath the ice is at a temperature sufficiently high to prevent the formation of ice at the control section.

The extent of these effects depends on the natural condition of the channel and on the general condition of the ice, the latter depending largely on temperature. Each station where such conditions exist, singly or in combination, presents a problem that can be solved only after a careful study of all the factors.

At a station located in a comparatively sluggish stretch of a stream where the channel is partly open throughout the winter and the control is a riffle the gage heights will be materially affected by anchor ice, which will form at temperatures of zero and below. The amount of anchor ice will depend on the roughness of the channel and the velocity of the current and will tend to increase as the temperature falls and decrease as the temperature rises, disappearing entirely as the temperature approaches 32°. As the variation in daily temperature may have an important effect on the amount of anchor ice formed, and therefore on the fluctuations in stage at the station, a record of the maximum and minimum temperatures is necessary to arrive at a proper interpretation of variation in the gage heights caused by anchor ice. It is also necessary to have a more complete record of the gage heights at stations of this character than at stations where complete ice cover is formed. At least two readings should be made each day as nearly as possible at the time of maximum and minimum temperatures. Careful observations should be made to determine the maximum temperature at which anchor ice forms and at which it may be expected to disappear, and the relation between the increase of the anchor ice and the decrease in temperature. On days when the temperature rises above this maximum, if other conditions are normal, it may be assumed that no anchor ice exists and that the gage heights at or immediately following the time of maximum temperature are reliable. With this information

available it is possible to determine the corrections to be made to the gage heights in order that they may be applied to the open-channel rating curve. As a check on the gage corrections a number of discharge measurements should, if possible, be made at different temperatures.

On a stream with small slope the formation of anchor ice may create a reservoir in which a considerable part of the flow may for a time be stored. Discharge measurements made during that time will indicate a flow less than the natural flow of the river; but measurements made while the anchor ice is going out, or after it has gone out and before the river has returned to its normal stage, will indicate a flow greater than the normal flow of the river, because of the release of the water that had been held in storage by the anchor ice. It is doubtful whether any corrections can be determined and applied to discharge measurements made under such conditions, which will recur whenever anchor ice forms at the gaging station or at points above. The measurements should if possible be made when the stage is normal.

If there is in the vicinity of the station a section in which the current is swift and the channel remains open all winter, a gage should be installed, as at many stations gage readings in open sections with high velocity will indicate the discharge during periods of extreme low temperature in which the regular gage will be affected by ice. The flow at such stations should be computed from the observations at the temporary gage, but the station gage should be read regularly to obtain a record for comparison.

Whenever possible stations for winter records should be established at the outlets of lakes or in the vicinity of large springs. The water at such places is usually at a relatively high temperature, and if rapids are present a site can usually be found at which the channel remains open throughout the winter, even during periods of extremely low temperature.

COMPUTATION OF OTHER VALUES OF DISCHARGE AND RUN-OFF.

The quantity of water flowing in a stream is expressed by various terms or units, each of which is associated with a certain class of work. These terms may be divided into two classes—those which represent a rate of flow, or the discharge, as second-feet, gallons per minute, miner's inch, and second-feet per square mile; and those which represent actual quantities of water, or the run-off, as depth in inches and acre-feet.

UNITS OF DISCHARGE.

The second-foot.—The standard term for expressing discharge is the second-foot. As the second-foot is a unit of rate of flow and is in itself indefinite as regards duration, it must be used in connection with some unit of time, as a day, week, month, or year, in which event the term means that for each second during the period of time selected the flow averaged so many cubic feet per second. This has generally been considered the fundamental unit of discharge and from it other terms of discharge and run-off are usually computed, the conversion to other units being a simple arithmetical process, usually made by means of tables specially prepared for the purpose.

Gallons per minute.—Gallons per minute is generally used in connection with pumping and city water supply.

Miner's inch.—The miner's inch is usually defined as the quantity of water which passes through an orifice one inch square under a fixed head, which varies locally. It has been commonly used by miners and irrigators throughout the West, and is defined by statute in many States. Owing to the confusion caused in measuring the miner's inch, and to the fact that as formerly defined by size of orifice and head it was not exact, it is now defined as a certain part of a second-foot, usually $\frac{1}{16}$ or $\frac{1}{8}$.

Second-feet per square mile.—Second-feet per square mile is the average number of cubic feet of water flowing per second from each square mile of area drained, on the assumption that the discharge is distributed uniformly both as regards time and area. It is found by dividing the mean discharge in second-feet by the drainage area.

UNITS OF RUN-OFF

Run-off in inches.—Run-off in inches is the depth to which a plane surface equal in extent to the drainage area would be covered if all the water flowing from it in a given period were conserved and uniformly distributed thereon. It is used for comparing run-off with rainfall, which is usually expressed in depth in inches.

Acre-foot.—An acre-foot is equivalent to 43,560 cubic feet, and is the quantity required to cover an acre to the depth of one foot. It is commonly used in connection with storage. There is a convenient relation between the second-foot and the acre-foot. One second-foot flowing for twenty-four hours will deliver 86,400 cubic feet, or approximately 2 acre-feet. One acre-foot equals 325,851 gallons, or a million gallons is somewhat more than 3 acre-feet.

On pages 173-175 are given conversion tables for the various units of discharge and run-off.

ACCURACY OF STREAM-GAGING DATA.^a

In considering the accuracy that can be expected and obtained in stream-gaging data, it must be remembered that both the total flow of a stream and its distribution over the drainage area are constantly changing and that exact conditions existing at any time may probably never occur again. Therefore the flow that may be expected in the future for a given stream can be determined only by a study of a series of records extending over a long time. From these records it is possible to obtain information which will show the conditions of flow to be expected in the future. Records of a reasonable degree of accuracy that extend over a considerable period of time are consequently of much more value than extremely accurate data covering a short period.

The sources of error in estimates of stream flow may be divided into four classes. Most of these errors are readily within the control of the engineer and can be eliminated by careful work. A few, however, can be eliminated only by the expenditure of considerable time and money. A list of the sources of errors is given to assist the engineer in investigating discordant results.

1. Gage height errors, due to: (a) change of relation between the gage reading and true height above gage datum, (b) error in reading gage by observer, (c) fluctuation of water stage between readings, and (d) error due to lack of refinement in reading.

2. Errors of measurement: (a) instrumental errors, (b) velocity errors, (c) area errors, and (d) computation errors.

3. Errors due to changes in conditions: (a) ice conditions, (b) shifting stream bed, (c) backwater effect of dams, and (d) temporary obstructions.

4. Computation errors: (a) errors due to fundamental assumptions, (b) errors of construction and extension of curves, (c) errors due to incorrect period of application of curve, and (d) errors due to changed condition of flow (which may or may not be shown by measurement).

DETERMINATION OF DURATION OF FLOW AND HORSEPOWER.

One of the first steps in investigations for developments which will utilize the flow of streams is the determination of the water supply that can be expected. This includes data in regard to the absolute minimum flow, the average minimum flow, and the maximum flow. For each

^a See U. S. Geol. Survey Water-Supply Paper No. 95.




FIG. 30.—Hydrograph and Curve of Duration of Flow for 1904, Potomac River at Point of Rocks, Md.

case the duration as well as the quantity of the flow is essential. In order to obtain a reliable idea of the conditions of flow that may be expected, several years' records of daily flow should be available for study and comparison.

The duration of flow for a given year may be determined by tabulating, as shown in the following table, the values of the various daily flows in order of their magnitude, and then tabulating the number of days of the year on which each flow occurs. The sum of the numbers in the "Number of days" column up to any given flow will give the number of days when the flow is less than that indicated in the "Discharge" column, or the number of days deficiency. The column should be filled out showing deficiency for each discharge.

By plotting the discharge as abscissas and the number of days deficiencies as ordinates, a curve (fig. 30) can be constructed which shows the number of days during the year when the discharge is below any given amount.

The horsepower corresponding to the various discharges can then be computed and tabulated on the sheets with the discharge, which will show the number of days when an auxiliary will have to be used for given development. In computing the horsepower the loss of head caused by backwater, if any, should be taken into account.

Discharge and horsepower table for Potomac River at Point of Rocks, Md., for 1904.

| Discharge in sec.-ft. | Horse- power (80% eff.) per foot fall. | Number days duration between consecutive values of discharge in first column. | | | | | | | | | | | | Days of deficient discharge. | |
|--------------------------|--|--|------|--------|--------|------|-------|-------|---------|-------|------|------|------|------------------------------------|---------|
| | | Jan. | Feb. | March. | April. | May. | June. | July. | August. | Sept. | Oct. | Nov. | Dec. | | Totals. |
| 900 | 82 | .. | .. | .. | .. | .. | .. | .. | .. | 0 | .. | .. | 0 | 6 | |
| 990 | 90 | .. | .. | .. | .. | .. | .. | .. | 6 | .. | .. | .. | .. | 23 | |
| 1,100 | 100 | .. | .. | .. | .. | .. | .. | .. | 15 | 2 | .. | .. | 17 | 58 | |
| 1,320 | 120 | .. | .. | .. | .. | .. | .. | .. | 8 | 7 | 20 | .. | 35 | 86 | |
| 1,540 | 140 | .. | .. | .. | .. | .. | .. | .. | 10 | 1 | 8 | .. | 28 | 107 | |
| 1,760 | 160 | .. | .. | .. | .. | .. | .. | 3 | 7 | 1 | .. | 10 | 21 | 126 | |
| 1,980 | 180 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 140 | |
| 2,200 | 200 | .. | .. | .. | .. | .. | 1 | 8 | 5 | 1 | .. | 5 | 19 | 161 | |
| 2,750 | 250 | .. | .. | .. | .. | .. | 12 | 1 | .. | .. | .. | 1 | 21 | 196 | |
| 3,300 | 300 | .. | .. | .. | .. | .. | 7 | .. | .. | .. | .. | 1 | 35 | 207 | |
| 3,850 | 350 | 17 | .. | .. | 3 | .. | 5 | 8 | 1 | .. | .. | 1 | 35 | 210 | |
| 4,400 | 400 | 2 | .. | .. | 3 | .. | 2 | 2 | .. | .. | .. | 2 | 11 | 223 | |
| 4,950 | 450 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 1 | 3 | 249 | |
| 5,500 | 500 | .. | .. | 1 | 4 | 1 | 3 | 1 | .. | .. | .. | 1 | 13 | 268 | |
| 6,000 | 600 | 1 | .. | 7 | 5 | 10 | 2 | 1 | .. | .. | .. | .. | 26 | 282 | |
| 7,700 | 700 | .. | .. | 4 | 4 | 6 | 4 | 1 | .. | .. | .. | .. | 19 | 296 | |
| 8,800 | 800 | .. | 2 | 3 | 1 | 4 | 2 | 2 | .. | .. | .. | .. | 14 | 305 | |
| 9,900 | 900 | 2 | 1 | 4 | 3 | 1 | 2 | .. | .. | .. | .. | .. | 14 | 322 | |
| 11,000 | 1,000 | 2 | 3 | 2 | .. | .. | 1 | 1 | .. | .. | .. | .. | 9 | 333 | |
| 13,200 | 1,200 | 1 | 7 | 3 | 3 | 2 | 1 | .. | .. | .. | .. | .. | 17 | 339 | |
| 15,400 | 1,400 | 1 | 3 | 3 | .. | 2 | 2 | .. | .. | .. | .. | .. | 11 | 344 | |
| 17,600 | 1,600 | .. | 1 | 3 | .. | .. | 2 | .. | .. | .. | .. | .. | 6 | 351 | |
| 19,800 | 1,800 | .. | 3 | 1 | .. | 1 | .. | .. | .. | .. | .. | .. | 5 | 358 | |
| 22,000 | 2,000 | 2 | 1 | 2 | .. | .. | 2 | .. | .. | .. | .. | .. | 7 | 363 | |
| 27,500 | 2,500 | .. | 4 | 1 | .. | 2 | .. | .. | .. | .. | .. | .. | 7 | 366 | |
| 33,000 | 3,000 | .. | 3 | .. | 1 | .. | 1 | .. | .. | .. | .. | .. | 5 | 366 | |
| 38,500 | 3,500 | 1 | 1 | .. | .. | .. | 1 | .. | .. | .. | .. | .. | 3 | 366 | |
| Total days..... | | 31 | 29 | 31 | 30 | 31 | 30 | 31 | 31 | 30 | 31 | 30 | 31 | 366 | |

SUGGESTIONS FOR ESTIMATING DISCHARGE.

The engineer is often called upon for estimates of flow of streams on which few if any measurements of discharge have been made. In such cases it is necessary to prepare estimates of discharge and run-off for the stream basin by comparison of that basin with others for which records are available.

When no measurements of discharge are available the estimates are made by determining from records at other stations the probable discharge and run-off per square mile from the area under consideration. This multiplied by the drainage area gives the discharge. Such comparisons can be safely made, however, only when the streams used are in the same section of the country and are similar in character. The table, pp. 146-149, give the run-off per square mile from areas in the northeastern United States.

When few measurements are available coefficients may be determined by means of which the discharge can be computed from the records at a neighboring station.

Rainfall data are of use as a check on estimates of flow, and they also show years of high and low water. As noted in Chapter VI, care should be exercised in their use.

HYDROGRAPHS.

In order to show graphically the daily and seasonal distribution of flow of a stream for comparative purposes, hydrographs (fig. 30) are prepared by plotting the daily discharge for each day during the year and connecting the points so plotted by a curve. These curves are of use not only in studying the variations in flow from year to year, but may also be used in storage problems, where the total quantity of water is an essential factor. The mass curve may also be used to advantage in the study of storage. (See Water-Supply Paper No. 197, U. S. Geol. Survey.)

MEASUREMENT OF DRAINAGE AREAS FROM MAPS.

In connection with most hydrologic studies it is necessary to obtain an estimate of the area of the drainage basin under consideration, and it will usually be necessary for the engineer to measure such areas.

Accompanying most planimeters are tables giving either (1) the proper settings of the arm for maps of various scales so that the planimeter readings will give the area directly, or, (2) the settings so that the readings will give square inches and coefficients to be used in con-

nection with maps of various scales for reducing these readings to square miles. In measuring drainage areas, however, it is more satisfactory to calibrate the planimeter, with the arm at any setting, directly from the map on which the area is to be measured rather than to use those tables. This method is applicable to maps constructed either on the Mercator or on the polyconic projection. By it considerable time is saved in making the measurement and greater accuracy is obtainable, as errors due to shrinkage or stretch of paper and those due to the planimeter itself, are eliminated.

The calibration is readily made by determining the number of revolutions of the planimeter wheel for a quadrangle of equal extent in latitude and longitude for which the area is given in standard tables similar to those shown on pages 127 and 128. The area at the given latitude corresponding to a revolution of the planimeter wheel for the map used, may then be determined by dividing the area of the measured quadrangle by the number of revolutions of the planimeter wheel, thus calibrating the instrument for that latitude and map.

In the calibration a quadrangle should be chosen, the middle parallel of which passes approximately through the center of gravity of the area. This is necessary in order to equalize the variation in area due to differences in latitude. In case the area extends over several degrees of latitude, it may be necessary to divide it into two or more parts and calibrate the planimeter for each part.

In determining an area it is necessary to measure only the portions which do not occupy full quadrangles as the areas for full quadrangles can be taken directly from the tables.

In using the planimeter, start at any observed wheel reading, without attempting to set the arm at zero. Move the pointer around the area in a clockwise direction and observe the final wheel reading. Change the position of the planimeter wheel on the paper, observe the initial reading and move the pointer around the area in a counter-clockwise direction and observe the final wheel reading. The differences between the initial and final readings in the two runs respectively should be very small and their mean will be the mean reading for the area. The double tracing of the area in this manner gives a check on the reading and when applied as explained removes the error due to lag of the instrument.

In some cases it is convenient to calibrate the planimeter, using the area of a State or county instead of the area of a quadrilateral. Areas of quadrilaterals of various sizes may be found in "Geographic Tables and Formulas," United States Geological Survey, from which the tables

Areas of quadrilaterals of the earth's surface of 30' extent in latitude and longitude.

| Middle latitude of quadrilateral. | Area in square miles. | Middle latitude of quadrilateral. | Area in square miles. | Middle latitude of quadrilateral. | Area in square miles. |
|-----------------------------------|-----------------------|-----------------------------------|-----------------------|-----------------------------------|-----------------------|
| ° / | | ° / | | ° / | |
| 0 00 | 1,188.10 | 11 00 | 1,166.84 | 22 00 | 1,103.68 |
| 0 15 | 1,188.08 | 11 15 | 1,165.86 | 22 15 | 1,101.77 |
| 0 30 | 1,188.05 | 11 30 | 1,164.86 | 22 30 | 1,099.84 |
| 0 45 | 1,188.00 | 11 45 | 1,163.85 | 22 45 | 1,097.88 |
| 1 00 | 1,187.92 | 12 00 | 1,162.81 | 23 00 | 1,095.91 |
| 1 15 | 1,187.82 | 12 15 | 1,161.75 | 23 15 | 1,093.92 |
| 1 30 | 1,187.70 | 12 30 | 1,160.67 | 23 30 | 1,091.90 |
| 1 45 | 1,187.56 | 12 45 | 1,159.56 | 23 45 | 1,089.87 |
| 2 00 | 1,187.39 | 13 00 | 1,158.44 | 24 00 | 1,087.81 |
| 2 15 | 1,187.20 | 13 15 | 1,157.29 | 24 15 | 1,085.74 |
| 2 30 | 1,186.99 | 13 30 | 1,156.12 | 24 30 | 1,083.64 |
| 2 45 | 1,186.76 | 13 45 | 1,154.93 | 24 45 | 1,081.52 |
| 3 00 | 1,186.51 | 14 00 | 1,153.72 | 25 00 | 1,079.39 |
| 3 15 | 1,186.24 | 14 15 | 1,152.48 | 25 15 | 1,077.23 |
| 3 30 | 1,185.95 | 14 30 | 1,151.23 | 25 30 | 1,075.05 |
| 3 45 | 1,185.62 | 14 45 | 1,149.95 | 25 45 | 1,072.85 |
| 4 00 | 1,185.28 | 15 00 | 1,148.65 | 26 00 | 1,070.64 |
| 4 15 | 1,184.92 | 15 15 | 1,147.33 | 26 15 | 1,068.40 |
| 4 30 | 1,184.53 | 15 30 | 1,145.99 | 26 30 | 1,066.14 |
| 4 45 | 1,184.13 | 15 45 | 1,144.63 | 26 45 | 1,063.86 |
| 5 00 | 1,183.70 | 16 00 | 1,143.25 | 27 00 | 1,061.56 |
| 5 15 | 1,183.24 | 16 15 | 1,141.84 | 27 15 | 1,059.24 |
| 5 30 | 1,182.77 | 16 30 | 1,140.41 | 27 30 | 1,056.90 |
| 5 45 | 1,182.28 | 16 45 | 1,138.96 | 27 45 | 1,054.54 |
| 6 00 | 1,181.76 | 17 00 | 1,137.50 | 28 00 | 1,052.16 |
| 6 15 | 1,181.22 | 17 15 | 1,136.00 | 28 15 | 1,049.76 |
| 6 30 | 1,180.66 | 17 30 | 1,134.49 | 28 30 | 1,047.34 |
| 6 45 | 1,180.08 | 17 45 | 1,132.96 | 28 45 | 1,044.90 |
| 7 00 | 1,179.48 | 18 00 | 1,131.41 | 29 00 | 1,042.44 |
| 7 15 | 1,178.85 | 18 15 | 1,129.83 | 29 15 | 1,039.97 |
| 7 30 | 1,178.20 | 18 30 | 1,128.24 | 29 30 | 1,037.47 |
| 7 45 | 1,177.53 | 18 45 | 1,126.62 | 29 45 | 1,034.95 |
| 8 00 | 1,176.84 | 19 00 | 1,124.98 | 30 00 | 1,032.41 |
| 8 15 | 1,176.13 | 19 15 | 1,123.32 | 30 15 | 1,029.85 |
| 8 30 | 1,175.39 | 19 30 | 1,121.64 | 30 30 | 1,027.27 |
| 8 45 | 1,174.63 | 19 45 | 1,119.93 | 30 45 | 1,024.68 |
| 9 00 | 1,173.86 | 20 00 | 1,118.21 | 31 00 | 1,022.06 |
| 9 15 | 1,173.06 | 20 15 | 1,116.47 | 31 15 | 1,019.43 |
| 9 30 | 1,172.23 | 20 30 | 1,114.71 | 31 30 | 1,016.77 |
| 9 45 | 1,171.39 | 20 45 | 1,112.92 | 31 45 | 1,014.10 |
| 10 00 | 1,170.52 | 21 00 | 1,111.11 | 32 00 | 1,011.40 |
| 10 15 | 1,169.63 | 21 15 | 1,109.28 | 32 15 | 1,008.69 |
| 10 30 | 1,168.73 | 21 30 | 1,107.44 | 32 30 | 1,005.96 |
| 10 45 | 1,167.80 | 21 45 | 1,105.57 | 32 45 | 1,003.20 |

Areas of quadrilaterals of the earth's surface of 30' extent in latitude and longitude (continued).

| Middle latitude of quadrilateral. | Area in square miles. | Middle latitude of quadrilateral. | Area in square miles. | Middle latitude of quadrilateral. | Area in square miles. |
|-----------------------------------|-----------------------|-----------------------------------|-----------------------|-----------------------------------|-----------------------|
| ° / | | ° / | | ° / | |
| 33 00 | 1,000.43 | 44 00 | 860.25 | 55 00 | 687.70 |
| 33 15 | 997.64 | 44 15 | 856.67 | 55 15 | 683.44 |
| 33 30 | 994.83 | 44 30 | 853.07 | 55 30 | 679.17 |
| 33 45 | 992.00 | 44 45 | 849.46 | 55 45 | 674.89 |
| 34 00 | 989.16 | 45 00 | 845.82 | 56 00 | 670.60 |
| 34 15 | 986.29 | 45 15 | 842.18 | 56 15 | 666.29 |
| 34 30 | 983.41 | 45 30 | 838.51 | 56 30 | 661.97 |
| 34 45 | 980.50 | 45 45 | 834.83 | 56 45 | 657.64 |
| 35 00 | 977.58 | 46 00 | 831.13 | 57 00 | 653.29 |
| 35 15 | 974.64 | 46 15 | 827.42 | 57 15 | 648.93 |
| 35 30 | 971.68 | 46 30 | 823.68 | 57 30 | 644.55 |
| 35 45 | 968.70 | 46 45 | 819.94 | 57 45 | 640.17 |
| 36 00 | 965.70 | 47 00 | 816.18 | 58 00 | 635.77 |
| 36 15 | 962.68 | 47 15 | 812.40 | 58 15 | 631.36 |
| 36 30 | 959.65 | 47 30 | 808.60 | 58 30 | 626.93 |
| 36 45 | 956.60 | 47 45 | 804.79 | 58 45 | 622.49 |
| 37 00 | 953.52 | 48 00 | 800.97 | 59 00 | 618.05 |
| 37 15 | 950.43 | 48 15 | 797.13 | 59 15 | 613.59 |
| 37 30 | 947.32 | 48 30 | 793.27 | 59 30 | 609.11 |
| 37 45 | 944.21 | 48 45 | 789.39 | 59 45 | 604.62 |
| 38 00 | 941.05 | 49 00 | 785.50 | 60 00 | 600.13 |
| 38 15 | 937.88 | 49 15 | 781.60 | 60 15 | 595.62 |
| 38 30 | 934.71 | 49 30 | 777.68 | 60 30 | 591.09 |
| 38 45 | 931.51 | 49 45 | 773.74 | 60 45 | 586.56 |
| 39 00 | 928.29 | 50 00 | 769.79 | 61 00 | 582.01 |
| 39 15 | 925.06 | 50 15 | 765.83 | 61 15 | 577.45 |
| 39 30 | 921.80 | 50 30 | 761.85 | 61 30 | 572.88 |
| 39 45 | 918.53 | 50 45 | 757.85 | 61 45 | 568.30 |
| 40 00 | 915.25 | 51 00 | 753.84 | 62 00 | 563.71 |
| 40 15 | 911.94 | 51 15 | 749.82 | 62 15 | 559.11 |
| 40 30 | 908.61 | 51 30 | 745.78 | 62 30 | 554.49 |
| 40 45 | 905.27 | 51 45 | 741.72 | 62 45 | 549.86 |
| 41 00 | 901.91 | 52 00 | 737.65 | 63 00 | 545.23 |
| 41 15 | 898.54 | 52 15 | 733.57 | 63 15 | 540.58 |
| 41 30 | 895.14 | 52 30 | 729.47 | 63 30 | 535.92 |
| 41 45 | 891.73 | 52 45 | 725.36 | 63 45 | 531.25 |
| 42 00 | 888.30 | 53 00 | 721.23 | 64 00 | 526.57 |
| 42 15 | 884.85 | 53 15 | 717.08 | 64 15 | 521.88 |
| 42 30 | 881.39 | 53 30 | 712.93 | 64 30 | 517.17 |
| 42 45 | 877.91 | 53 45 | 708.76 | 64 45 | 512.46 |
| 43 00 | 874.41 | 54 00 | 704.57 | 65 00 | 507.74 |
| 43 15 | 870.90 | 54 15 | 700.38 | 65 15 | 503.01 |
| 43 30 | 867.37 | 54 30 | 696.16 | 65 30 | 498.28 |
| 43 45 | 863.82 | 54 45 | 691.94 | 65 45 | 493.51 |

on pages 127 and 128 have been obtained. Standard areas of various States are given in Bulletin 302, United States Geological Survey, and areas of counties can be obtained from Rand and McNally Atlas maps.

Unfortunately, in measuring drainage areas in many sections of the country, maps of sufficient detail are not available for determining accurately the boundaries of the areas. In general, maps from various sources may be rated as to reliability in the following order:

- (1) Results of special detail surveys.
- (2) Topographic sheets, United States Geological Survey.
- (3) United States Land Office maps.
- (4) United States post route maps.
- (5) Rand and McNally Atlas maps.
- (6) Miscellaneous State and county maps.

LOGARITHMIC PLOTTING.*

In ordinary plotting, the co-ordinates or distances from the axes represent values of the variables. In logarithmic plotting, the co-ordinates represent values of the logarithms of the variables.

Thus figure 31 is the result of plotting directly the following simultan-




FIG. 31.

* "Hydraulic Laboratory Manual," by Professors Ernest W. Schoder and Kenneth B. Turner, Cornell University.

eous values of X and Y , the plotted points having been joined by a smooth curve:

| X | Y |
|------|------|
| .50 | .162 |
| .90 | .45 |
| 1.20 | .74 |
| 1.60 | 1.22 |
| 2.00 | 1.80 |

Let us now tabulate the logarithms of the above values.

| $\text{Log } X$ | $\text{Log } Y$ |
|-----------------|-----------------|
| 9.6990(-10) | 9.2095(-10) |
| 9.9542(-10) | 9.6532(-10) |
| .0792 | 9.8692(-10) |
| .2041 | .0864 |
| .3010 | .2553 |




FIG. 82.

It should be noted that the logarithms of numbers less than 1 are negative. Instead, however, of writing the logarithm of 0.50 as -0.3010 (*i. e.* $\log \frac{1}{2} = 0 - 0.3010$), we change it to a whole negative number plus a positive decimal, *i. e.* either to $-1 + 0.6990$ (because $\log \frac{1}{10} = 0.6990 - 1$), written 1.6990, or to $9.6990 - 10$ (the -10 being usually omitted in writing, but always understood).

In figure 32 these simultaneous values of the logarithms are plotted. The numbers marked along the axes to the left of and below the origin are in accordance with the usual scheme of writing the negative logarithms.

In figure 32 the plotted points give a straight line, while in figure 31 with the direct plotting of the simultaneous values there is obtained a curve resembling a parabola. Herein appears one advantage of logarithmic plotting. In figure 31 we have no ready means of determining the equation of the curve, but in figure 32, since we have a straight line, the equation can be found readily as follows:

The equation of a straight line is of the form

$$y = ax + b \quad (1)$$

where a is the slope of the line and b is the intercept on the Y axis, *i. e.* when $x=0$, $y=b$. So, by measuring the slope (the tangent of the angle made with the X axis) and the intercept, we can write out the correct equation of any straight line.

It is to be noted that the slope of a line may be negative as well as positive. If the line is in the second and fourth quadrants the slope is negative. Or, from another standpoint, when y increases with an increase in x the slope is positive and when y decreases with an increase in x the slope is negative.

Now, if we know, or assume, the equation

$$Y = mX^n \quad (2)$$

we may write also

$$(\log Y) = n(\log X) + (\log m) \quad (3)$$

because if quantities are equal, their logarithms are equal.

Equation (3) is of the same form as (1), *i. e.* a straight line equation. In (3) the slope of the straight line is n and the intercept on the $(\log Y)$ axis is $(\log m)$ *i. e.* when $(\log X) = 0$, $(\log Y) = (\log m)$. Hence an equation like (2), which gives a parabola-like curve when corresponding values of X and Y are plotted, gives a straight line when the logarithms of X and Y are plotted. Conversely, when the logarithms of X and Y have been plotted, and the points found to lie on a straight line, we know that the equation is of the form

$$Y = mX^n$$

the slope of the line being equal to the exponent n and the intercept on the $(\log Y)$ axis being equal to $(\log m)$. To find m when $(\log m)$ is known a table of logarithms is used.

The above reasoning holds good for all real values of the exponent n , whether positive or negative, whole number or fraction. m is assumed to be positive, as it usually is in equations that occur in engineering. We deal with only positive values of the original variables, X and Y , since the logarithm of a negative number is an imaginary quantity.

With the above facts demonstrated we can proceed to write the equation of the line in figure 32.

The slope is $\frac{y'}{x'} = 1.75$. (See Fig. 32.) The intercept on the $(\log Y)$ axis is negative and by the chosen scale the distance below the origin equals -0.277 , or, by the system of representing negative logarithms, it equals $9.733(-10)$ as may be read directly on figure 32. Therefore the equation of the straight line is

$$(\log Y) = 1.75(\log X) + (9.733 - 10).$$

Taking the anti-logarithms of both sides, we have

$$Y = 0.54X^{1.75},$$

which is the desired equation in terms of X and Y , the original variables.

Let us now make use of *logarithmic scales* along the axes of figure 32, (See Fig. 33), and note the results.

On a logarithmic scale the divisions and marking are such that a division with some particular number represents (by its distance from the starting point) the logarithm of that number, just as on the common slide rule. Figure 34 shows an equal division scale and a logarithmic scale side by side. A careful study of these scales in their relation to each other will fix in mind the principle involved.

So by using the logarithmic scales it is not necessary, for instance, to scale off the intercept, as was done in figure 32, and then to look up the corresponding number in a table of logarithms. In figure 33 on the logarithmic scale at the left, horizontally opposite the intersection of the sloping line with the $(\log Y)$ axis, we see the division representing 0.54. This is the same value of m previously obtained by the longer roundabout method.

So also in figure 33, opposite each plotted point, we see, on the left and bottom logarithmic scales, the divisions representing the values of X and Y given at the beginning of this discussion. It thus appears that the logarithmic scales enable us both to plot in proper position the logarithms of given numbers without using a table and also to read off

directly the number whose logarithm is represented by a given distance, *e. g.* an intercept.

Hence for purposes of logarithmic plotting we do not need the equal divisions along the axes, as in figures 32 and 33, but can advantageously




FIG. 33.

substitute the logarithmic scales. This brings us to the method of ruling *Logarithmic Cross-Section Paper* or a *Logarithmic Diagram*. As ordinary cross-section paper is made by drawing two sets of lines, equally spaced, perpendicular to each other, so logarithmic paper is made by




FIG. 34.

drawing two sets of lines spaced according to a logarithmic scale.

The "base" of such paper, and of a logarithmic scale in general, is the distance representing 1.0 in logarithms. Thus the "base" of the lower scales on the common 10-inch slide rule is 10 inches (sometimes 25 centimeters). The "base" of the upper scales of the slide rule is 5 inches.

A logarithmic scale has the same salient features as a common logarithmic table. Thus a table of logarithms contains the logarithms of all numbers between 1 and 10, advancing by intervals of, *e. g.*, .01 or .001 or .0001, etc. We consider such a table complete, but really it is not, because we modify the tabular logarithms by adding or subtracting one or more whole units (*the characteristic*) whenever the number is more than 10 or less than one. Under the same conditions we may consider a logarithmic scale to be complete when its divisions extend from 1 to 10. We can provide for the position of the decimal point by shifting one "base" length for each place that the decimal point is moved, because changing the decimal point one place on a number changes its logarithm by 1.0. Then on a logarithmic scale the position of the division representing the number would be moved one "base."

But in plotting we do not wish to bother with a scale that must be shifted about on the paper. The paper should be ruled so it will furnish its own scale at all points. Evidently, then, logarithmic scale cross-sections consist of a succession of panels one base square. All panels are ruled alike, just as on the upper scales of a slide rule the right half is a repetition of the left half. The logarithmic scale in figure 34 illustrates a succession of five base distances each divided alike, and giving a range of values from .01 to 1000.

It appears from figure 33 that the axes are situated where the logarithm

mic scales are marked 1. This is so because $(\log 1)=0$. So on logarithmic paper the line for $(\log X)=0$ is marked with the value of X , viz., 1. Therefore on logarithmic paper, in plotting lines from equations or finding equations from plotted lines, the origin always is at the intersection of the lines marked 1, and the intercept is to be taken on the Y axis, which is the line marked $X=1$.




FIG. 35.

Of course on the unused sheet of logarithmic cross-section paper there is a division marked 1 every base distance along all four edges. We can choose any one of these for the unity value depending on convenience and the range of values it is desired to represent. After this we must properly place the decimal points on the printed numbers of the unused sheet. The lines one or more "bases" to the left or right of the Y axis represent $(\log X) = -1, -2$, etc., or $+1, +2$, etc., and the markings are to be changed respectively, to 0.1, .01, etc., 10, 100, etc..

In short when we have selected an origin we must use it and no other during the whole calculations. Decimal points are not to be disregarded any more than on the slide rule.

In figures 35 and 36 are shown logarithmic plottings of three equations. The only difference between the figures is that the background in figure 35 is composed of equal division cross-section lines as on ordinary cross-section paper, while the background in figure 36 is composed of lines ruled according to a logarithmic scale as on logarithmic paper.




FIG. 36.

The equations in terms of X and Y , are respectively:

(Full line), $Y = 0.166X^{1.72}$.

(Dotted line), $Y = 1.26X^{0.55}$.

(Dashed line), $Y = 0.282X^{-1.11} = \frac{0.282}{X^{1.11}}$.

These equations are read directly from figure 35, or indirectly from

figure 35 by first writing out the straight line equations of the logarithms, namely :

$$(\log Y) = 1.72 (\log X) + (9.22 - 10).$$

$$(\log Y) = 0.55 (\log X) + 0.1.$$

$$(\log Y) = -1.11 (\log X) + (9.45 - 10).$$

By taking the anti-logarithms of each side of these equations we obtain those given above. The advantage of using the logarithmic paper is obvious.

It is to be noted that the slope of a line on logarithmic paper is a ratio of two *distances*, and that these distances must be measured with an ordinary scale, *not with the logarithmic scale of the paper*.

Following are a few relations involving powers and roots, and in the representation of which logarithmic plotting is useful :

Flow in pipe:—

$$H = 4f \frac{l}{d} \frac{v^2}{2g}, \quad H = \frac{K}{d^{1.25}} V^{1.86},$$

$$V = C s^{.54} d^{.67}.$$

Flow in open channel:—

$$V = A\sqrt{Rs}.$$

Velocity of jet:—

$$V = C\sqrt{2gh}.$$

Head corresponding to velocity:—

$$h = \frac{V^2}{2g}.$$

Power in a nozzle stream:—

$$L = \frac{FvV^3}{2g}$$

WHERE STREAM-GAGING DATA CAN BE FOUND.*

As a result of hydrographic studies by the Federal Government, by States, by special commissions, and by individuals, data in regard to stream flow and the conditions affecting it are now available for streams in nearly all sections of the country. These data are contained in publications which should form a part of every engineer's library, and should be freely used in order to avoid duplication of work.

* Notes on Hydrology, by Daniel W. Mead, professor of hydraulic engineering, Wisconsin University, contains many tables and references in regard to hydrologic data.

These publications are prepared and issued by—

1. United States Geological Survey.
2. United States Census.
3. United States Weather Bureau.
4. Corps of Engineers, United States Army.
5. State officials.
6. Special commissions.
7. City officials.

Reports of the United States Geological Survey.—The United States Geological Survey has for many years carried on systematic measurements of flow of streams and publishes annually a report of the results of such stream measurements. In connection with this work much other data, such as river profiles, quality of water, etc., are collected, and from time to time as information becomes available, special reports are prepared, which either bring together all the hydrographic data for particular drainage areas, or treat of special hydrographic subjects. These are published in the series of Water-Supply and Irrigation Papers.

Reports of the United States Census.—Volumes 16 and 17 of the Tenth Census are devoted to water powers, and contain the results of detailed studies of the important rivers of the United States. During the Census of 1900 schedules were prepared showing the amount of utilized water power in the United States. These schedules have never been published, but the data may be obtained on application to the Census Bureau.

Reports of the United States Weather Bureau.—The reports of the United States Weather Bureau contain a large amount of data in regard to precipitation, evaporation, and other factors which affect the run-off of streams. A summary of these data is published each year in the Annual Report of the Chief of the Weather Bureau. The Weather Bureau also publishes each month a "Climate and Crop Report," which gives daily temperature, precipitation, and other information for a limited area, usually one State; and the "The Weather Review," which gives under one cover a monthly summary of the data collected in all sections of the country and special articles in regard to various climatic conditions.

Besides collecting these data in regard to climate, the Weather Bureau maintains a flood service, in connection with which a large number of river-height observation stations are maintained for the records of daily fluctuations of stage. These data have been printed under the title "Daily River Stages," of which volumes 1 to 11 have been published.

Reports of the Chief of Engineers, United States Army.—The Army Engineers have made extensive investigations in regard to the flow and slope of many of the larger rivers in the United States, among which are the Mississippi, Missouri, Niagara, and St. Lawrence. Data collected in these investigations are published in the Annual Reports of the Chief of Engineers, United States Army, and in reports of special commissions working under the direction of the Chief of Engineers. The Army Engineers also have a large amount of manuscript data relative to the various streams, which may be obtained on application.

Reports of State officials.—A large amount of valuable information has been collected and published by various States. Among these publications may be mentioned the following:

Reports of the New York State Engineer.

Hydrology of the State of New York, by G. W. Rafter (1905).

Reports of the Illinois State Board of Health.

Report of the Geological Survey of New Jersey, vol. 3 (1894).

Reports of the State Board of Health of Massachusetts.

Reports of the Metropolitan Water and Sewage Board of Massachusetts.

Wells, "Water Powers of Maine" (1869).

Bulletins of the Geological Survey of North Carolina.

Reports of the Commission of Public Works of California.

Reports of special commissions.—A large number of special hydrographic problems have been investigated by commissions appointed by Federal, State, or city governments. Among these reports may be mentioned:

Report of New York City Water Supply, by John R. Freeman (1900).

Report of the Commission on Additional Water Supply of New York City (1904).

Report of Commission on Charles River dam (1903).

Report of the U. S. Deep Waterways Commission (1900).

Report of the State Water Storage Commission of New York (1903).

Reports of city officials.—Nearly all large cities have investigated and reported upon the water supply in their locality in connection with the municipal waterworks. These reports may usually be obtained by application to the city engineer.

How to obtain Government publications.—Most Government publications may be obtained or consulted in the following ways:

(1) A limited number of every issue is delivered to the Department under which the work was done. Copies of these reports may be

obtained either free of charge or for a nominal sum on application to the Department publishing them.

(2) Every member of Congress is allotted a certain number, from which they may be obtained, free of charge, on application.

(3) Other copies are deposited with the Superintendent of Documents, Washington, D. C., from whom they may be purchased practically at cost.

(4) Copies are furnished to the principal public libraries in the large cities throughout the United States, where they may be consulted by those interested.

CHAPTER VI.

CONDITIONS AFFECTING STREAM FLOW.

Water, in its ceaseless round from atmosphere to earth and return, in its courses over or through the land or through vegetation, affords an endless number of interesting problems for study. In this discussion, which pertains essentially to stream flow, there will be considered only the conditions affecting the quantity and distribution of water from the time it reaches the earth in some form of precipitation until it flows into the ocean or is returned to the atmosphere. The amount and distribution of the water in the streams, which is derived primarily from precipitation, are modified by evaporation, temperature, geology, topography, vegetation, and artificial control. Since the effects of these influencing factors can not as a rule be differentiated from one another, no data can in general be given to show their magnitude; tendencies only can be discussed.

It is important to observe that while precipitation and evaporation largely affect the distribution of the run-off, they also practically control its total amount. The other factors, except in so far as they affect precipitation and evaporation, exert their influence principally on the distribution of flow and but slightly on the total quantity of discharge.

PRECIPITATION.

All the water that appears in streams has at some time been condensed and precipitated from the atmosphere. The quantity, intensity, and distribution of precipitation are therefore prime factors influencing the quantity and distribution of the run-off.

Rain gages for measuring precipitation consist of a collecting cylinder, which exposes a circular surface for collecting the rainfall, and a storage vessel in which the water is retained until measured.

The standard rain gage of the United States Weather Bureau (fig. 37 and Pl. VIII, A) is best suited for the measurement of precipitation under ordinary conditions. This gage consists of a receiver, an overflow attachment, and a measuring tube.

In this rain gage the exposed area is 8 inches in diameter and is

connected by means of a reducing funnel with the measuring tube, which has an inside area of cross-section of $\frac{1}{10}$ the area of the surface of the receiver. The measured depth of water in this tube is therefore 10 times the depth of precipitation.

Other rain gages are arranged for weighing the collected waters and for easily reducing the observed weights to inches of depth.

Rain gages are usually non-recording and must be visited daily whenever precipitation takes place. The attendant measures the precipitation either directly, by measuring the depth, or indirectly, by weighing the water which has been collected since his last record, empties the gage, and replaces it for further use. Satisfactory recording rain gages that require only occasional attention and that are therefore suited to the collection of records in uninhabited and mountainous sections have not yet been devised.




FIG. 37.—Rain Gage and Support.

Inaccuracies in precipitation records may result from one of two causes—(1) poor exposure of the gage or (2) incorrect collections and measurement of snowfall.

Rain gages in slightly different positions, if badly exposed, catch very different amounts of rainfall. Two gages placed within a few yards of each other may show a difference of 20 per cent in rainfall in a heavy rainstorm. Wind seems to be the principal factor in producing this difference. The stronger the wind the greater the difference is likely to be. In a high location eddies of wind produced by walls of buildings divert rain that would otherwise fall in the gage. A gage near the edge of the roof, on the windward side of a building, shows less rainfall than one in the center of the roof. The vertical ascending current along the side of the wall extends slightly above the level of the roof, and part of the rain is carried away from the gage. In the center of a large, flat roof, at least 60 feet square, the rainfall collected by a gage does not differ materially from what is collected at the level of the ground. A gage on a plain with a fence 3 feet high around it at a distance of 3 feet may collect 6 per cent more rain than without the fence. The gage should therefore, if possible, be set in an open lot,



A. PRECIPITATION AND EVAPORATION STATION, MADISON, WIS.



B. SNOW OBSERVATION STATION, WHITE MOUNTAINS, N. H.

unobstructed by large trees, buildings, or fences. Low bushes and fences, or walls that break the force of the wind in the vicinity of the gage are, however, beneficial, if at a distance at least as great as the height of the object. Such a place, in general, affords the best exposure. Gages should be exposed on roofs of buildings only when necessary, and then the roof should be flat, or nearly so.

Satisfactory measurements of the snowfall of individual storms are seldom obtained because of the difficulty in collecting in a receptacle the true amount of snow falling in wind. In order to measure snowfall, therefore, it has been found most satisfactory to arrange a platform, on which the snow is allowed to fall, and to collect and melt a vertical sample of known area, thus determining its water equivalent. The tube and scale method, devised by the United States Weather Bureau (Pl. VIII, B), for determining the water equivalent of accumulated snow represents the latest and best practice and will give satisfactory results when sufficient observations are made.

The amount of water collected on the small surface presented by a rain gage is assumed to represent the precipitation over a large area. Since, as explained above, slight differences may occur in the amount of water collected, and consequently, in the recorded rainfall, any data in regard to the precipitation over an area may be in error. Moreover, observation stations are generally located in the lower, inhabited sections, and even if accurate records are obtained at the gage, they may not correctly represent the precipitation on the more elevated portions of the basin. It follows, therefore, that the application of a few records to a large area may result in considerable error.

The United States Weather Bureau has collected precipitation records for many stations. The plan followed contemplates the establishment of a precipitation station in each county; therefore, in most of the areas considered the horizontal distribution of the stations is fairly uniform and representative. This is not generally the case, however, with the vertical distribution of the stations, as the location of the gage depends in large measure on the accessibility of a reliable observer and a telegraph station for use in reporting excessive rains. Neither the observer nor the telegraph is generally available at high altitudes. Most of the stations have therefore been located at low or medium elevations, and little is yet known concerning the effect of elevation on precipitation.

The records of precipitation show great variations from season to season and from place to place, with no ascertainable sequence or order. They show also great variations between different sections of the country and for different altitudes and exposures in the same sections. The

mean yearly and seasonal rainfall for any locality is, however, fairly constant and has been determined for many observation stations from records extending over a series of years.

The average precipitation and the range of departure from the average has been determined with reasonable accuracy for many localities in the United States. In Pl. IX* are shown lines of equal rainfall which have been drawn from the means of records collected in several years at many observation stations. The departures from the mean conditions can be determined for any place only by study of detailed records of precipitation.


Although a discussion of the conditions that affect precipitation will not be attempted here, it seems desirable to call attention to the effects of variations in latitude, altitude, and topography on the amount and distribution of precipitation, in order that the user of such records may be able to estimate the probable errors in the application of available records to an extended area.

The effects of latitude and altitude on precipitation are similar, since they are the principal factors governing temperature, which affects both the amount of moisture received by the atmosphere and its precipitation. Other conditions being equal, precipitation decreases toward the poles, probably on account of lesser evaporation with decrease of temperature and consequent smaller absolute amounts of moisture in the air. It increases with altitude to the usual height of rain clouds, above which it probably decreases.

The evaporation from water surfaces is in many places so great that the air above such surfaces generally contains a large amount of moisture. If such moisture-laden air is carried by prevailing winds over adjacent lands, and especially if the lands contain mountains high enough to deflect the air currents to those altitudes in which the temperature is sufficiently low to cause precipitation, there will be heavy precipitation in such mountains and between them and the water surfaces. By this process the winds are so robbed of moisture that the lands beyond the mountains receive much smaller amounts of precipitation. On the other hand, if the prevailing winds are away from the land or if no mountains are near to deflect the air currents upward, the adjacent land surfaces may be arid.


A study of the actual annual and seasonal variations of rainfall is of great importance, and a comparison of such rainfall with the measured stream flow is of interest in hydraulic investigations. Such comparisons show that great errors will probably result from attempts to estimate stream flow from precipitation data, and the estimates made

* See Water-Supply Paper No. 301, U. S. Geol. Survey.



ION

Prepared by Henry Gannett
mainly from data of the
United States Geological Survey
and United States Weather Bureau



should never be used as the only basis for computations of the amount of water available for power or irrigation.

In using rainfall data the conditions affecting the accuracy of the records, previously noted, must be considered, as well as the possible sources of error stated below.

The record obtained by a single rain gage shows only the measured precipitation on a few square inches of surface. This record, even if accurately made, may not be representative of a considerable area. In order to ascertain with certainty the average precipitation over a large area many rain gages should be employed. Under ordinary conditions of practice, however, the gages in any drainage basin are generally few in number, and as a result the extremes of precipitation, which always occur in comparatively small areas, may not be recorded.

No means have yet been devised for obtaining reliable data in regard to precipitation during the winter months, and practically no data have been collected to show the amount of snow storage at the end of each month. Hence the records of snowfall are especially unreliable, while the lack of information in regard to the amount of water held in the form of snow on the ground makes it necessary to study the winter conditions as a whole.

In any use of rainfall data it is necessary to assume that for any period of time the mean rainfall over the whole of an area is either the arithmetical or weighted mean of the rainfall during that period as observed at the various stations in that area. Since all rainfall records are liable to great errors the weighting of the data is not generally warranted.

In order to compare rainfall and run-off both records should be expressed in "depth in inches" over the drainage basins considered and should of course pertain to the same periods of time. Such data have usually been computed and recorded for calendar months. This period is, however, too short for comparative purposes and may lead to apparently erroneous results, because heavy precipitation which occurs at the end of the month will not appear as run-off until the following month. A year is a better period but is not entirely satisfactory. The calendar year is undesirable as a comparative period, because the conditions of snow and ground storage are not the same at the end of every December. The year beginning with October is a much better period, since on the first of that month the storage conditions are more nearly uniform from year to year, because there is at that time no snow storage, and surface and ground storage are usually at a minimum. The largest disturbing factors in the relation between run-off and rainfall are

Monthly and yearly maximum, minimum, and mean loss, for an

[Note:—M = Mean;

PRECIPITATION, IN INCHES.

| Drainage. | OCTOBER. | | NOVEMBER. | | DECEMBER. | | JANUARY. | | FEBRUARY. | | MARCH. | |
|---|----------|------|-----------|------|-----------|------|----------|------|-----------|------|--------|------|
| | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. |
| Connecticut, above Orford; 3 800 sq. miles.... | 2.99 | 4.12 | | 5.54 | | 4.77 | | 2.94 | | 3.18 | | 4.77 |
| Housatonic, above Gaylordsville; 1080 sq. miles | 2.98 | 2.12 | 2.17 | 1.05 | 2.80 | 1.26 | 2.98 | 1.99 | 1.00 | 0.71 | 3.44 | 2.05 |
| Susquehanna, above Harrisburg; 24 080 sq. miles. | 3.08 | 6.49 | 2.89 | 4.29 | 4.38 | 6.76 | | 4.89 | | 4.24 | | 5.20 |
| Susquehanna, above Wilkes-Barre; 9 810 sq. miles..... | | 2.74 | | 0.89 | | 2.72 | | 1.65 | | 0.76 | 4.10 | 3.04 |
| Susquehanna, above Williamsport; 5 640 sq. miles..... | | 5.74 | | 4.43 | | 5.63 | | 4.40 | | 4.55 | | 4.58 |
| Susquehanna, above Williamsport; 5 640 sq. miles..... | | 0.95 | 0.63 | 0.98 | 2.97 | 1.04 | 2.73 | 1.77 | 2.67 | 0.98 | 3.35 | 1.21 |
| Susquehanna, above Williamsport; 5 640 sq. miles..... | | 6.04 | | 4.70 | | 5.58 | | 3.40 | | 3.46 | | 4.77 |
| Susquehanna, above Williamsport; 5 640 sq. miles..... | | 1.69 | 2.41 | 1.13 | 3.30 | 2.24 | 2.57 | 1.69 | 2.30 | 1.17 | 3.60 | 3.17 |
| Susquehanna, above Williamsport; 5 640 sq. miles..... | | 6.22 | | 4.91 | | 5.48 | | 3.69 | | 4.00 | | 5.20 |
| Ohio, above Wheeling; 28 680 sq. miles..... | 2.90 | 0.89 | 2.74 | 0.54 | 3.15 | 1.25 | 2.63 | 1.51 | | 1.05 | 4.09 | 3.43 |
| Potomac, above Point of Rocks; 9 650 sq. miles..... | 2.66 | 6.78 | | 5.67 | | 5.07 | | 4.97 | | 6.34 | | 5.63 |
| Shenandoah, above Millville; 8 000 sq. miles..... | 2.21 | 0.51 | 2.09 | 0.65 | 3.13 | 1.84 | 2.24 | 1.72 | 3.19 | 1.19 | 2.89 | 1.40 |
| James, above Cartersville; 6 330 sq. miles..... | 2.47 | 6.41 | | 4.10 | | 5.71 | | 3.73 | | 5.98 | | 4.44 |
| James, above Cartersville; 6 330 sq. miles..... | 2.46 | 0.57 | 2.29 | 0.79 | 2.67 | 0.74 | 2.53 | 1.55 | 2.91 | 0.46 | 3.42 | 2.08 |
| James, above Buchanan; 2 060 sq. miles..... | 2.53 | 7.10 | | 4.16 | | 6.12 | | 4.08 | | 6.25 | | 5.13 |
| James, above Glasgow; 2 800 sq. miles..... | 2.61 | 0.48 | 2.06 | 0.81 | 2.61 | 0.23 | 2.53 | 1.41 | 3.12 | 0.33 | 3.53 | 2.08 |
| James, above Glasgow; 2 800 sq. miles..... | | 8.35 | | 3.57 | | 7.19 | | 4.43 | | 5.05 | | 6.38 |
| James, above Glasgow; 2 800 sq. miles..... | | 0.57 | 1.89 | 0.98 | 3.28 | 1.41 | 2.30 | 2.21 | 3.53 | 0.59 | 3.83 | 2.59 |
| James, above Glasgow; 2 800 sq. miles..... | | 8.03 | | 5.20 | | 7.63 | | 4.56 | | 5.89 | | 5.65 |
| James, above Glasgow; 2 800 sq. miles..... | | 0.46 | 2.42 | 0.71 | 3.00 | 0.30 | 2.79 | 1.77 | 3.66 | 0.63 | 3.83 | 2.39 |
| James, above Glasgow; 2 800 sq. miles..... | | 8.70 | | 5.27 | | 7.60 | | 4.49 | | 5.42 | | 6.36 |
| James, above Glasgow; 2 800 sq. miles..... | | 0.32 | 2.29 | 0.73 | 2.87 | 0.17 | 2.86 | 1.80 | 3.57 | 0.49 | 3.89 | 2.67 |
| Appomattox, above Mattoax; 745 sq. miles..... | 2.70 | 7.60 | | 3.99 | | 8.08 | | 4.88 | | 5.22 | | 5.96 |
| Roanoke, above Roanoke; 300 sq. miles..... | 2.71 | 0.35 | 2.30 | 1.06 | 2.76 | 1.88 | 2.38 | 2.00 | 3.11 | 0.94 | 3.63 | 2.37 |
| Roanoke, above Roanoke; 300 sq. miles..... | | 6.32 | | 4.60 | | 7.45 | | 4.08 | | 7.10 | | 6.49 |
| Roanoke, above Randolph; 3 060 sq. miles..... | 2.61 | 0.13 | 2.49 | 1.04 | 2.92 | 0.50 | 2.85 | 1.64 | 2.98 | 0.62 | 4.01 | 2.44 |
| Roanoke, above Randolph; 3 060 sq. miles..... | | 5.54 | | 3.15 | | 7.84 | | 4.35 | | 5.63 | | 6.49 |
| Roanoke, above Randolph; 3 060 sq. miles..... | | 0.65 | 2.22 | 1.22 | 2.95 | 1.78 | 3.10 | 2.19 | 3.56 | 0.53 | 3.57 | 2.29 |

RUN-OFF, IN INCHES.

| Drainage. | OCTOBER. | | NOVEMBER. | | DECEMBER. | | JANUARY. | | FEBRUARY. | | MARCH. | |
|--------------------------------------|----------|--------|-----------|------|-----------|--------|----------|------|-----------|--------|--------|--------|
| | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. |
| Connecticut, above Orford..... | 1.24 | 1.94 | | 2.51 | | 2.34 | | 1.11 | | 1.03 | | 7.56 |
| Housatonic, above Gaylordsville..... | | 0.45 | 1.23 | 0.50 | 1.28 | 0.47 | 0.76 | 0.37 | 0.54 | 0.26 | 3.91 | 1.60 |
| Susquehanna, above Harrisburg..... | 1.89 | 3.25 | | 1.92 | | 4.13 | | 3.21 | | (3.68) | | 8.77 |
| Susquehanna, above Harrisburg..... | | (0.40) | 1.39 | 0.96 | 2.68 | (1.03) | 2.32 | 0.96 | 1.61 | 0.49 | 5.88 | (4.24) |
| Susquehanna, above Harrisburg..... | 0.90 | 2.17 | | 2.18 | | 3.53 | | 3.79 | | 4.04 | | 7.46 |
| Susquehanna, above Harrisburg..... | | 0.16 | 1.08 | 0.28 | 1.75 | 0.49 | 1.94 | 0.67 | 1.98 | 0.53 | 4.48 | 2.46 |
| Susquehanna, above Harrisburg..... | | 3.22 | | 1.47 | | 4.91 | | 3.45 | | 3.92 | | 7.94 |
| Susquehanna, above Harrisburg..... | 1.16 | 0.13 | 0.96 | 0.60 | 2.53 | 0.90 | 2.89 | 2.14 | 2.56 | 1.57 | 5.33 | 2.79 |
| Susquehanna, above Harrisburg..... | | 2.68 | | 1.84 | | 4.14 | | 3.22 | | 4.52 | | 8.09 |
| Susquehanna, above Harrisburg..... | | 0.15 | 1.14 | 0.29 | 1.75 | 0.33 | 1.96 | 1.01 | 1.96 | 0.56 | 5.59 | 2.83 |
| Susquehanna, above Harrisburg..... | | 3.70 | | 2.97 | | 3.64 | | 4.30 | | 7.29 | | 6.89 |
| Ohio, above Wheeling.... | 0.72 | 0.12 | 1.21 | 0.24 | 1.99 | 0.53 | 2.78 | 1.23 | 3.12 | 0.78 | 4.07 | 1.37 |
| Potomac, above Point of Rocks..... | | 1.63 | | 0.99 | | 3.06 | | 2.49 | | 4.60 | | 6.50 |
| Shenandoah, above Millville..... | 0.52 | 0.14 | 0.44 | 0.15 | 1.06 | 0.26 | 1.30 | 0.51 | 2.00 | 0.39 | 2.80 | 1.34 |
| James, above Cartersville..... | | 3.99 | | 1.05 | | 3.12 | | 2.62 | | 3.63 | | 5.34 |
| James, above Cartersville..... | 0.82 | 0.20 | 0.48 | 0.20 | 1.05 | 0.29 | 1.21 | 0.47 | 1.53 | 0.46 | 2.16 | 0.86 |
| James, above Cartersville..... | | 2.34 | | 1.27 | | 3.29 | | 2.76 | | 3.74 | | 5.29 |
| James, above Cartersville..... | 0.89 | 0.21 | 0.75 | 0.26 | 1.51 | 0.46 | 1.80 | 0.66 | 2.11 | 0.64 | 3.16 | 1.52 |
| James, above Buchanan..... | | 2.33 | | 2.46 | | 4.32 | | 2.51 | | 5.34 | | 5.67 |
| James, above Buchanan..... | 0.60 | 0.18 | 0.71 | 0.0 | 1.30 | 0.26 | 1.36 | 0.43 | 2.34 | 0.51 | 3.35 | 1.53 |
| James, above Buchanan..... | | 2.48 | | 1.67 | | 4.50 | | 2.79 | | 3.99 | | 4.44 |
| James, above Buchanan..... | 0.67 | 0.22 | 0.63 | 0.24 | 1.21 | 0.31 | 1.41 | 0.63 | 2.34 | 0.43 | 2.82 | 1.23 |
| James, above Buchanan..... | | 1.44 | | 1.32 | | 2.54 | | 2.73 | | 3.60 | | 4.01 |
| James, above Buchanan..... | 0.68 | 0.27 | 0.64 | 0.33 | 1.46 | 0.58 | 1.75 | 0.61 | 2.29 | 0.45 | 2.26 | 0.78 |
| James, above Buchanan..... | | 3.06 | | 1.71 | | 4.23 | | 3.34 | | 5.63 | | 7.49 |
| Roanoke, above Roanoke..... | 0.85 | 0.26 | 0.78 | 0.24 | 1.29 | 0.35 | 1.43 | 0.32 | 2.34 | 0.64 | 2.88 | 0.94 |
| Roanoke, above Roanoke..... | | 1.23 | | 1.08 | | 3.61 | | 2.29 | | 3.49 | | 4.13 |
| Roanoke, above Roanoke..... | 1.08 | 0.30 | 0.81 | 0.32 | 1.71 | 0.71 | 1.63 | 0.78 | 1.98 | 1.02 | 2.33 | 1.04 |

rainfall, run-off in percentage of rainfall, and average year.

R = Range.]

| APRIL. | | MAY. | | JUNE. | | JULY. | | AUGUST. | | SEPTEMBER. | | YEAR. | | No. of Years. |
|--------|------|------|------|-------|-------|-------|-------|---------|-------|------------|------|--------|-------|---------------|
| M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | Total. | R. | |
| | 3.54 | | 4.78 | | 5.27 | | 5.08 | | 4.69 | | 5.75 | | 41.80 | |
| 2.77 | 1.87 | 2.99 | 0.27 | 3.78 | 2.10 | 4.84 | 3.78 | 3.88 | 3.23 | 3.78 | 1.08 | 36.76 | 33.44 | 5 |
| | 6.12 | | 6.24 | | 10.42 | | 7.25 | | 7.28 | | 6.42 | | 51.49 | |
| 3.71 | 2.95 | 2.97 | 1.12 | 5.46 | 1.88 | 5.00 | 3.72 | 5.56 | 3.45 | 4.70 | 1.94 | 47.86 | 39.77 | 5 |
| | 4.46 | | 7.70 | | 6.44 | | 7.24 | | 6.48 | | 5.61 | | 45.17 | |
| 2.76 | 1.27 | 3.96 | 1.27 | 3.96 | 2.77 | 4.11 | 2.42 | 4.16 | 1.92 | 3.04 | 1.41 | 39.88 | 31.62 | 14 |
| | 4.67 | | 5.89 | | 6.28 | | 7.86 | | 6.51 | | 4.23 | | 44.13 | |
| 2.70 | 1.50 | 2.73 | 1.11 | 4.46 | 2.94 | 5.05 | 4.08 | 4.49 | 2.72 | 2.90 | 1.40 | 39.85 | 31.77 | 6 |
| | 4.69 | | 5.41 | | 6.03 | | 7.58 | | 6.63 | | 4.70 | | 44.11 | |
| 2.89 | 1.23 | 3.20 | 1.74 | 4.11 | 2.94 | 4.62 | 2.77 | 4.14 | 2.26 | 2.83 | 1.05 | 40.02 | 32.04 | 10 |
| | 6.50 | | 7.43 | | 5.90 | | 9.08 | | 6.83 | | 6.42 | | 55.56 | |
| 3.28 | 1.57 | 4.04 | 2.18 | 4.32 | 2.50 | 4.55 | 2.54 | 3.74 | 1.80 | 3.07 | 1.56 | 41.71 | 33.47 | 21 |
| | 6.05 | | 6.47 | | 6.57 | | 6.63 | | 7.00 | | 6.09 | | 44.81 | |
| 2.61 | 1.24 | 3.77 | 1.97 | 4.15 | 1.81 | 4.15 | 2.28 | 3.50 | 1.69 | 2.65 | 1.23 | 36.66 | 29.27 | 10 |
| | 6.94 | | 5.82 | | 7.63 | | 6.21 | | 7.73 | | 7.29 | | 48.06 | |
| 2.55 | 1.16 | 3.85 | 2.28 | 4.00 | 2.09 | 4.14 | 2.17 | 3.56 | 1.41 | 2.95 | 1.01 | 38.33 | 30.47 | 10 |
| | 6.92 | | 6.70 | | 7.73 | | 7.47 | | 10.23 | | 4.11 | | 54.83 | |
| 3.07 | 1.72 | 3.75 | 1.78 | 5.13 | 3.55 | 4.06 | 2.35 | 4.50 | 1.54 | 3.94 | 1.98 | 42.98 | 30.58 | 7 |
| | 6.52 | | 6.31 | | 7.57 | | 8.48 | | 8.71 | | 6.20 | | 53.31 | |
| 2.66 | 1.57 | 4.20 | 1.25 | 4.78 | 3.34 | 4.42 | 2.27 | 3.67 | 1.61 | 3.17 | 1.06 | 41.17 | 30.45 | 10 |
| | 7.08 | | 5.82 | | 8.71 | | 6.23 | | 7.47 | | 6.70 | | 51.42 | |
| 2.70 | 1.19 | 4.04 | 1.33 | 4.78 | 2.72 | 4.09 | 2.18 | 3.82 | 1.46 | 3.94 | 0.73 | 40.76 | 32.48 | 10 |
| | 5.99 | | 7.26 | | 5.04 | | 7.05 | | 13.06 | | 4.20 | | 52.98 | |
| 3.09 | 1.08 | 3.96 | 1.72 | 3.99 | 3.30 | 4.13 | 1.94 | 6.24 | 2.70 | 2.89 | 2.29 | 42.98 | 30.80 | 5 |
| | 6.50 | | 7.46 | | 8.14 | | 11.64 | | 10.73 | | 5.16 | | 53.30 | |
| 2.80 | 1.67 | 4.13 | 0.98 | 4.77 | 1.90 | 4.91 | 3.08 | 3.80 | 0.68 | 3.22 | 1.22 | 42.98 | 35.19 | 9 |
| | 6.04 | | 6.33 | | 5.98 | | 5.09 | | 11.21 | | 3.29 | | 53.95 | |
| 2.35 | 1.48 | 4.07 | 1.92 | 4.53 | 2.84 | 4.92 | 2.68 | 5.15 | 2.40 | 2.77 | 1.86 | 43.90 | 34.00 | 5 |

| APRIL. | | MAY. | | JUNE. | | JULY. | | AUGUST. | | SEPTEMBER. | | YEAR. | | No. of Years. |
|--------|------|------|--------|-------|------|-------|------|---------|------|------------|------|--------|-------|---------------|
| M. | R. | L. | R. | M. | R. | M. | R. | M. | R. | M. | R. | Total. | R. | |
| | 7.10 | | 4.80 | | 3.20 | | 1.51 | | 1.53 | | 1.82 | | 27.04 | |
| 4.70 | 3.64 | 3.10 | 1.16 | 1.69 | 1.02 | 1.09 | 0.49 | 1.09 | 0.69 | 1.08 | 0.87 | 21.66 | 16.01 | 5 |
| | 6.43 | | 4.50 | | 4.28 | | 2.49 | | 2.19 | | 2.25 | | 36.94 | |
| 4.68 | 3.32 | 2.40 | 1.11 | 2.24 | 0.92 | 1.47 | 0.56 | 1.41 | 0.87 | 1.51 | 1.06 | 29.43 | 23.76 | 5 |
| | 4.53 | | 4.54 | | 3.08 | | 3.25 | | 1.60 | | 1.42 | | 28.08 | |
| 3.48 | 2.54 | 2.07 | 0.61 | 1.25 | 0.50 | 0.83 | 0.34 | 0.77 | 0.24 | 0.61 | 0.17 | 21.09 | 16.34 | 14 |
| | 4.46 | | 2.52 | | 1.79 | | 3.41 | | 1.53 | | 1.44 | | 27.18 | |
| 3.17 | 2.49 | 1.13 | 0.40 | 1.07 | 0.40 | 1.01 | 0.23 | 0.66 | 0.12 | 0.72 | 0.15 | 23.19 | 15.15 | 6 |
| | 5.45 | | 8.15 | | 2.44 | | 4.11 | | 1.41 | | 1.24 | | 27.60 | |
| 3.50 | 2.24 | 1.68 | 0.60 | 1.20 | 0.54 | 1.23 | 0.36 | 0.87 | 0.27 | 0.52 | 0.18 | 22.26 | 16.57 | 10 |
| | 6.24 | | 5.10 | | 3.37 | | 3.49 | | 1.28 | | 2.50 | | 34.20 | |
| 3.30 | 1.80 | 1.94 | 0.51 | 1.30 | 0.31 | 1.06 | 0.23 | 0.76 | 0.16 | 0.58 | 0.15 | 22.08 | 16.29 | 21 |
| | 4.60 | | 3.22 | | 2.18 | | 1.52 | | 2.66 | | 0.88 | | 21.46 | |
| 1.98 | 0.76 | 1.34 | (0.31) | 0.99 | 0.37 | 0.76 | 0.29 | 0.69 | 0.23 | 0.34 | 0.16 | 14.22 | 8.16 | 10 |
| | 4.79 | | 3.86 | | 3.07 | | 1.71 | | 3.15 | | 0.63 | | 19.78 | |
| 1.77 | 0.72 | 1.39 | 0.53 | 1.16 | 0.52 | 0.83 | 0.34 | 0.81 | 0.38 | 0.43 | 0.23 | 13.04 | 7.86 | 10 |
| | 4.45 | | 3.45 | | 3.05 | | 1.45 | | 3.08 | | 1.25 | | 24.73 | |
| 2.18 | 1.01 | 1.68 | 0.94 | 1.50 | 0.68 | 0.99 | 0.38 | 1.02 | 0.30 | 0.67 | 0.29 | 18.21 | 10.69 | 7 |
| | 4.98 | | 3.55 | | 3.15 | | 3.02 | | 2.71 | | 0.99 | | 26.30 | |
| 2.02 | 0.82 | 1.77 | 0.58 | 1.17 | 0.49 | 0.98 | 0.24 | 0.81 | 0.22 | 0.50 | 0.21 | 16.91 | 11.45 | 10 |
| | 4.20 | | 2.83 | | 3.00 | | 2.82 | | 2.49 | | 2.14 | | 21.33 | |
| 1.79 | 0.80 | 1.51 | 0.58 | 1.15 | 0.30 | 0.99 | 0.24 | 0.84 | 0.25 | 0.63 | 0.17 | 15.99 | 12.15 | 10 |
| | 3.67 | | 3.19 | | 1.51 | | 1.31 | | 4.01 | | 1.18 | | 25.15 | |
| 2.12 | 0.25 | 1.44 | 0.22 | 0.90 | 0.48 | 0.73 | 0.39 | 1.42 | 0.53 | 0.88 | 0.37 | 16.48 | 10.92 | 5 |
| | 4.90 | | 4.36 | | 2.54 | | 3.54 | | 5.73 | | 1.53 | | 29.66 | |
| 1.89 | 0.58 | 1.79 | 0.76 | 1.14 | 0.54 | 1.16 | 0.39 | 1.33 | 0.26 | 0.80 | 0.22 | 17.69 | 8.83 | 9 |
| | 3.49 | | 3.16 | | 1.73 | | 2.43 | | 4.94 | | 1.45 | | 25.16 | |
| 1.88 | 0.81 | 1.65 | 1.10 | 1.87 | 1.05 | 1.45 | 0.79 | 1.80 | 0.32 | 1.02 | 0.63 | 18.66 | 10.99 | 5 |

Monthly and yearly maximum, minimum, and mean loss, for an

[Note:—M = Mean:

RUN-OFF IN PERCENTAGE OF RAINFALL.

| Drainage. | OCTOBER. | | NOVEMBER. | | DECEMBER. | | JANUARY. | | FEBRUARY. | | MARCH. | |
|--------------------------------------|----------|------|-----------|-----|-----------|------|----------|------|-----------|------|--------|-----|
| | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. |
| Connecticut, above Orford..... | 41 | 92 | 57 | 129 | 46 | 108 | 38 | 55 | 34 | 86 | 114 | 163 |
| Housatonic, above Gaylordsville..... | 47 | 64 | 58 | 175 | 61 | 87 | 76 | 149 | 63 | (87) | 148 | 208 |
| Susquehanna, above Harrisburg..... | 30 | (18) | 41 | 22 | 59 | (87) | 71 | (41) | 74 | (39) | 184 | 277 |
| Susquehanna, above Wilkes-Barre..... | 35 | 44 | 40 | 105 | 77 | 19 | 112 | 183 | 111 | 209 | 197 | 228 |
| Susquehanna, above Williamsport..... | 39 | 6 | 40 | 85 | 56 | 140 | 76 | 90 | 73 | (47) | 146 | 78 |
| Ohio, above Wheeling..... | 27 | 58 | 49 | 68 | 64 | 102 | 86 | 116 | 98 | 146 | 151 | 191 |
| Potomac, above Point of Rocks..... | 24 | 10 | 42 | 19 | 56 | 15 | 76 | 50 | 73 | 43 | 127 | 74 |
| Shenandoah, above Millville..... | 33 | 72 | 114 | 99 | 99 | 199 | 199 | 199 | 151 | 191 | 191 | 191 |
| James, above Cartersville..... | 25 | 6 | 39 | 12 | 64 | 27 | 86 | 45 | 98 | 54 | 120 | 88 |
| James, above Buchanan..... | 24 | 102 | 41 | 76 | 10 | 51 | 80 | 69 | 83 | 82 | 82 | 41 |
| James, above Glasgow..... | 26 | 8 | 19 | 6 | 40 | 10 | 51 | 80 | 69 | 83 | 82 | 41 |
| Appomattox, above Mattoax..... | 28 | 623 | 64 | 862 | 9 | 47 | 37 | 78 | 49 | 139 | 108 | 148 |
| Roanoke, above Roanoke..... | 31 | 10 | 23 | 12 | 40 | 9 | 47 | 37 | 49 | 139 | 108 | 148 |
| Roanoke, above Randolph..... | 40 | 121 | 60 | 70 | 56 | 74 | 81 | 80 | 34 | 81 | 44 | 173 |
| | 25 | 13 | 26 | 28 | 46 | 21 | 56 | 81 | 80 | 34 | 81 | 44 |
| | 25 | 92 | 75 | 67 | 77 | 75 | 75 | 75 | 105 | 105 | 173 | 173 |
| | 24 | 8 | 29 | 14 | 43 | 11 | 49 | 24 | 64 | 16 | 86 | 40 |
| | 26 | 381 | 64 | 653 | 12 | 49 | 24 | 64 | 16 | 86 | 40 | 127 |
| | 28 | 8 | 28 | 11 | 42 | 12 | 49 | 24 | 64 | 16 | 86 | 40 |
| | 28 | 100 | 47 | 71 | 17 | 53 | 80 | 74 | 48 | 68 | 26 | 76 |
| | 28 | 11 | 29 | 13 | 39 | 17 | 53 | 80 | 74 | 48 | 68 | 26 |
| | 28 | 206 | 77 | 98 | 7 | 50 | 90 | 180 | 15 | 72 | 87 | 115 |
| | 31 | 9 | 31 | 15 | 39 | 7 | 50 | 13 | 60 | 15 | 72 | 87 |
| | 40 | 180 | 89 | 58 | 94 | 53 | 71 | 116 | 81 | 103 | 103 | 103 |
| | 40 | 25 | 17 | 43 | 94 | 53 | 86 | 56 | (81) | 65 | 41 | 41 |

LOSS, IN INCHES.

| Drainage. | OCTOBER. | | NOVEMBER. | | DECEMBER. | | JANUARY. | | FEBRUARY. | | MARCH. | |
|--------------------------------------|----------|-------|-----------|-------|-----------|-------|----------|-------|-----------|--------|--------|-------|
| | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. |
| Connecticut, above Orford..... | 1.75 | 2.60 | 0.94 | 3.08 | 1.56 | 2.43 | 1.56 | 1.97 | 1.06 | 2.15 | -0.47 | 1.92 |
| Housatonic, above Gaylordsville..... | 2.09 | 0.18 | 1.00 | -0.41 | 1.70 | -0.06 | 0.78 | 0.91 | 0.95 | 0.10 | -1.78 | 2.91 |
| Susquehanna, above Harrisburg..... | 2.12 | 3.24 | 1.55 | 3.23 | 1.22 | 2.68 | 0.79 | 1.99 | 0.69 | 2.36 | -1.78 | 0.66 |
| Susquehanna, above Wilkes-Barre..... | 2.17 | 0.98 | 1.45 | 0.67 | 0.77 | 0.96 | -0.32 | -1.05 | -0.96 | (0.30) | -1.13 | -4.46 |
| Susquehanna, above Williamsport..... | 2.05 | 4.16 | 1.60 | 3.42 | 1.40 | 2.76 | 0.87 | 1.84 | 0.76 | 2.14 | -1.50 | 1.65 |
| Ohio, above Wheeling..... | 1.94 | 3.45 | 1.88 | 3.40 | 1.14 | 1.70 | 0.46 | 0.83 | 0.07 | 0.65 | -1.78 | 0.80 |
| Potomac, above Point of Rocks..... | 1.68 | 4.71 | 1.85 | 3.58 | 1.61 | 2.82 | 1.26 | 1.50 | 0.91 | 1.52 | -0.68 | 1.02 |
| Shenandoah, above Millville..... | 1.65 | 4.78 | 1.60 | 3.87 | 1.56 | 2.65 | 1.37 | 1.91 | 1.59 | 2.32 | 0.62 | 2.00 |
| James, above Cartersville..... | 2.57 | 0.39 | 1.14 | 0.17 | 0.77 | 0.09 | 1.40 | 0.07 | 0.91 | 0.90 | -0.68 | 3.13 |
| James, above Buchanan..... | 1.92 | 4.78 | 1.71 | 3.88 | 1.70 | 2.67 | 1.43 | 2.09 | 1.41 | 2.32 | 0.72 | 2.62 |
| James, above Glasgow..... | 1.94 | 0.57 | 1.06 | 0.64 | 1.67 | 3.90 | 1.45 | 0.84 | 1.32 | 0.06 | 0.58 | -2.37 |
| Appomattox, above Mattoax..... | 2.07 | 6.22 | 1.58 | 3.60 | 2.30 | 3.10 | 1.53 | 1.83 | 0.89 | 2.30 | 1.07 | 2.55 |
| Roanoke, above Roanoke..... | 1.86 | 6.16 | 1.71 | 0.43 | 1.68 | 5.77 | 1.42 | 2.09 | 1.57 | 1.62 | 1.07 | -0.86 |
| Roanoke, above Randolph..... | 1.58 | -0.21 | 1.41 | 0.56 | 2.24 | 3.33 | 1.47 | 2.61 | 1.58 | 4.10 | 1.24 | 2.37 |
| | 1.86 | 3.96 | 1.71 | 3.91 | 1.68 | 3.83 | 1.42 | 2.61 | 1.57 | 4.10 | 1.24 | 2.53 |
| | 1.86 | -0.14 | 1.71 | 0.43 | 1.68 | 0.04 | 1.42 | 0.39 | 1.57 | -0.92 | 1.18 | 1.00 |
| | 1.86 | 3.72 | 1.71 | 2.13 | 1.68 | 4.28 | 1.42 | 2.06 | 1.57 | 2.73 | 1.18 | 2.86 |
| | 1.58 | -0.56 | 1.41 | 0.14 | 2.24 | 1.03 | 1.47 | 0.82 | 1.58 | -0.14 | 1.24 | -0.09 |

CONDITIONS AFFECTING STREAM FLOW.

149

rainfall, run-off in percentage of rainfall, and average year.

R = Range.]

| APRIL. | | MAY. | | JUNE. | | JULY. | | AUGUST. | | SEPTEMBER. | | YEAR. | | No. of Years |
|--------|-----|------|------|-------|-----|-------|----|---------|----|------------|----|-------|----|--------------|
| M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | Mean. | R. | |
| 170 | 206 | 104 | 420 | 45 | 68 | 25 | 38 | 28 | 39 | 28 | 34 | 59 | 65 | 5 |
| | 190 | | 65 | | 90 | | 13 | | 16 | | 23 | | 46 | |
| | 187 | | 118 | | 113 | | 61 | | 40 | | 80 | | 73 | |
| 125 | 105 | 81 | 73 | 41 | 90 | 29 | 11 | 25 | 18 | 23 | 17 | 63 | 53 | 5 |
| | 234 | | 73 | | 86 | | 47 | | 47 | | 73 | | 63 | |
| 124 | 25 | 52 | 21 | 31 | 10 | 20 | 9 | 18 | 6 | 20 | 5 | 55 | 44 | 14 |
| | 200 | | 50 | | 58 | | 43 | | 24 | | 74 | | 65 | |
| 117 | 96 | 41 | 96 | 24 | 10 | 20 | 7 | 15 | 4 | 25 | 11 | 53 | 47 | 6 |
| | 276 | | 69 | | 66 | | 54 | | 22 | | 56 | | 63 | |
| 121 | 85 | 52 | 24 | 29 | 12 | 27 | 12 | 21 | 7 | 18 | 7 | 56 | 42 | 10 |
| | 156 | | 62 | | 67 | | 53 | | 56 | | 39 | | 53 | |
| 98 | 58 | 46 | 12 | 30 | 10 | 23 | 9 | 20 | 5 | 17 | 6 | 54 | 44 | 21 |
| | 104 | | 57 | | 46 | | 24 | | 23 | | 23 | | 61 | |
| 76 | 85 | 36 | (11) | 24 | 11 | 18 | 9 | 20 | 10 | 13 | 4 | 39 | 29 | 10 |
| | 113 | | 65 | | 41 | | 43 | | 41 | | 41 | | 58 | |
| 69 | 81 | 36 | 14 | 24 | 13 | 20 | 11 | 23 | 10 | 15 | 5 | 36 | 21 | 10 |
| | 101 | | 66 | | 54 | | 37 | | 80 | | 44 | | 50 | |
| 71 | 48 | 43 | 22 | 29 | 18 | 24 | 12 | 24 | 11 | 21 | 8 | 43 | 23 | 7 |
| | 123 | | 70 | | 52 | | 38 | | 39 | | 80 | | 58 | |
| 76 | 40 | 42 | 19 | 25 | 14 | 22 | 8 | 22 | 5 | 16 | 8 | 41 | 28 | 10 |
| | 128 | | 68 | | 52 | | 38 | | 23 | | 23 | | 53 | |
| 66 | 37 | 37 | 18 | 24 | 9 | 24 | 10 | 22 | 6 | 19 | 6 | 39 | 23 | 10 |
| | 113 | | 54 | | 41 | | 32 | | 31 | | 49 | | 48 | |
| 69 | 43 | 36 | 24 | 23 | 13 | 18 | 9 | 23 | 14 | 29 | 14 | 38 | 30 | 5 |
| | 89 | | 15 | | 57 | | 43 | | 53 | | 37 | | 56 | |
| 66 | 25 | 43 | 75 | 24 | 14 | 24 | 12 | 35 | 8 | 24 | 7 | 41 | 23 | 9 |
| | 87 | | 66 | | 35 | | 40 | | 44 | | 44 | | 57 | |
| 56 | 31 | 41 | 23 | 30 | 21 | 29 | 16 | 35 | 24 | 37 | 25 | 43 | 32 | 5 |

| APRIL. | | MAY. | | JUNE. | | JULY. | | AUGUST. | | SEPTEMBER. | | YEAR. | | No. of Years |
|--------|-------|-------|-------|-------|-------|-------|------|---------|------|------------|------|--------|-------|--------------|
| M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | M. | R. | Total. | R. | |
| | -0.70 | | 1.07 | | 4.23 | | 3.81 | | 3.03 | | 3.74 | | 18.81 | |
| -1.94 | -3.02 | -0.11 | -1.39 | 2.00 | 1.05 | 3.25 | 2.41 | 2.79 | 2.00 | 2.70 | 0.71 | 15.10 | 12.84 | 5 |
| | -0.20 | | 1.74 | | 6.14 | | 5.06 | | 5.71 | | 5.19 | | 22.56 | |
| -0.22 | -2.20 | 0.57 | -0.22 | 3.23 | -0.25 | 5.53 | 1.56 | 4.15 | 2.08 | 3.19 | 0.89 | 18.43 | 13.39 | 5 |
| | 1.37 | | 3.16 | | 5.57 | | 4.41 | | 5.25 | | 4.81 | | 21.04 | |
| -0.67 | -2.64 | 1.89 | 0.58 | 2.73 | 0.40 | 3.28 | 1.94 | 3.39 | 1.22 | 2.43 | 0.63 | 18.29 | 18.54 | 14 |
| | 0.21 | | 2.87 | | 5.30 | | 4.53 | | 5.10 | | 3.76 | | 18.61 | |
| -0.46 | -0.47 | 1.00 | 0.71 | 3.39 | 1.32 | 4.04 | 3.47 | 3.33 | 2.63 | 2.18 | 0.43 | 16.66 | 14.53 | 6 |
| | 1.50 | | 2.26 | | 5.05 | | 4.58 | | 5.18 | | 4.39 | | 20.89 | |
| -0.61 | -3.54 | 1.52 | 0.94 | 2.91 | 1.25 | 3.39 | 2.41 | 3.27 | 0.96 | 2.31 | 0.87 | 17.73 | 15.70 | 10 |
| | 2.00 | | 3.14 | | 4.91 | | 6.07 | | 5.44 | | 4.50 | | 24.86 | |
| 0.07 | -1.56 | 2.10 | 0.95 | 3.02 | 1.33 | 3.50 | 2.26 | 2.98 | 1.09 | 2.53 | 0.81 | 19.02 | 15.18 | 21 |
| | 1.00 | | 3.77 | | 4.49 | | 5.41 | | 5.23 | | 5.84 | | 29.09 | |
| 0.63 | -0.14 | 2.43 | 1.26 | 3.16 | 1.33 | 3.39 | 1.94 | 2.81 | 1.27 | 2.31 | 1.08 | 22.44 | 18.87 | 10 |
| | 1.22 | | 3.92 | | 5.14 | | 5.11 | | 4.58 | | 6.33 | | 33.05 | |
| 0.73 | -0.30 | 2.46 | 1.46 | 3.74 | 1.49 | 3.31 | 1.73 | 2.75 | 1.03 | 2.52 | 0.76 | 21.69 | 14.58 | 10 |
| | 2.47 | | 3.59 | | 5.37 | | 4.93 | | 7.14 | | 3.54 | | 30.79 | |
| 0.39 | -0.02 | 2.12 | 0.60 | 3.63 | 2.57 | 3.07 | 1.94 | 3.48 | 1.34 | 2.57 | 1.33 | 21.77 | 18.90 | 7 |
| | 1.54 | | 4.10 | | 5.77 | | 5.46 | | 6.00 | | 5.21 | | 32.38 | |
| 0.64 | -0.37 | 2.43 | 0.23 | 3.60 | 2.79 | 3.44 | 1.87 | 2.80 | 1.30 | 2.67 | 0.83 | 24.26 | 14.59 | 10 |
| | 2.28 | | 3.47 | | 6.37 | | 4.13 | | 4.98 | | 4.56 | | 30.46 | |
| 0.91 | -0.45 | 2.53 | 0.41 | 3.63 | 1.93 | 3.10 | 1.91 | 2.97 | 1.15 | 2.61 | 0.50 | 24.77 | 16.29 | 10 |
| | 2.51 | | 4.07 | | 4.04 | | 6.43 | | 9.05 | | 3.46 | | 36.10 | |
| 0.35 | -0.41 | 2.52 | 0.79 | 3.09 | 2.19 | 3.40 | 1.51 | 4.32 | 2.17 | 2.07 | 1.22 | 26.50 | 19.83 | 5 |
| | 1.70 | | 4.91 | | 6.35 | | 8.10 | | 4.99 | | 4.31 | | 31.71 | |
| 0.91 | 0.20 | 2.30 | -0.23 | 3.63 | 0.81 | 3.75 | 2.44 | 2.47 | 0.73 | 2.53 | 0.84 | 24.99 | 15.91 | 9 |
| | 2.35 | | 4.75 | | 4.75 | | 6.30 | | 6.27 | | 1.99 | | 29.33 | |
| 1.47 | 0.24 | 2.42 | 0.65 | 3.16 | 1.76 | 3.47 | 1.87 | 3.35 | 1.53 | 1.75 | 1.31 | 25.14 | 16.00 | 5 |

ground, surface, and snow storage. As data in regard to them are not available as a rule, it has been impossible to allow for their effects.

The table^a (pp. 146-149) shows, for various drainage areas in the northeastern United States, the monthly and yearly rainfall, run-off, and loss for each of the years for which run-off records are available. The records of precipitation were in some instances incomplete, and figures for several months in the period considered were missing. In such cases the mean of the records for the stations available was taken as the mean for the month in question. Interpolation for supplying missing rainfall data adds nothing to the accuracy of the record and is probably never justifiable by theory or facts. The records of mean annual run-off for all important stations in the United States have been compiled in uniform manner, and the results used in the construction of a run-off map shown in Pl. X.^b

EVAPORATION.

All precipitated water, in some portion of its course over the earth's surface, is subjected to the effects of evaporation, whereby a portion is returned to the atmosphere again and thus disappears from the surface waters.


The principal conditions on which the amount of evaporation depends are the temperature of the atmosphere and of the surface from which evaporation takes place, the relative humidity of the air, and the wind movement. The greatest of these factors is temperature, although the others are important. The greater the wind movement the lower the relative humidity, and the higher the temperature the greater the evaporation. Consequently the rate of evaporation from land surface and from rivers, lakes, canals, or reservoirs varies widely in different localities, and in the same locality in different seasons.

The determination of the amount of evaporated water received by the air from land surfaces is very difficult, and no satisfactory direct measurements have been made. The best information available in regard to this phenomenon has been obtained by subtracting from the total annual precipitation, expressed in inches of depth on the basin, the total annual run-off expressed in the same unit. The difference represents closely the total loss by evaporation from the land and water surfaces of the basin (see table on pp. 146-149).

The measurement of evaporation from water surfaces offers considerable difficulties, but approximate records have been collected at many

^a See Proceedings of the American Society of Civil Engineers, Vol. XXXIII, May, 1907.

^b See Water-Supply Paper No. 301, U. S. Geol. Survey.



N-OFF

es

Prepared by Henry Gannett
mainly from data of the
United States Geological Survey

points. These records are of great value in studies of artificial storage, since the total annual storage is diminished by the annual evaporation from the water surface.

The method adopted for measuring the evaporation from a body of water consists in measuring the loss of water from a pan (Pl. VIII, A), which is so placed that the contained water has as nearly as possible the same temperature and exposure as that of the water which it is intended to represent.

In order that the proper conditions of temperature and exposure may be most nearly attained the pan is either floated in the water at a place where the wind velocity is the average for the body of water under consideration, or, in occasional cases, is sunk nearly to its top in marshy ground. In general, the condition that the pan should be in a place of average wind velocity must be sacrificed to the practical requirement that the water about the pan when it is floated shall be so still that water will not slop in or out and that accurate observation of its height can be made. The location should therefore be chosen with a view to securing a body of relatively quiet water around the pan. The pan should be floated as deep as possible and the water in the pan maintained as near the top as possible, consistent with the requirement that the wind does not drive water in or out of the pan by direct splashing. It is usually not possible to maintain the height above $1\frac{1}{2}$ inches below the rim. The height of water in the pan may be read by means of an inclined scale of such form that the readings, which must be made to hundredths of an inch of vertical elevation, are magnified by the inclination of the scale. It is better, however, to use a point projecting from the center of the pan, fixed at a uniform height, the water in the pan being restored night and morning to such a height that the point is just submerged. The height of water in the pan is thus maintained at practically the same distance below the rim, and the magnitude of errors of observation is reduced.

For the purpose of ascertaining the amount of evaporation a small cup is provided, the cubical contents of which is exactly equivalent to that of the pan at a depth of one one-hundredth of an inch. Such a cup, of cylindrical form, is 4.13 inches high and 2 inches in diameter for a pan 36 inches square. When an observation is to be made the pan should be level. The cup should then be filled with water. This is emptied into the pan and the operation is repeated until the point is exactly submerged. The number of cupfuls emptied into the pan is the amount of water, in hundredths of an inch that is evaporated. If a rain storm has occurred and the point in the center of the pan has been

submerged, water must be dipped out of the pan and the exact number of cupfuls noted.

Reports of the observations should contain data on wind movement, temperature of water inside and outside the pan, amount of precipitation, and amount of water added to or removed from the pan. The annual evaporation from water surfaces varies from 20 to 40 inches in the humid Eastern States to 70 to 100 inches in the arid West.

In all sections of the country and under all conditions, practically all of the precipitation is either evaporated or appears ultimately as surface water. The only exceptions are the small amounts which are lost permanently to the ground or which undergo chemical change by vegetable growth or by entering into composition with other minerals. The major part of all ground water becomes a part of the surface water again by flowing from springs, or is transmitted directly to the atmosphere by transpiration from vegetation.

The difference between annual rainfall and run-off thus represents very closely the annual evaporation.

The effects of evaporation extend, therefore, both to the total flow of streams, as indicated above, and to the distribution of flow by the different rates of evaporation for different seasons.

The major part of summer precipitation returns in a relatively short time to the atmosphere, while the winter precipitation remains longer on the surface and practically all runs off either directly as winter or spring flow, or later as summer flow from ground water. A comparison of rainfall and run-off for the summer and winter seasons, as shown in the table on page 153, illustrates forcibly the effect of evaporation on the regimen of the streams and the remarkable constancy of the total yearly evaporation in the sections covered by the data. It also shows the direct variation of the yearly evaporation with the mean annual temperature and the remarkably small losses during the period of low temperatures.

TEMPERATURE.

Temperature is the chief factor affecting evaporation and rainfall and thereby affects both the total run-off and its distribution. Low temperature exerts a further effect, mainly on the distribution of flow, by forming snow and ice and temporarily storing the precipitated moisture.

Storage resulting from low temperature is an important factor in the regimen of streams in high latitudes and in mountainous areas. A

few determinations of the quantity of such storage have been made by collecting cylindrical samples of the snow and ice, extending from the surface of the snow to the ground, and melting each such sample to determine the equivalent depth of water. The relation between depth of snow and equivalent depth of water varies with the temperature at the times of the snowfalls and also, generally much more, with the length of time the snows have remained on the ground, because the weight of snow above and the absorption of rains, if any, or of water from melting snows, serve to compact the snow and thereby to increase the water equivalent for a given depth.

Rainfall, run-off, run-off in percentage of rainfall, and loss, for the winter and the summer months, for the mean year.^a

| Station. | WINTER MONTHS, DEC. TO APR., INCLUSIVE. | | | | SUMMER MONTHS, JUNE, JULY, AUGUST. | | | | Total yearly loss. |
|--|--|----------|---------------------------|-------|---------------------------------------|----------|---------------------------|-------|--------------------|
| | Rainfall. | Run-off. | Percentage of run-off. | Loss. | Rainfall. | Run-off. | Percentage of run-off. | Loss. | |
| Connecticut, at Orford, N. H. | 12.89 | 11.19 | 87 | 1.70 | 12.00 | 8.87 | 83 | 8.13 | 15.10 |
| Lionsatic, at Gaylordsville, Conn. | 17.80 | 17.12 | 96 | 0.68 | 16.02 | 5.12 | 32 | 10.90 | 18.43 |
| Susquehanna, at Harrisburg, Pa. | 14.48 | 18.58 | 94 | 0.90 | 12.25 | 2.85 | 23 | 9.40 | 18.39 |
| Susquehanna, at Wilkes- Barre, Pa. | 14.47 | 16.48 | 114 | -2.01 | 14.00 | 2.74 | 20 | 11.26 | 16.66 |
| Susquehanna, at Williams- port, Pa. | 15.48 | 14.76 | 95 | 0.72 | 12.87 | 8.30 | 66 | 9.57 | 17.76 |
| Ohio, at Wheeling, W. Va. | 18.33 | 15.16 | 93 | 1.07 | 12.61 | 8.12 | 65 | 9.49 | 19.08 |
| Potomac, at Point of Rocks, Md. | 14.14 | 9.14 | 65 | 5.00 | 11.80 | 2.44 | 21 | 9.36 | 22.64 |
| Shenandoah, at Millville, W. Va. | 14.38 | 7.73 | 54 | 6.65 | 12.67 | 2.70 | 22 | 9.90 | 24.69 |
| James, at Cartersville, Va. | 16.96 | 10.76 | 63 | 6.19 | 18.69 | 8.51 | 46 | 10.18 | 24.77 |
| James, at Buchanan, Va. | 15.99 | 10.37 | 65 | 5.62 | 12.87 | 2.97 | 23 | 9.90 | 24.36 |
| North (of James) Glasgow, Va. | 15.89 | 9.57 | 60 | 6.32 | 12.69 | 2.98 | 23 | 9.71 | 24.77 |
| Appomattox, at Mattoax, Va. | 16.87 | 9.89 | 59 | 6.98 | 14.36 | 8.05 | 56 | 11.31 | 26.50 |
| Roanoke, at Roanoke, Va. | 16.50 | 9.84 | 60 | 6.66 | 13.48 | 3.68 | 27 | 9.80 | 24.99 |
| Roanoke, at Randolph, Va. | 17.53 | 9.53 | 54 | 8.00 | 14.60 | 4.63 | 32 | 9.97 | 26.14 |

^aFor the number of years records see table on pp. 136-139.

GEOLOGY.

Aside from its effect on topography, which results directly from it, geology has an important influence on the regimen of stream flow in two ways, which relate to the nature and depth of the soil and the dip of the strata. It affects both the total run-off and its regimen.

Rain that falls upon a sandy soil enters it almost immediately, with a minimum loss through evaporation, is retained there tempo-

rarily, and readily and gradually flows from it to springs and rivers. Clay and loam receive water much less readily and give it up much less freely. Large areas and depths of sand are therefore among the best natural regulators of stream flow.

Basins of bare rock, on the other hand, shed immediately the major portion of the water that falls upon them. Between these two extremes of rock and sand are all grades of clay, silt, and loam, of varying depths, affecting very decidedly the regimen of the streams that drain them.

The dip of the strata and their porosity are often important on account of their effect on the courses of streams and on the concentration of fall, but also on the amount of water absorbed by the ground to appear elsewhere as springs in the same or another drainage basin, or to be lost permanently to the ground, unless it is brought to the surface again by means of some deep well.

TOPOGRAPHY.

The general topography of the country affects largely both the total amount and the distribution of the run-off. Its influence on the total run-off is derived principally from its effect on precipitation. Mountain ranges frequently cause the precipitation of large quantities of moisture upon them, thereby decreasing the moisture and the clouds in the atmosphere, which they intercept, so that little precipitation occurs beyond the range. By their storage of snow, mountainous areas form the principal reservoirs for the water supply of western streams.

The nature of the slopes of the basin and stream affects principally the distribution of run-off. Steep slopes discharge their water rapidly and as a rule store relatively small amounts of ground water. Flat areas, on the other hand, if pervious, absorb much of the water that falls upon them and yield it up gradually.

Rivers draining steep slopes and having steep beds are therefore "flashy" in character, having great ranges in stage and very small minimum discharges. Rivers that drain flat countries, containing swamp or sand areas, fluctuate less rapidly, having fairly uniform stage and relatively large minimum discharge.

The shape and size of a drainage basin has a decided effect on the streams draining it. The flow from basins which are so large that they cover considerable latitude may be materially affected thereby on account of the difference in the times at which the snows are melted. Rivers flowing southward may discharge the snow water without serious freshet, since the snows melt gradually, beginning in the southern part

and gradually extending toward the north. On the other hand, rivers flowing northward are more liable to freshets from the accumulation of water as the higher temperatures advance north, and to ice-jams and consequent freshets from backwater therefrom, because of the greater thickness and strength of the more northern ice. Rivers flowing east and west are more liable to have the same temperature conditions throughout the whole basin and consequently an accumulation of waters resulting from freshets simultaneously in all tributaries. The shape of the basin, whether long or palmate, affects in a similar way the accumulation of freshet waters.

The shape of the basin and the direction of its axis relative to the direction of motion of prevailing storms is often an important factor in determining the magnitude of freshets. Basins whose axes lie in such direction of motion of storms and whose streams flow in the direction of such motion rather than against it are especially liable to excessive freshets.

The surfaces of lakes and ponds affect the regimen of streams in two ways—first, by decreasing the total annual run-off, on account of the great evaporation from their surfaces, and second, by equalizing flow and making the discharge more regular. They are also important on account of their availability for artificial storage. Swamp areas affect streams in much the same way, especially as regards their regimen.

VEGETATION.

Vegetation affects very largely the regimen of streams. Its influence does not probably extend to rainfall but pertains principally to effects on surface and ground storage and evaporation.

The ground storage is increased on account of the greater receptivity of a soil loosened and opened by roots and a surface covered with fallen leaves and litter. The roots and cover retard the flow of water over the surface and thereby promote the absorption of the water by the soils. The effect of forests on ground storage is therefore a minimum on open, sandy soils, which would readily absorb water under all conditions, and a maximum on heavy, compact soils and clays, which do not take up water easily.

The differences between evergreen and deciduous forests or between large and small trees in their effects on ground storage are probably small. Young trees and bushes, or even grass and weeds, produce approximately the same effects in this respect as virgin forests. In their effects on temperature and resultant evaporation, and especially

on snow storage, the differences in forests are great. In the latter respect, especially, dense evergreen growths have much more marked effects than open or deciduous growths. Unfortunately the magnitudes of their effects have not been measured, and the conclusions in regard to them are based rather on general observations than on measured differences in stream flow. The variety of conditions existing within basins of considerable size makes exact determinations of the effect of the various factors very difficult. Many attempts have been made to study the magnitude of the effects of forests on stream flow, but without satisfactory success. In order that such observations may result in definite conclusions it is necessary that conditions of climate, geology, and topography shall be the same, and that the only differences shall pertain to forestation. Such conditions are not readily found or produced.

ARTIFICIAL CONTROL.

Artificial control of the flow of surface water may be effected either by storage in ponds, lakes, or reservoirs, or by drainage of swamp or wet areas by drains or open ditches.

Artificial storage is generally cheapest and its results greatest in glaciated regions, where natural ponds and lakes available for increased storage are numerous. By means of such artificial storage freshet flows are diminished and low flows increased.

By artificial drainage, on the other hand, the opposite effects are produced. It is believed that a considerable proportion of the effects on stream flow usually ascribed to deforestation and cultivation are due to the artificial surface and subsurface drainage which has been accomplished incidental to cultivation.

TABLES.

TABLES.

There are available a large number of tables for facilitating the computations in various hydraulic problems. It is often necessary, however, for the engineer to prepare special tables adapted to the problem in hand. Among the tables available are a number having wide application, which are given on the following pages.

These tables have been adapted from Water-Supply Papers of the U. S. Geological Survey.

In connection with the use of these tables attention is called to Barlow's tables and to Crelle's Rechentafeln. The former tables give for numbers from 1 to 10,000 the squares, cubes, square roots, cube roots, etc. The latter give products of all numbers between 1 and 1000, and can be used both for multiplication and division.

LIST OF TABLES.

TABLE I. Discharge in second-feet over rectangular sharp-crested weirs having complete end contractions.

$$[\text{Formula: } Q = 3.33 (l - .2H) H^{3/2}]$$

TABLE II. Discharge in second-feet per foot of crest over rectangular sharp-crested weirs without end contractions.

$$[\text{Formula: } Q = 3.33 l H^{3/2}]$$

TABLE III. Discharge in second-feet per foot of crest length for certain broad-crested weirs.

$$[\text{Formula: } Q = 2.64 l H^{3/2}]$$

TABLE IV. Discharge in second-feet per foot of crest over sharp-crested rectangular weirs without end contractions.

$$[\text{Formula: } Q = (0.405 + \frac{.00984}{H}) (1 + 0.55 \frac{H^2}{(p+H)^2}) l H \sqrt{2gH}]$$

TABLE V. Multipliers to be used in connection with Table IV to obtain the discharge over broad-crested weirs of rectangular cross-section of type *a*, Fig. 38.

TABLE VI. Multipliers to be used in connection with Table IV to obtain the discharge over broad-crested weirs of trapezoidal cross-section of types *b* and *c*, Fig. 38.

TABLE VII. Multipliers to be used in connection with Table IV to obtain the discharge over broad-crested weirs of compound cross section of types *d* to *m* inclusive, Fig. 38.

TABLE VIII. Three-halves powers of numbers.

TABLE IX. For converting discharge in second-feet per square mile into run-off in depth in inches over the area.

TABLE X. For converting discharge in second-feet into run-off in acre-feet.

TABLE XI. For converting discharge in second-feet per day into run-off in millions of gallons.

TABLE XII. For converting run-off in millions of gallons into discharge in second-feet per day.

TABLE XIII. For converting run-off in acre-feet into run-off in million gallons.

TABLE XIV. For converting run-off in million gallons into run-off in acre-feet.

TABLE XV. Values of *c* for use in the Chezy formula: $V = c \sqrt{R_s}$.

TABLE XVI. Square roots of numbers (\sqrt{R} , \sqrt{s}) for use in Kutter's formula.

TABLE XVII. Convenient equivalents.

Table I.—Discharges in second-feet, over rectangular sharp-crested weirs having

| | Head. | | Length of weir. | | | | | | | | | | | |
|----|---------|--------|-----------------|--------|---------|--------|--------|--------|--------|--------------|--------|--------------|--------|--------------|
| | Inches. | Feet. | 4 in. | 6 in. | 9 in. | 12 in. | 15 in. | 18 in. | 24 in. | 2 ft., 6 in. | 3 ft. | 3 ft., 6 in. | 4 ft. | 4 ft., 6 in. |
| 1 | 0.010 | 0.0011 | 0.0017 | 0.0026 | 0.00353 | 0.0125 | 0.0150 | 0.0200 | 0.0250 | 0.0300 | 0.0350 | 0.0400 | 0.0450 | 0.0450 |
| 2 | 0.021 | 0.0033 | 0.0050 | 0.0075 | 0.00997 | 0.0229 | 0.0275 | 0.0367 | 0.0459 | 0.0551 | 0.0643 | 0.0735 | 0.0821 | 0.0821 |
| 3 | 0.031 | 0.0060 | 0.0091 | 0.0137 | 0.0183 | 0.0352 | 0.0422 | 0.0564 | 0.0706 | 0.0847 | 0.0989 | 0.113 | 0.127 | 0.127 |
| 4 | 0.042 | 0.0092 | 0.0139 | 0.0210 | 0.0281 | 0.0491 | 0.0590 | 0.0788 | 0.0986 | 0.118 | 0.138 | 0.158 | 0.178 | 0.178 |
| 5 | 0.052 | 0.0128 | 0.0194 | 0.0293 | 0.0392 | 0.0644 | 0.0774 | 0.103 | 0.129 | 0.155 | 0.181 | 0.207 | 0.233 | 0.233 |
| 6 | 0.062 | 0.0167 | 0.0254 | 0.0384 | 0.0514 | 0.0810 | 0.0974 | 0.130 | 0.163 | 0.196 | 0.229 | 0.261 | 0.294 | 0.294 |
| 7 | 0.073 | 0.0209 | 0.0318 | 0.0482 | 0.0646 | 0.0988 | 0.119 | 0.159 | 0.199 | 0.239 | 0.279 | 0.319 | 0.359 | 0.359 |
| 8 | 0.083 | 0.0254 | 0.0387 | 0.0587 | 0.0788 | 0.118 | 0.142 | 0.189 | 0.237 | 0.285 | 0.333 | 0.381 | 0.428 | 0.428 |
| 9 | 0.094 | 0.0301 | 0.0463 | 0.0699 | 0.0938 | 0.138 | 0.166 | 0.222 | 0.278 | 0.334 | 0.389 | 0.445 | 0.501 | 0.501 |
| 10 | 0.104 | 0.0349 | 0.0536 | 0.0816 | 0.110 | 0.159 | 0.191 | 0.255 | 0.320 | 0.385 | 0.449 | 0.514 | 0.578 | 0.578 |
| 11 | 0.115 | 0.0401 | 0.0616 | 0.0939 | 0.126 | 0.180 | 0.217 | 0.291 | 0.364 | 0.438 | 0.511 | 0.585 | 0.659 | 0.659 |
| 12 | 0.125 | 0.0454 | 0.0699 | 0.107 | 0.144 | 0.203 | 0.244 | 0.327 | 0.410 | 0.493 | 0.576 | 0.659 | 0.742 | 0.742 |
| 13 | 0.135 | 0.0508 | 0.0784 | 0.120 | 0.161 | 0.226 | 0.273 | 0.365 | 0.458 | 0.551 | 0.644 | 0.736 | 0.829 | 0.829 |
| 14 | 0.146 | 0.0564 | 0.0873 | 0.134 | 0.180 | 0.251 | 0.302 | 0.405 | 0.508 | 0.611 | 0.714 | 0.816 | 0.919 | 0.919 |
| 15 | 0.156 | 0.0622 | 0.0965 | 0.148 | 0.199 | 0.276 | 0.332 | 0.446 | 0.559 | 0.672 | 0.786 | 0.899 | 1.012 | 1.012 |
| 16 | 0.167 | 0.0680 | 0.106 | 0.162 | 0.219 | 0.301 | 0.364 | 0.488 | 0.612 | 0.736 | 0.860 | 0.984 | 1.108 | 1.108 |
| 17 | 0.177 | 0.0743 | 0.115 | 0.177 | 0.239 | 0.323 | 0.395 | 0.531 | 0.666 | 0.801 | 0.936 | 1.071 | 1.206 | 1.206 |
| 18 | 0.187 | 0.0793 | 0.125 | 0.193 | 0.260 | 0.355 | 0.428 | 0.575 | 0.722 | 0.868 | 1.015 | 1.161 | 1.308 | 1.308 |
| 19 | 0.198 | 0.0852 | 0.135 | 0.208 | 0.282 | 0.383 | 0.462 | 0.620 | 0.778 | 0.937 | 1.095 | 1.253 | 1.412 | 1.412 |
| 20 | 0.208 | 0.0924 | 0.145 | 0.224 | 0.303 | 0.411 | 0.496 | 0.667 | 0.837 | 1.007 | 1.178 | 1.348 | 1.518 | 1.518 |
| 21 | 0.219 | 0.0997 | 0.155 | 0.241 | 0.326 | 0.440 | 0.531 | 0.714 | 0.897 | 1.079 | 1.262 | 1.444 | 1.627 | 1.627 |
| 22 | 0.229 | 0.1071 | 0.166 | 0.257 | 0.349 | 0.469 | 0.567 | 0.762 | 0.958 | 1.153 | 1.348 | 1.543 | 1.739 | 1.739 |
| 23 | 0.24 | 0.1146 | 0.177 | 0.274 | 0.372 | 0.499 | 0.604 | 0.812 | 1.020 | 1.228 | 1.436 | 1.644 | 1.852 | 1.852 |
| 24 | 0.25 | 0.1221 | 0.187 | 0.291 | 0.395 | 0.530 | 0.641 | 0.862 | 1.083 | 1.305 | 1.526 | 1.747 | 1.968 | 1.968 |
| 25 | 0.263 | 0.1296 | 0.198 | 0.309 | 0.420 | 0.561 | 0.679 | 0.913 | 1.148 | 1.383 | 1.617 | 1.852 | 2.087 | 2.087 |
| 26 | 0.271 | 0.1371 | 0.209 | 0.327 | 0.444 | 0.593 | 0.717 | 0.966 | 1.214 | 1.462 | 1.711 | 1.959 | 2.207 | 2.207 |
| 27 | 0.281 | 0.1446 | 0.220 | 0.345 | 0.469 | 0.625 | 0.756 | 1.018 | 1.281 | 1.543 | 1.805 | 2.068 | 2.330 | 2.330 |
| 28 | 0.292 | 0.1521 | 0.232 | 0.363 | 0.494 | 0.658 | 0.796 | 1.072 | 1.349 | 1.625 | 1.902 | 2.178 | 2.455 | 2.455 |
| 29 | 0.302 | 0.1596 | 0.243 | 0.381 | 0.520 | 0.691 | 0.836 | 1.127 | 1.418 | 1.709 | 2.000 | 2.291 | 2.581 | 2.581 |
| 30 | 0.312 | 0.1671 | 0.254 | 0.400 | 0.545 | 0.724 | 0.877 | 1.183 | 1.488 | 1.794 | 2.099 | 2.405 | 2.710 | 2.710 |
| 31 | 0.323 | 0.1746 | 0.265 | 0.419 | 0.572 | 0.758 | 0.919 | 1.239 | 1.559 | 1.880 | 2.200 | 2.521 | 2.841 | 2.841 |
| 32 | 0.333 | 0.1821 | 0.276 | 0.438 | 0.598 | 0.793 | 0.961 | 1.296 | 1.632 | 1.967 | 2.303 | 2.638 | 2.974 | 2.974 |
| 33 | 0.344 | 0.1896 | 0.287 | 0.457 | 0.625 | 0.828 | 1.003 | 1.354 | 1.705 | 2.056 | 2.407 | 2.759 | 3.105 | 3.105 |
| 34 | 0.354 | 0.1971 | 0.298 | 0.477 | 0.652 | 0.863 | 1.046 | 1.413 | 1.779 | 2.146 | 2.512 | 2.879 | 3.249 | 3.249 |
| 35 | 0.365 | 0.2046 | 0.309 | 0.496 | 0.680 | 0.899 | 1.090 | 1.472 | 1.854 | 2.237 | 2.619 | 3.001 | 3.384 | 3.384 |
| 36 | 0.375 | 0.2121 | 0.320 | 0.516 | 0.707 | 0.935 | 1.134 | 1.532 | 1.930 | 2.329 | 2.727 | 3.126 | 3.524 | 3.524 |
| 37 | 0.385 | 0.2196 | 0.331 | 0.535 | 0.735 | 0.971 | 1.178 | 1.593 | 2.008 | 2.422 | 2.837 | 3.252 | 3.666 | 3.666 |
| 38 | 0.396 | 0.2271 | 0.342 | 0.554 | 0.764 | 1.009 | 1.224 | 1.655 | 2.086 | 2.517 | 2.949 | 3.380 | 3.811 | 3.811 |
| 39 | 0.406 | 0.2346 | 0.353 | 0.573 | 0.793 | 1.045 | 1.269 | 1.717 | 2.164 | 2.612 | 3.060 | 3.508 | 3.956 | 3.956 |
| 40 | 0.417 | 0.2421 | 0.364 | 0.592 | 0.821 | 1.082 | 1.315 | 1.779 | 2.244 | 2.709 | 3.174 | 3.638 | 4.103 | 4.103 |
| 41 | 0.427 | 0.2496 | 0.375 | 0.611 | 0.850 | 1.120 | 1.361 | 1.843 | 2.324 | 2.806 | 3.288 | 3.770 | 4.252 | 4.252 |
| 42 | 0.437 | 0.2571 | 0.386 | 0.630 | 0.879 | 1.158 | 1.407 | 1.906 | 2.405 | 2.904 | 3.404 | 3.903 | 4.402 | 4.402 |
| 43 | 0.448 | 0.2646 | 0.397 | 0.649 | 0.908 | 1.196 | 1.455 | 1.971 | 2.488 | 3.005 | 3.521 | 4.038 | 4.555 | 4.555 |
| 44 | 0.458 | 0.2721 | 0.408 | 0.668 | 0.938 | 1.235 | 1.502 | 2.037 | 2.571 | 3.105 | 3.640 | 4.174 | 4.708 | 4.708 |
| 45 | 0.469 | 0.2796 | 0.419 | 0.687 | 0.968 | 1.274 | 1.550 | 2.103 | 2.653 | 3.207 | 3.760 | 4.312 | 4.864 | 4.864 |
| 46 | 0.479 | 0.2871 | 0.430 | 0.706 | 0.998 | 1.314 | 1.599 | 2.170 | 2.740 | 3.310 | 3.881 | 4.451 | 5.021 | 5.021 |
| 47 | 0.490 | 0.2946 | 0.441 | 0.725 | 1.029 | 1.354 | 1.649 | 2.237 | 2.826 | 3.415 | 4.003 | 4.592 | 5.181 | 5.181 |
| 48 | 0.500 | 0.3021 | 0.452 | 0.744 | 1.060 | 1.394 | 1.697 | 2.304 | 2.912 | 3.519 | 4.126 | 4.733 | 5.340 | 5.340 |
| 49 | 0.510 | 0.3096 | 0.463 | 0.763 | 1.090 | 1.434 | 1.747 | 2.372 | 2.999 | 3.624 | 4.250 | 4.876 | 5.502 | 5.502 |
| 50 | 0.521 | 0.3171 | 0.474 | 0.782 | 1.120 | 1.475 | 1.798 | 2.442 | 3.087 | 3.732 | 4.377 | 5.021 | 5.666 | 5.666 |
| 51 | 0.531 | 0.3246 | 0.485 | 0.801 | 1.150 | 1.516 | 1.848 | 2.511 | 3.175 | 3.839 | 4.503 | 5.166 | 5.830 | 5.830 |
| 52 | 0.542 | 0.3321 | 0.496 | 0.820 | 1.180 | 1.557 | 1.898 | 2.581 | 3.264 | 3.947 | 4.630 | 5.313 | 5.996 | 5.996 |
| 53 | 0.552 | 0.3396 | 0.507 | 0.839 | 1.210 | 1.598 | 1.949 | 2.652 | 3.354 | 4.067 | 4.759 | 5.461 | 6.164 | 6.164 |
| 54 | 0.563 | 0.3471 | 0.518 | 0.858 | 1.240 | 1.640 | 2.001 | 2.723 | 3.445 | 4.167 | 4.889 | 5.611 | 6.333 | 6.333 |
| 55 | 0.573 | 0.3546 | 0.529 | 0.877 | 1.270 | 1.682 | 2.053 | 2.795 | 3.536 | 4.275 | 5.020 | 5.762 | 6.504 | 6.504 |
| 56 | 0.583 | 0.3621 | 0.540 | 0.896 | 1.300 | 1.725 | 2.106 | 2.867 | 3.629 | 4.391 | 5.153 | 5.914 | 6.676 | 6.676 |
| 57 | 0.594 | 0.3696 | 0.551 | 0.915 | 1.330 | 1.767 | 2.158 | 2.940 | 3.722 | 4.504 | 5.286 | 6.067 | 6.849 | 6.849 |
| 58 | 0.604 | 0.3771 | 0.562 | 0.934 | 1.360 | 1.809 | 2.210 | 3.012 | 3.815 | 4.617 | 5.419 | 6.221 | 7.023 | 7.023 |
| 59 | 0.615 | 0.3846 | 0.573 | 0.953 | 1.390 | 1.851 | 2.263 | 3.085 | 3.908 | 4.731 | 5.554 | 6.376 | 7.199 | 7.199 |
| 60 | 0.625 | 0.3921 | 0.584 | 0.972 | 1.420 | 1.892 | 2.316 | 3.160 | 4.003 | 4.848 | 5.690 | 6.533 | 7.376 | 7.376 |
| 61 | 0.635 | 0.4000 | 0.595 | 0.991 | 1.450 | 1.934 | 2.370 | 3.234 | 4.098 | 4.963 | 5.827 | 6.691 | 7.555 | 7.555 |
| 62 | 0.646 | 0.4079 | 0.606 | 1.010 | 1.480 | 1.976 | 2.423 | 3.308 | 4.193 | 5.079 | 5.964 | 6.849 | 7.734 | 7.734 |
| 63 | 0.656 | 0.4158 | 0.617 | 1.029 | 1.510 | 2.018 | 2.477 | 3.384 | 4.290 | 5.196 | 6.103 | 7.009 | 7.915 | 7.915 |
| 64 | 0.667 | 0.4237 | 0.628 | 1.048 | 1.540 | 2.060 | 2.531 | 3.460 | 4.387 | 5.313 | 6.230 | 7.176 | 8.086 | 8.086 |
| 65 | 0.678 | 0.4316 | 0.639 | 1.067 | 1.570 | 2.102 | 2.585 | 3.535 | 4.484 | 5.433 | 6.353 | 7.332 | 8.261 | 8.261 |
| 66 | 0.688 | 0.4395 | 0.650 | 1.086 | 1.600 | 2.144 | 2.639 | 3.610 | 4.581 | 5.554 | 6.474 | 7.493 | 8.432 | 8.432 |
| 67 | 0.699 | 0.4474 | 0.661 | 1.105 | 1.630 | 2.186 | 2.693 | 3.685 | 4.678 | 5.674 | 6.595 | 7.654 | 8.603 | 8.603 |
| 68 | 0.709 | 0.4553 | 0.672 | 1.124 | 1.660 | 2.228 | 2.747 | 3.760 | 4.775 | 5.795 | 6.715 | 7.815 | 8.774 | 8.774 |
| 69 | 0.720 | 0.4632 | 0.683 | 1.143 | 1.690 | 2.270 | 2.801 | 3.835 | 4.872 | 5.916 | 6.836 | 7.976 | 8.945 | 8.945 |
| 70 | 0.730 | 0.4711 | 0.694 | 1.162 | 1.720 | 2.312 | 2.855 | 3.910 | 4.969 | 6.037 | 6.957 | 8.137 | 9.116 | 9.116 |
| 71 | 0.740 | 0.4790 | 0.705 | 1.181 | 1.750 | 2.354 | 2.909 | 3.985 | 5.066 | 6.158 | 7.078 | 8.298 | 9.287 | 9.287 |
| 72 | 0.750 | 0.4869 | 0.716 | 1.200 | 1.780 | 2.396 | 2.963 | 4.060 | 5.163 | 6.279 | 7.199 | 8.459 | 9.458 | 9.458 |
| 73 | 0.760 | 0.4948 | 0.727 | 1.219 | 1.810 | 2.438 | 3.017 | 4.135 | 5.260 | 6.399 | 7.320 | 8.620 | 9.629 | 9.629 |
| 74 | 0.770 | 0.5027 | 0.738 | 1.238 | 1.840 | 2.480 | 3.071 | 4.210 | 5.357 | 6.520 | 7.441 | 8.781 | 9.799 | 9.799 |
| 75 | 0.780 | 0.5106 | 0.749 | 1.257 | 1.870 | 2.522 | 3.125 | 4.285 | 5.454 | 6.641 | 7.562 | 8.942 | 9.969 | 9.969 |
| 76 | 0.790 | 0.5185 | 0.760 | 1.276 | 1.900 | 2.564 | 3.179 | 4.360 | 5.551 | 6.762 | 7.683 | 9.103 | 10.139 | 10.139 |
| 77 | 0.800 | 0.5264 | 0.771 | 1.295 | 1.930 | 2.606 | 3.233 | 4.435 | 5.648 | 6.883 | 7.804 | 9.264 | 10.309 | 10.309 |
| 78 | 0.810 | 0.5343 | 0.782 | 1.314 | 1.960 | 2.648 | 3.287 | 4.510 | 5.745 | 7.004 | 7.925 | | | |

TABLES.

161

complete end contractions. [Formula $Q = 3.33 (l - .2H) H^{3/2}$].

| Length of weir—Continued. | | | | | | | | | | | Addition for increase of length. | |
|---------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|----------------------------------|---------|
| 5 ft. | 6 ft. | 7 ft. | 8 ft. | 9 ft. | 10 ft. | 12 ft. | 14 ft. | 16 ft. | 18 ft. | 20 ft. | 1 in. | 1 ft. |
| 0.0500 | 0.0600 | 0.0700 | 0.0800 | 0.0900 | 0.100 | 0.120 | 0.140 | 0.160 | 0.180 | 0.200 | 0.00029 | 0.00354 |
| .0918 | .110 | .129 | .147 | .166 | .184 | .221 | .258 | .294 | .331 | .368 | .00083 | .01001 |
| .141 | .170 | .198 | .226 | .255 | .283 | .340 | .396 | .453 | .510 | .566 | .00236 | .0283 |
| .198 | .237 | .277 | .316 | .356 | .395 | .475 | .554 | .633 | .712 | .791 | .00330 | .0396 |
| .260 | .312 | .364 | .416 | .468 | .520 | .624 | .728 | .832 | .936 | 1.040 | .00433 | .0520 |
| .327 | .392 | .458 | .524 | .589 | .655 | .786 | .917 | 1.048 | 1.179 | 1.310 | .00546 | .0656 |
| .399 | .479 | .559 | .640 | .720 | .800 | .960 | 1.120 | 1.230 | 1.441 | 1.601 | .00667 | .0801 |
| .476 | .572 | .667 | .763 | .859 | .954 | 1.145 | 1.337 | 1.528 | 1.719 | 1.910 | .00796 | .0959 |
| .557 | .669 | .781 | .893 | 1.005 | 1.117 | 1.341 | 1.565 | 1.789 | 2.013 | 2.237 | .00933 | .112 |
| .643 | .772 | .901 | 1.030 | 1.160 | 1.289 | 1.547 | 1.805 | 2.064 | 2.322 | 2.580 | .0108 | .129 |
| .732 | .879 | 1.026 | 1.174 | 1.321 | 1.468 | 1.762 | 2.057 | 2.351 | 2.645 | 2.940 | .0123 | .147 |
| .825 | .991 | 1.157 | 1.323 | 1.489 | 1.655 | 1.967 | 2.319 | 2.650 | 2.982 | 3.314 | .0138 | .166 |
| .922 | 1.107 | 1.293 | 1.478 | 1.664 | 1.849 | 2.220 | 2.591 | 2.962 | 3.333 | 3.704 | .0155 | .185 |
| 1.022 | 1.228 | 1.433 | 1.639 | 1.845 | 2.050 | 2.462 | 2.873 | 3.284 | 3.696 | 4.107 | .0171 | .206 |
| 1.125 | 1.352 | 1.579 | 1.805 | 2.032 | 2.258 | 2.711 | 3.165 | 3.618 | 4.071 | 4.524 | .0189 | .227 |
| 1.232 | 1.480 | 1.728 | 1.976 | 2.225 | 2.473 | 2.969 | 3.463 | 3.962 | 4.458 | 4.954 | .0207 | .248 |
| 1.342 | 1.612 | 1.882 | 2.153 | 2.423 | 2.693 | 3.234 | 3.775 | 4.316 | 4.856 | 5.397 | .0225 | .270 |
| 1.455 | 1.748 | 2.041 | 2.334 | 2.627 | 2.921 | 3.537 | 4.093 | 4.630 | 5.266 | 5.853 | .0244 | .293 |
| 1.570 | 1.887 | 2.203 | 2.520 | 2.837 | 3.153 | 3.787 | 4.420 | 5.053 | 5.686 | 6.320 | .0264 | .317 |
| 1.689 | 2.029 | 2.370 | 2.711 | 3.051 | 3.392 | 4.074 | 4.755 | 5.436 | 6.118 | 6.799 | .0284 | .341 |
| 1.810 | 2.175 | 2.540 | 2.906 | 3.271 | 3.636 | 4.367 | 5.098 | 5.828 | 6.559 | 7.290 | .0304 | .365 |
| 1.934 | 2.324 | 2.715 | 3.105 | 3.496 | 3.886 | 4.667 | 5.448 | 6.229 | 7.010 | 7.792 | .0325 | .391 |
| 2.060 | 2.477 | 2.893 | 3.309 | 3.725 | 4.142 | 4.974 | 5.807 | 6.630 | 7.472 | 8.304 | .0347 | .416 |
| 2.190 | 2.632 | 3.075 | 3.517 | 3.960 | 4.402 | 5.287 | 6.172 | 7.058 | 7.943 | 8.828 | .0369 | .443 |
| 2.321 | 2.791 | 3.260 | 3.729 | 4.199 | 4.668 | 5.607 | 6.546 | 7.484 | 8.423 | 9.362 | .0391 | .469 |
| 2.455 | 2.952 | 3.449 | 3.948 | 4.442 | 4.939 | 5.932 | 6.926 | 7.919 | 8.913 | 9.906 | .0414 | .497 |
| 2.592 | 3.117 | 3.641 | 4.168 | 4.690 | 5.215 | 6.264 | 7.313 | 8.362 | 9.411 | 10.460 | .0437 | .525 |
| 2.731 | 3.284 | 3.837 | 4.390 | 4.943 | 5.495 | 6.601 | 7.707 | 8.813 | 9.918 | 11.024 | .0461 | .553 |
| 2.872 | 3.454 | 4.036 | 4.617 | 5.199 | 5.781 | 6.944 | 8.108 | 9.271 | 10.435 | 11.598 | .0485 | .582 |
| 3.016 | 3.627 | 4.238 | 4.849 | 5.460 | 6.071 | 7.293 | 8.515 | 9.737 | 10.960 | 12.182 | .0509 | .611 |
| 3.162 | 3.802 | 4.443 | 5.084 | 5.725 | 6.366 | 7.648 | 8.929 | 10.211 | 11.493 | 12.774 | .0534 | .641 |
| 3.310 | 3.981 | 4.652 | 5.323 | 5.994 | 6.665 | 8.007 | 9.350 | 10.692 | 12.034 | 13.376 | .0559 | .671 |
| 3.460 | 4.161 | 4.863 | 5.565 | 6.267 | 6.969 | 8.373 | 9.776 | 11.180 | 12.584 | 13.988 | .0585 | .702 |
| 3.612 | 4.345 | 5.078 | 5.811 | 6.544 | 7.277 | 8.743 | 10.209 | 11.676 | 13.142 | 14.608 | .0611 | .733 |
| 3.766 | 4.531 | 5.296 | 6.060 | 6.825 | 7.590 | 9.119 | 10.648 | 12.178 | 13.707 | 15.237 | .0637 | .765 |
| 3.922 | 4.719 | 5.516 | 6.313 | 7.110 | 7.906 | 9.500 | 11.093 | 12.687 | 14.281 | 15.874 | .0664 | .797 |
| 4.081 | 4.910 | 5.739 | 6.569 | 7.398 | 8.227 | 9.886 | 11.545 | 13.203 | 14.862 | 16.520 | .0691 | .829 |
| 4.242 | 5.104 | 5.967 | 6.829 | 7.691 | 8.553 | 10.278 | 12.002 | 13.727 | 15.451 | 17.176 | .0719 | .862 |
| 4.404 | 5.299 | 6.195 | 7.090 | 7.986 | 8.882 | 10.673 | 12.464 | 14.256 | 16.047 | 17.838 | .0747 | .896 |
| 4.568 | 5.497 | 6.427 | 7.358 | 8.285 | 9.215 | 11.074 | 12.933 | 14.791 | 16.650 | 18.509 | .0775 | .929 |
| 4.733 | 5.697 | 6.661 | 7.624 | 8.588 | 9.551 | 11.479 | 13.406 | 15.333 | 17.277 | 19.187 | .0803 | .964 |
| 4.901 | 5.899 | 6.897 | 7.895 | 8.894 | 9.892 | 11.888 | 13.885 | 15.881 | 17.879 | 19.874 | .0832 | .998 |
| 5.071 | 6.105 | 7.138 | 8.171 | 9.204 | 10.238 | 12.304 | 14.371 | 16.438 | 18.504 | 20.571 | .0861 | 1.033 |
| 5.243 | 6.312 | 7.380 | 8.449 | 9.518 | 10.586 | 12.724 | 14.861 | 16.999 | 19.066 | 21.273 | .0891 | 1.069 |
| 5.416 | 6.521 | 7.626 | 8.730 | 9.835 | 10.939 | 13.149 | 15.358 | 17.567 | 19.776 | 21.985 | .0921 | 1.105 |
| 5.592 | 6.733 | 7.873 | 9.014 | 10.155 | 11.295 | 13.577 | 15.858 | 18.140 | 20.421 | 22.702 | .0951 | 1.141 |
| 5.769 | 6.947 | 8.124 | 9.301 | 10.478 | 11.656 | 14.016 | 16.365 | 18.720 | 21.074 | 23.429 | .0981 | 1.177 |
| 5.948 | 7.162 | 8.376 | 9.591 | 10.805 | 12.020 | 14.448 | 16.877 | 19.306 | 21.735 | 24.164 | .101 | 1.214 |
| 6.128 | 7.380 | 8.631 | 9.883 | 11.135 | 12.386 | 14.890 | 17.393 | 19.997 | 22.400 | 24.903 | .104 | 1.252 |
| 6.311 | 7.600 | 8.889 | 10.179 | 11.468 | 12.758 | 15.336 | 17.915 | 20.494 | 23.073 | 25.652 | .107 | 1.289 |
| 6.491 | 7.822 | 9.149 | 10.477 | 11.804 | 13.125 | 15.787 | 18.442 | 21.019 | 23.752 | 26.407 | .111 | 1.328 |
| 6.670 | 8.045 | 9.411 | 10.771 | 12.143 | 13.506 | 16.241 | 18.973 | 21.705 | 24.437 | 27.169 | .114 | 1.366 |
| 6.866 | 8.271 | 9.676 | 11.081 | 12.485 | 13.890 | 16.700 | 19.509 | 22.319 | 25.129 | 27.938 | .117 | 1.405 |
| 7.055 | 8.500 | 9.944 | 11.388 | 12.832 | 14.276 | 17.164 | 20.052 | 22.941 | 25.829 | 28.717 | .120 | 1.444 |
| 7.245 | 8.729 | 10.213 | 11.698 | 13.180 | 14.663 | 17.631 | 20.595 | 23.565 | 26.532 | 29.499 | .124 | 1.484 |
| 7.438 | 8.962 | 10.485 | 12.003 | 13.532 | 15.056 | 18.108 | 21.150 | 24.197 | 27.244 | 30.291 | .127 | 1.524 |
| 7.631 | 9.195 | 10.759 | 12.323 | 13.886 | 15.450 | 18.578 | 21.705 | 24.833 | 27.941 | 31.083 | .130 | 1.564 |
| 7.826 | 9.430 | 11.034 | 12.658 | 14.243 | 15.848 | 19.050 | 22.265 | 25.478 | 28.683 | 31.892 | .134 | 1.604 |
| 8.022 | 9.667 | 11.312 | 12.984 | 14.603 | 16.249 | 19.539 | 22.830 | 26.121 | 29.429 | 32.703 | .137 | 1.645 |
| 8.220 | 9.907 | 11.593 | 13.280 | 14.967 | 16.653 | 20.027 | 23.400 | 26.774 | 30.147 | 33.520 | .141 | 1.687 |
| 8.419 | 10.148 | 11.876 | 13.604 | 15.332 | 17.061 | 20.517 | 23.974 | 27.431 | 30.887 | 34.344 | .144 | 1.728 |
| 8.619 | 10.390 | 12.160 | 13.930 | 15.700 | 17.471 | 21.011 | 24.552 | 28.093 | 31.633 | 35.174 | .148 | 1.770 |
| 8.821 | 10.634 | 12.447 | 14.259 | 16.072 | 17.884 | 21.510 | 25.135 | 28.760 | 32.385 | 36.010 | .151 | 1.813 |
| 9.023 | 10.881 | 12.740 | 14.594 | 16.423 | 18.298 | 22.016 | 25.716 | 29.430 | 33.133 | 36.867 | .155 | 1.856 |
| 9.245 | 11.130 | 13.031 | 14.924 | 16.785 | 18.712 | 22.526 | 26.300 | 30.100 | 33.885 | 37.729 | .158 | 1.899 |
| 9.465 | 11.380 | 13.315 | 15.260 | 17.148 | 19.126 | 23.036 | 26.884 | 30.770 | 34.637 | 38.591 | .161 | 1.942 |
| 9.685 | 11.630 | 13.611 | 15.600 | 17.519 | 19.540 | 23.546 | 27.468 | 31.440 | 35.389 | 39.453 | .165 | 1.985 |
| 9.905 | 11.881 | 13.915 | 15.950 | 17.889 | 19.954 | 24.056 | 28.052 | 32.100 | 36.141 | 40.315 | .168 | 2.028 |
| 10.125 | 12.132 | 14.219 | 16.300 | 18.259 | 20.368 | 24.566 | 28.636 | 32.760 | 36.893 | 41.177 | .171 | 2.071 |
| 10.345 | 12.383 | 14.519 | 16.650 | 18.629 | 20.782 | 25.076 | 29.220 | 33.420 | 37.645 | 42.039 | .175 | 2.114 |
| 10.565 | 12.634 | 14.819 | 16.999 | 19.000 | 21.196 | 25.586 | 29.784 | 34.080 | 38.397 | 42.901 | .178 | 2.157 |
| 10.785 | 12.885 | 15.119 | 17.349 | 19.370 | 21.610 | 26.096 | 30.348 | 34.740 | 39.149 | 43.763 | .181 | 2.200 |
| 11.005 | 13.136 | 15.419 | 17.699 | 19.740 | 22.024 | 26.606 | 30.912 | 35.400 | 39.901 | 44.625 | .185 | 2.243 |
| 11.225 | 13.387 | 15.719 | 18.049 | 20.110 | 22.438 | 27.116 | 31.476 | 36.060 | 40.653 | 45.487 | .188 | 2.286 |
| 11.445 | 13.638 | 16.019 | 18.399 | 20.480 | 22.852 | 27.626 | 32.040 | 36.720 | 41.405 | 46.349 | .191 | 2.329 |
| 11.665 | 13.889 | 16.319 | 18.749 | 20.850 | 23.266 | 28.136 | 32.604 | 37.380 | 42.157 | 47.211 | .195 | 2.372 |
| 11.885 | 14.140 | 16.619 | 19.099 | 21.220 | 23.680 | 28.646 | 33.168 | 38.040 | 42.909 | 48.073 | .198 | 2.415 |
| 12.105 | 14.391 | 16.919 | 19.449 | 21.590 | 24.094 | 29.156 | 33.732 | 38.700 | 43.661 | 48.935 | .201 | 2.458 |
| 12.325 | 14.642 | 17.219 | 19.799 | 21.960 | 24.508 | 29.666 | 34.296 | 39.360 | 44.413 | 49.797 | .205 | 2.501 |
| 12.545 | 14.893 | 17.519 | 20.149 | 22.330 | 24.922 | 30.176 | 34.860 | 40.020 | 45.165 | 50.659 | .208 | 2.544 |
| 12.765 | 15.144 | 17.819 | 20.499 | 22.700 | 25.336 | 30.686 | 35.424 | 40.680 | 45.917 | 51.521 | .211 | 2.587 |
| 12.985 | 15.395 | 18.119 | 20.849 | 23.070 | 25.750 | 31.196 | 35.988 | 41.340 | 46.669 | 52.383 | .215 | 2.630 |
| 13.205 | 15.646 | 18.419 | 21.199 | 23.440 | 26.164 | 31.706 | 36.552 | 42.000 | 47.421 | 53.245 | .218 | 2.673 |
| 13.425 | 15.897 | 18.719 | 21.549 | 23.810 | 26.578 | 32.216 | 37.116 | 42.660 | 48.173 | 54.107 | .221 | 2.716 |
| 13.645 | 16.148 | 19.019 | 21.899 | 24.180 | 26.992 | 32.726 | 37.680 | 43.320 | 48.925 | 54.969 | .225 | 2.759 |
| 13.865 | 16.399 | 19.319 | 22.249 | 24.550 | 27.406 | 33.236 | 38.240 | 43.980 | 49.677 | 55.831 | .228 | 2.802 |
| 14.085 | 16.650 | 19.619 | 22.599 | 24.920 | 27.820 | 33.746 | 38.804 | 44.640 | 50.429 | 56.693 | .231 | 2.845 |
| 14 | | | | | | | | | | | | |

Table II.—Discharge in second-feet per foot of crest over rectangular sharp-crested weirs without end contractions.

Formula: $Q=3.33 l H^{\frac{3}{2}}$.

| Head <i>H</i> , feet. | .00 | .01 | .02 | .03 | .04 | .05 | .06 | .07 | .08 | .09 |
|--------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| 0.0 | 0.0000 | 0.0083 | 0.0094 | 0.0173 | 0.0266 | 0.0372 | 0.0489 | 0.0617 | 0.0758 | 0.0899 |
| .1 | .1063 | .1215 | .1384 | .1561 | .1744 | .1935 | .2131 | .2334 | .2543 | .2758 |
| .2 | .2978 | .3205 | .3436 | .3673 | .3915 | .4162 | .4415 | .4672 | .4934 | .5200 |
| .3 | .5472 | .5748 | .6028 | .6313 | .6602 | .6895 | .7193 | .7495 | .7800 | .8110 |
| .4 | .8424 | .8742 | .9084 | .9390 | .9719 | 1.0052 | 1.0389 | 1.0730 | 1.1074 | 1.1422 |
| .5 | 1.1773 | 1.2128 | 1.2487 | 1.2849 | 1.3214 | 1.3583 | 1.3955 | 1.4330 | 1.4709 | 1.5091 |
| .6 | 1.5476 | 1.5865 | 1.6257 | 1.6652 | 1.7050 | 1.7451 | 1.7855 | 1.8262 | 1.8673 | 1.9086 |
| .7 | 1.9503 | 1.9922 | 2.0344 | 2.0770 | 2.1198 | 2.1629 | 2.2063 | 2.2500 | 2.2940 | 2.3382 |
| .8 | 2.3828 | 2.4276 | 2.4727 | 2.5180 | 2.5637 | 2.6096 | 2.6558 | 2.7022 | 2.7490 | 2.7959 |
| .9 | 2.8432 | 2.8907 | 2.9385 | 2.9865 | 3.0348 | 3.0834 | 3.1322 | 3.1813 | 3.2306 | 3.2802 |
| 1.0 | 3.3300 | 3.3801 | 3.4304 | 3.4810 | 3.5318 | 3.5828 | 3.6342 | 3.6857 | 3.7375 | 3.7895 |
| 1.1 | 3.8418 | 3.8948 | 3.9470 | 4.0000 | 4.0532 | 4.1067 | 4.1604 | 4.2143 | 4.2384 | 4.3228 |
| 1.2 | 4.3774 | 4.4322 | 4.4873 | 4.5426 | 4.5981 | 4.6538 | 4.7096 | 4.7660 | 4.8224 | 4.8790 |
| 1.3 | 4.9358 | 4.9929 | 5.0502 | 5.1077 | 5.1654 | 5.2233 | 5.2814 | 5.3398 | 5.3984 | 5.4572 |
| 1.4 | 5.5162 | 5.5754 | 5.6348 | 5.6944 | 5.7542 | 5.8143 | 5.8745 | 5.9350 | 5.9957 | 6.0565 |
| 1.5 | 6.1176 | 6.1789 | 6.2404 | 6.3020 | 6.3638 | 6.4260 | 6.4883 | 6.5508 | 6.6135 | 6.6764 |
| 1.6 | 6.7394 | 6.8027 | 6.8662 | 6.9299 | 6.9937 | 7.0578 | 7.1221 | 7.1865 | 7.2512 | 7.3160 |
| 1.7 | 7.3810 | 7.4463 | 7.5117 | 7.5773 | 7.6431 | 7.7091 | 7.7752 | 7.8416 | 7.9081 | 7.9749 |
| 1.8 | 8.0418 | 8.1089 | 8.1762 | 8.2437 | 8.3118 | 8.3792 | 8.4472 | 8.5154 | 8.5838 | 8.6524 |
| 1.9 | 8.7212 | 8.7901 | 8.8592 | 8.9285 | 8.9980 | 9.0677 | 9.1375 | 9.2075 | 8.2777 | 9.3481 |
| 2.0 | 9.4187 | 9.4894 | 9.5603 | 9.6314 | 9.7028 | 9.7741 | 9.8457 | 9.9174 | 9.9894 | 10.0620 |
| 2.1 | 10.1340 | 10.2060 | 10.2790 | 10.3520 | 10.4250 | 10.4980 | 10.5710 | 10.6450 | 10.7180 | 10.7920 |
| 2.2 | 10.8660 | 10.9400 | 11.0150 | 11.0890 | 11.1640 | 11.2390 | 11.3140 | 11.3890 | 11.4640 | 11.5400 |
| 2.3 | 11.6150 | 11.6910 | 11.7670 | 11.8430 | 11.9200 | 11.9960 | 12.0730 | 12.1500 | 12.2270 | 12.3040 |
| 2.4 | 12.3810 | 12.4590 | 12.5360 | 12.6140 | 12.6920 | 12.7700 | 12.8480 | 12.9270 | 13.0050 | 13.0840 |
| 2.5 | 13.1630 | 13.2430 | 13.3210 | 13.4010 | 13.4800 | 13.5600 | 13.6400 | 13.7200 | 13.8000 | 13.8800 |
| 2.6 | 13.9610 | 14.0410 | 14.1220 | 14.2030 | 14.2840 | 14.3650 | 14.4470 | 14.5280 | 14.6100 | 14.6920 |
| 2.7 | 14.7740 | 14.8560 | 14.9380 | 15.0210 | 15.1030 | 15.1860 | 15.2690 | 15.3520 | 15.4350 | 15.5190 |
| 2.8 | 15.6020 | 15.6860 | 15.7690 | 15.8530 | 15.9380 | 16.0220 | 16.1060 | 16.1910 | 16.2750 | 16.3600 |
| 2.9 | 16.4450 | 16.5300 | 16.6160 | 16.7010 | 16.7870 | 16.8720 | 16.9580 | 17.0440 | 17.1300 | 17.2170 |
| 3.0 | 17.3038 | 17.3899 | 17.4658 | 17.5634 | 17.6503 | 17.7376 | 17.8248 | 17.9124 | 18.0000 | 18.0876 |
| 3.1 | 18.1754 | 18.2634 | 18.3516 | 18.4399 | 18.5285 | 18.6170 | 18.7056 | 18.7945 | 18.8838 | 18.9727 |
| 3.2 | 19.0619 | 19.1515 | 19.2410 | 19.3307 | 19.4206 | 19.5105 | 19.6007 | 19.6910 | 19.7812 | 19.8718 |
| 3.3 | 19.9624 | 20.0528 | 20.1442 | 20.2354 | 20.3267 | 20.4179 | 20.5095 | 20.6011 | 20.6930 | 20.7849 |
| 3.4 | 20.8777 | 20.9690 | 21.0613 | 21.1538 | 21.2464 | 21.3390 | 21.4319 | 21.5248 | 21.6180 | 21.7113 |
| 3.5 | 21.8045 | 21.8980 | 21.9917 | 22.0856 | 22.1795 | 22.2734 | 22.3677 | 22.4618 | 22.5564 | 22.6510 |
| 3.6 | 22.7456 | 22.8405 | 22.9354 | 23.0306 | 23.1259 | 23.2211 | 23.3167 | 23.4122 | 23.5081 | 23.6040 |
| 3.7 | 23.6999 | 23.7962 | 23.8924 | 23.9887 | 24.0852 | 24.1818 | 24.2787 | 24.3756 | 24.4728 | 24.5697 |
| 3.8 | 24.6673 | 24.7645 | 24.8621 | 24.9600 | 25.0576 | 25.1555 | 25.2537 | 25.3520 | 25.4502 | 25.5488 |
| 3.9 | 25.6473 | 25.7459 | 25.8448 | 25.9437 | 26.0429 | 26.1422 | 26.2414 | 26.3410 | 26.4405 | 26.5401 |
| 4.0 | 26.6400 | 26.7399 | 26.8401 | 26.9404 | 27.0406 | 27.1412 | 27.2417 | 27.3423 | 27.4432 | 27.5441 |
| 4.1 | 27.6453 | 27.7466 | 27.8478 | 27.9494 | 28.0509 | 28.1525 | 28.2544 | 28.3563 | 28.4582 | 28.5604 |
| 4.2 | 28.6626 | 28.7652 | 28.8678 | 28.9703 | 29.0732 | 29.1761 | 29.2790 | 29.3823 | 29.4855 | 29.5890 |
| 4.3 | 29.6926 | 29.7962 | 29.9001 | 30.0040 | 30.1079 | 30.2118 | 30.3163 | 30.4205 | 30.5251 | 30.6297 |
| 4.4 | 30.7342 | 30.8391 | 30.9440 | 31.0493 | 31.1545 | 31.2597 | 31.3649 | 31.4705 | 31.5764 | 31.6820 |
| 4.5 | 31.7878 | 31.8941 | 32.0003 | 32.1065 | 32.2128 | 32.3193 | 32.4259 | 32.5324 | 32.6398 | 32.7462 |
| 4.6 | 32.8534 | 32.9607 | 33.0679 | 33.1755 | 33.2830 | 33.3906 | 33.4985 | 33.6064 | 33.7143 | 33.8225 |
| 4.7 | 33.9307 | 34.0373 | 34.1475 | 34.2560 | 34.3646 | 34.4735 | 34.5824 | 34.6913 | 34.8005 | 34.9097 |
| 4.8 | 35.0193 | 35.1288 | 35.2354 | 35.3480 | 35.4578 | 35.5677 | 35.6780 | 35.7882 | 35.8984 | 36.0086 |
| 4.9 | 36.1182 | 36.2297 | 36.3406 | 36.4515 | 36.5624 | 36.6736 | 36.7845 | 36.8961 | 37.0078 | 37.1188 |

Table II.—Continued.

| Head <i>H</i> , feet. | .00 | .01 | .02 | .03 | .04 | .05 | .06 | .07 | .08 | .09 |
|--------------------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| 5.0 | 37.2804 | 37.3423 | 37.4542 | 37.5661 | 37.6783 | 37.7905 | 37.9027 | 38.0153 | 38.1275 | 38.2404 |
| 5.1 | 38.3529 | 38.4658 | 38.5787 | 38.6919 | 38.8052 | 38.9184 | 39.0319 | 39.1455 | 39.2591 | 39.3726 |
| 5.2 | 39.4865 | 39.6004 | 39.7146 | 39.8288 | 39.9430 | 40.0576 | 40.1718 | 40.2867 | 40.4012 | 40.5161 |
| 5.3 | 40.6310 | 40.7462 | 40.8281 | 40.9766 | 41.0919 | 41.2074 | 41.3230 | 41.4386 | 41.5544 | 41.6703 |
| 5.4 | 41.7866 | 41.9024 | 42.0186 | 42.1352 | 42.2517 | 42.3683 | 42.4848 | 42.6017 | 42.7186 | 42.8355 |
| 5.5 | 42.9523 | 43.0700 | 43.1871 | 43.3043 | 43.4219 | 42.5394 | 43.6573 | 43.7752 | 43.8931 | 44.0109 |
| 5.6 | 44.1292 | 44.2474 | 44.3659 | 44.4845 | 44.6030 | 44.7216 | 44.8404 | 44.9593 | 45.0782 | 45.1974 |
| 5.7 | 45.3166 | 45.4359 | 45.5554 | 45.6746 | 45.7945 | 45.9140 | 46.0339 | 46.1538 | 46.2740 | 46.3939 |
| 5.8 | 46.5141 | 46.6347 | 46.7552 | 46.8757 | 46.9963 | 47.1172 | 47.2380 | 47.3589 | 47.4798 | 47.6010 |
| 5.9 | 47.7226 | 47.8438 | 47.9653 | 48.0869 | 48.2084 | 48.3303 | 48.4522 | 48.5744 | 48.6963 | 48.8185 |
| 6.0 | 48.9407 | 49.0632 | 49.1858 | 49.3083 | 48.4312 | 49.5537 | 49.6766 | 49.7999 | 49.9230 | 50.0462 |
| 6.1 | 50.1694 | 50.2930 | 50.4162 | 50.5401 | 50.6637 | 50.7875 | 50.9114 | 51.0356 | 51.1595 | 51.2837 |
| 6.2 | 51.4082 | 51.5324 | 51.6570 | 51.7818 | 51.9034 | 52.0318 | 52.1581 | 52.2813 | 52.4062 | 52.5314 |
| 6.3 | 52.6570 | 52.7822 | 52.9077 | 53.0336 | 53.1591 | 53.2850 | 53.4109 | 53.5371 | 53.6630 | 53.7892 |
| 6.4 | 53.9157 | 54.0419 | 54.1684 | 54.2950 | 54.4219 | 54.5487 | 54.6756 | 54.8025 | 54.9297 | 55.0569 |
| 6.5 | 55.1832 | 55.3116 | 55.4392 | 55.5667 | 55.6943 | 55.8221 | 55.9500 | 56.0779 | 56.2061 | 56.3343 |
| 6.6 | 56.4625 | 56.5910 | 56.7192 | 56.8478 | 56.9766 | 57.1055 | 57.2340 | 57.3633 | 57.4921 | 57.6213 |
| 6.7 | 57.7505 | 57.8801 | 58.0093 | 58.1388 | 58.2687 | 58.3982 | 58.5281 | 58.6580 | 58.7882 | 58.9180 |
| 6.8 | 59.0482 | 59.1788 | 59.3090 | 59.4428 | 59.5700 | 59.7009 | 59.8314 | 59.9623 | 60.0935 | 60.2244 |
| 6.9 | 60.3556 | 60.4868 | 60.6183 | 60.7499 | 60.8814 | 61.0129 | 61.1445 | 61.2768 | 61.4082 | 61.5404 |
| 7.0 | 61.6736 | 61.8048 | 61.9370 | 62.0692 | 62.2017 | 62.3343 | 62.4671 | 62.6000 | 62.7329 | 62.8657 |
| 7.1 | 62.9986 | 63.1318 | 63.2650 | 63.3992 | 63.5317 | 63.6653 | 63.7991 | 63.9327 | 64.0665 | 64.2004 |
| 7.2 | 64.3334 | 64.4685 | 64.6027 | 64.7369 | 64.8711 | 65.0056 | 65.1288 | 65.2750 | 65.4095 | 65.5444 |
| 7.3 | 65.6793 | 65.8145 | 65.9493 | 66.0845 | 66.2197 | 66.3552 | 66.4908 | 66.6263 | 66.7618 | 66.8977 |
| 7.4 | 67.0336 | 67.1694 | 67.3053 | 67.4415 | 67.5777 | 67.7139 | 67.8504 | 67.9869 | 68.1235 | 68.2600 |
| 7.5 | 68.3969 | 68.5337 | 68.6706 | 68.8078 | 68.9447 | 69.0818 | 69.2194 | 69.3566 | 69.4941 | 69.6316 |
| 7.6 | 69.7695 | 69.9070 | 70.0449 | 70.1827 | 70.3209 | 70.4591 | 70.5973 | 70.7355 | 70.8737 | 71.0123 |
| 7.7 | 71.1508 | 71.2896 | 71.4282 | 71.5670 | 71.7059 | 71.8451 | 71.9843 | 72.1235 | 72.2627 | 72.4013 |
| 7.8 | 72.5414 | 72.6809 | 72.8208 | 72.9603 | 73.1002 | 73.2400 | 73.3802 | 73.5201 | 73.6603 | 73.8005 |
| 7.9 | 73.9410 | 74.0815 | 74.2220 | 74.3626 | 74.5031 | 74.6439 | 74.7848 | 74.9260 | 75.0669 | 75.2081 |
| 8.0 | 75.3492 | 75.4908 | 75.6320 | 75.7735 | 75.9150 | 76.0569 | 76.1987 | 76.3406 | 76.4824 | 76.6243 |
| 8.1 | 76.7665 | 76.9087 | 77.0509 | 77.1934 | 77.3360 | 77.4784 | 77.6210 | 77.7638 | 77.9067 | 78.0496 |
| 8.2 | 78.1924 | 78.3356 | 78.4788 | 78.6220 | 78.7655 | 78.9087 | 79.0522 | 79.1957 | 79.3396 | 79.4834 |
| 8.3 | 79.6273 | 79.7711 | 79.9153 | 80.0592 | 80.2034 | 80.3479 | 80.4921 | 80.6366 | 80.7811 | 80.9260 |
| 8.4 | 81.0705 | 81.2154 | 81.3602 | 81.5054 | 81.6503 | 81.7955 | 81.9406 | 82.0862 | 82.2314 | 82.3769 |
| 8.5 | 82.5224 | 82.6682 | 82.8141 | 82.9600 | 83.1058 | 83.2517 | 83.3979 | 83.5440 | 83.6902 | 83.8367 |
| 8.6 | 83.9833 | 84.1298 | 84.2763 | 84.4228 | 84.5697 | 84.7165 | 84.8634 | 85.0106 | 85.1578 | 85.3049 |
| 8.7 | 85.4521 | 85.5996 | 85.7472 | 85.8947 | 86.0455 | 86.1897 | 86.3376 | 86.4854 | 86.6336 | 86.7815 |
| 8.8 | 86.9297 | 87.0778 | 87.2264 | 87.3745 | 87.5231 | 87.6716 | 87.8204 | 87.9689 | 88.1178 | 88.2666 |
| 8.9 | 88.4192 | 88.5647 | 88.7139 | 88.8630 | 89.0126 | 89.1617 | 89.3113 | 89.4608 | 89.6103 | 89.7602 |
| 9.0 | 89.9100 | 90.0599 | 90.2064 | 90.3599 | 90.5101 | 90.6602 | 90.7778 | 90.9609 | 91.1115 | 91.2620 |
| 9.1 | 91.4125 | 91.5633 | 91.7142 | 91.8650 | 92.0159 | 92.1671 | 92.3183 | 92.4694 | 92.6206 | 92.7721 |
| 9.2 | 92.9237 | 93.0782 | 93.2267 | 93.3785 | 93.5304 | 93.6822 | 93.8341 | 93.9863 | 94.1384 | 94.2906 |
| 9.3 | 94.4428 | 94.5950 | 94.7475 | 94.9000 | 95.0529 | 95.2054 | 95.3582 | 95.5111 | 95.6639 | 95.8171 |
| 9.4 | 95.9703 | 96.1234 | 96.2766 | 96.4298 | 96.5833 | 96.7363 | 96.8903 | 97.0442 | 97.1977 | 97.3516 |
| 9.5 | 97.5057 | 97.6596 | 97.8138 | 97.9679 | 98.1021 | 98.2763 | 98.4308 | 98.5853 | 98.7398 | 98.8943 |
| 9.6 | 99.0492 | 99.2040 | 99.3589 | 99.5141 | 99.6689 | 99.8241 | 99.9793 | 100.1344 | 100.2899 | 100.4455 |
| 9.7 | 100.6010 | 100.7565 | 100.9123 | 101.0678 | 101.2237 | 101.3799 | 101.5357 | 101.6919 | 101.8481 | 102.0042 |
| 9.8 | 102.1607 | 102.3169 | 102.4734 | 102.6299 | 102.7868 | 102.9438 | 103.1001 | 103.2570 | 103.4141 | 103.5710 |
| 9.9 | 103.7282 | 103.8853 | 104.0429 | 104.2000 | 104.3575 | 104.5121 | 104.6726 | 104.8304 | 104.9882 | 105.1461 |
| 10.0 | 105.3039 | 105.4618 | 105.6199 | 105.7781 | 105.9363 | 106.0945 | 106.2530 | 106.4115 | 106.5700 | 106.7285 |

NOTE:—By increasing the quantities in this table by 1 per cent the discharge by the Cippoletti formula ($Q=3.33 \frac{2}{3} L H^{\frac{5}{2}}$) will be obtained.

Table III.—Discharge in second-feet per foot of crest length for certain broad-crested weirs.

Formula: $Q=2.64 \text{ } l H^{\frac{3}{2}}$

| Head H , feet. | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
|------------------|-------|------|------|------|------|------|------|------|------|------|------|
| 0.00 | 0.000 | 2.64 | 7.47 | 13.7 | 21.1 | 29.5 | 38.8 | 48.9 | 59.7 | 71.3 | 83.5 |
| .01 | .003 | 2.68 | 7.52 | 13.8 | 21.2 | 29.6 | 38.9 | 49.0 | 59.8 | 71.4 | 83.6 |
| .02 | .007 | 2.72 | 7.58 | 13.8 | 21.3 | 29.7 | 39.0 | 49.1 | 59.9 | 71.5 | 83.7 |
| .03 | .014 | 2.76 | 7.64 | 13.9 | 21.4 | 29.8 | 39.1 | 49.2 | 60.1 | 71.6 | 83.9 |
| .04 | .021 | 2.80 | 7.69 | 14.0 | 21.4 | 29.9 | 39.2 | 49.3 | 60.2 | 71.7 | 84.0 |
| .05 | .030 | 2.84 | 7.75 | 14.1 | 21.5 | 30.0 | 39.3 | 49.4 | 60.3 | 71.9 | 84.1 |
| .06 | .039 | 2.88 | 7.81 | 14.1 | 21.6 | 30.0 | 39.4 | 49.5 | 60.4 | 72.0 | 84.2 |
| .07 | .049 | 2.92 | 7.86 | 14.2 | 21.7 | 30.1 | 39.5 | 49.6 | 60.5 | 72.1 | 84.4 |
| .08 | .060 | 2.96 | 7.92 | 14.3 | 21.8 | 30.2 | 39.6 | 49.7 | 60.6 | 72.2 | 84.5 |
| .09 | .071 | 3.00 | 7.98 | 14.3 | 21.8 | 30.3 | 39.7 | 49.8 | 60.7 | 72.3 | 84.6 |
| 0.10 | 0.083 | 3.04 | 8.03 | 14.4 | 21.9 | 30.4 | 39.8 | 49.9 | 60.8 | 72.5 | 84.7 |
| .11 | .096 | 3.09 | 8.09 | 14.5 | 22.0 | 30.5 | 39.9 | 50.0 | 61.0 | 72.6 | 84.9 |
| .12 | .110 | 3.13 | 8.15 | 14.5 | 22.1 | 30.6 | 40.0 | 50.2 | 61.1 | 72.7 | 85.0 |
| .13 | .124 | 3.17 | 8.21 | 14.6 | 22.2 | 30.7 | 40.1 | 50.3 | 61.2 | 72.8 | 85.1 |
| .14 | .138 | 3.21 | 8.26 | 14.7 | 22.2 | 30.8 | 40.2 | 50.4 | 61.3 | 72.9 | 85.2 |
| .15 | .153 | 3.26 | 8.32 | 14.8 | 22.3 | 30.8 | 40.3 | 50.5 | 61.4 | 73.1 | 85.4 |
| .16 | .169 | 3.30 | 8.38 | 14.8 | 22.4 | 30.9 | 40.4 | 50.6 | 61.5 | 73.2 | 85.5 |
| .17 | .185 | 3.34 | 8.44 | 14.9 | 22.5 | 31.0 | 40.5 | 50.7 | 61.6 | 73.3 | 85.6 |
| .18 | .202 | 3.38 | 8.50 | 15.0 | 22.6 | 31.1 | 40.6 | 50.8 | 61.8 | 73.4 | 85.7 |
| .19 | .218 | 3.43 | 8.56 | 15.0 | 22.6 | 31.2 | 40.7 | 50.9 | 61.9 | 73.5 | 85.9 |
| 0.20 | 0.236 | 3.47 | 8.61 | 15.1 | 22.7 | 31.3 | 40.8 | 51.0 | 62.0 | 73.7 | 86.0 |
| .21 | .254 | 3.51 | 8.67 | 15.2 | 22.8 | 31.4 | 40.9 | 51.1 | 62.1 | 73.8 | 86.1 |
| .22 | .272 | 3.56 | 8.73 | 15.2 | 22.9 | 31.5 | 41.0 | 51.2 | 62.2 | 73.9 | 86.2 |
| .23 | .291 | 3.60 | 8.79 | 15.3 | 23.0 | 31.6 | 41.0 | 51.3 | 62.3 | 74.0 | 86.4 |
| .24 | .310 | 3.64 | 8.85 | 15.4 | 23.0 | 31.7 | 41.1 | 51.4 | 62.4 | 74.1 | 86.5 |
| .25 | .330 | 3.69 | 8.91 | 16.5 | 23.1 | 31.8 | 41.2 | 51.5 | 62.6 | 74.3 | 86.6 |
| .26 | .350 | 3.73 | 8.97 | 15.5 | 23.2 | 31.8 | 41.3 | 51.6 | 62.7 | 74.4 | 86.8 |
| .27 | .370 | 3.78 | 9.03 | 15.6 | 23.3 | 31.9 | 41.4 | 51.7 | 62.8 | 74.5 | 86.9 |
| .28 | .391 | 3.82 | 9.09 | 15.7 | 23.4 | 32.0 | 41.5 | 51.9 | 62.9 | 74.6 | 87.0 |
| .29 | .412 | 3.87 | 9.15 | 15.8 | 23.4 | 32.1 | 41.6 | 52.0 | 63.0 | 74.8 | 87.1 |
| 0.30 | 0.434 | 3.91 | 9.21 | 15.8 | 23.5 | 32.2 | 41.7 | 52.1 | 63.1 | 74.9 | 87.3 |
| .31 | .456 | 3.96 | 9.27 | 15.9 | 23.6 | 32.3 | 41.8 | 52.2 | 63.2 | 75.0 | 87.4 |
| .32 | .478 | 4.00 | 9.33 | 16.0 | 23.7 | 32.4 | 41.9 | 52.3 | 63.4 | 75.1 | 87.5 |
| .33 | .500 | 4.05 | 9.39 | 16.0 | 23.8 | 32.5 | 42.0 | 52.4 | 63.5 | 75.2 | 87.6 |
| .34 | .524 | 4.10 | 9.45 | 16.2 | 23.9 | 32.6 | 42.1 | 52.5 | 63.6 | 75.4 | 87.8 |
| .35 | .547 | 4.14 | 9.51 | 16.2 | 24.0 | 32.7 | 42.2 | 52.6 | 63.7 | 75.5 | 87.9 |
| .36 | .570 | 4.19 | 9.57 | 16.3 | 24.1 | 32.8 | 42.3 | 52.7 | 63.8 | 75.6 | 88.0 |
| .37 | .594 | 4.23 | 9.63 | 16.3 | 24.1 | 32.8 | 42.4 | 52.8 | 63.9 | 75.7 | 88.2 |
| .38 | .618 | 4.28 | 9.69 | 16.4 | 24.2 | 32.9 | 42.5 | 52.9 | 64.0 | 75.8 | 88.3 |
| .39 | .643 | 4.33 | 9.75 | 16.5 | 24.3 | 33.0 | 42.6 | 53.0 | 64.2 | 76.0 | 88.4 |
| 0.40 | 0.668 | 4.37 | 9.82 | 16.6 | 24.4 | 33.1 | 42.7 | 53.1 | 64.3 | 76.1 | 88.5 |
| .41 | .693 | 4.42 | 9.88 | 16.6 | 24.4 | 33.2 | 42.8 | 53.2 | 64.4 | 76.2 | 88.7 |
| .42 | .719 | 4.47 | 9.94 | 16.7 | 24.5 | 33.3 | 42.9 | 53.4 | 64.5 | 76.3 | 88.8 |
| .43 | .744 | 4.51 | 10.0 | 16.8 | 24.6 | 33.4 | 43.0 | 53.5 | 64.6 | 76.4 | 88.9 |
| .44 | .771 | 4.56 | 10.1 | 16.8 | 24.7 | 33.5 | 43.1 | 53.6 | 64.7 | 76.6 | 89.0 |
| .45 | .797 | 4.61 | 10.1 | 16.9 | 24.8 | 33.6 | 43.2 | 53.7 | 64.8 | 76.7 | 89.2 |
| .46 | .824 | 4.66 | 10.2 | 17.0 | 24.9 | 33.7 | 43.3 | 53.8 | 65.0 | 76.8 | 89.3 |
| .47 | .851 | 4.70 | 10.2 | 17.1 | 24.9 | 33.8 | 43.4 | 53.9 | 65.1 | 76.9 | 89.4 |
| .48 | .878 | 4.75 | 10.3 | 17.1 | 25.0 | 33.9 | 43.6 | 54.0 | 65.2 | 77.0 | 89.6 |
| .49 | .905 | 4.80 | 10.4 | 17.2 | 25.1 | 34.0 | 43.6 | 54.1 | 65.3 | 77.2 | 89.7 |

Table III.—Continued.

| Head <i>H</i> , feet. | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
|-----------------------|-------|------|------|------|------|------|------|------|------|------|------|
| 0.50 | 0.984 | 4.85 | 10.4 | 17.3 | 25.2 | 34.0 | 43.7 | 54.2 | 65.4 | 77.3 | 89.8 |
| .51 | .961 | 4.90 | 10.5 | 17.4 | 25.3 | 34.1 | 43.8 | 54.3 | 65.5 | 77.4 | 90.0 |
| .52 | .990 | 4.95 | 10.6 | 17.4 | 25.4 | 34.2 | 44.0 | 54.4 | 65.6 | 77.5 | 90.1 |
| .53 | 1.02 | 5.00 | 10.6 | 17.5 | 25.4 | 34.3 | 44.1 | 54.6 | 65.8 | 77.7 | 90.2 |
| .54 | 1.05 | 5.04 | 10.7 | 17.6 | 25.5 | 34.4 | 44.2 | 54.7 | 65.9 | 77.8 | 90.3 |
| .55 | 1.08 | 5.09 | 10.8 | 17.7 | 25.6 | 34.5 | 44.3 | 54.8 | 66.0 | 77.9 | 90.5 |
| .56 | 1.11 | 5.14 | 10.8 | 17.7 | 25.7 | 34.6 | 44.4 | 54.9 | 66.1 | 78.0 | 90.6 |
| .57 | 1.14 | 5.19 | 10.9 | 17.8 | 25.8 | 34.7 | 44.5 | 55.0 | 66.2 | 78.2 | 90.7 |
| .58 | 1.17 | 5.24 | 10.9 | 17.9 | 25.9 | 34.8 | 44.6 | 55.1 | 66.3 | 78.3 | 90.8 |
| .59 | 1.20 | 5.29 | 11.0 | 18.0 | 26.0 | 34.9 | 44.7 | 55.2 | 66.5 | 78.4 | 91.0 |
| 0.60 | 1.23 | 5.34 | 11.1 | 18.0 | 26.0 | 35.0 | 44.8 | 55.3 | 66.6 | 78.5 | 91.1 |
| .61 | 1.26 | 5.39 | 11.1 | 18.1 | 26.1 | 35.1 | 44.9 | 55.4 | 66.7 | 78.6 | 91.2 |
| .62 | 1.29 | 5.44 | 11.2 | 18.2 | 26.2 | 35.2 | 45.0 | 55.5 | 66.8 | 78.8 | 91.4 |
| .63 | 1.32 | 5.49 | 11.2 | 18.2 | 26.3 | 35.3 | 45.1 | 55.6 | 66.9 | 78.9 | 91.5 |
| .64 | 1.35 | 5.54 | 11.3 | 18.3 | 26.4 | 35.4 | 45.2 | 55.7 | 67.0 | 79.0 | 91.6 |
| .65 | 1.38 | 5.60 | 11.4 | 18.4 | 26.5 | 35.4 | 45.3 | 55.9 | 67.2 | 79.1 | 91.8 |
| .66 | 1.42 | 5.65 | 11.4 | 18.5 | 26.6 | 35.5 | 45.4 | 56.0 | 67.3 | 79.3 | 91.9 |
| .67 | 1.45 | 5.70 | 11.5 | 18.6 | 26.6 | 35.6 | 45.5 | 56.1 | 67.4 | 79.4 | 92.0 |
| .68 | 1.48 | 5.75 | 11.6 | 18.6 | 26.7 | 35.7 | 45.6 | 56.2 | 67.5 | 79.5 | 92.1 |
| .69 | 1.51 | 5.80 | 11.6 | 18.7 | 26.8 | 35.8 | 45.7 | 56.3 | 67.6 | 79.6 | 92.3 |
| 0.70 | 1.55 | 5.85 | 11.7 | 18.8 | 26.9 | 35.9 | 45.8 | 56.4 | 67.7 | 79.8 | 92.4 |
| .71 | 1.58 | 5.90 | 11.8 | 18.9 | 27.0 | 36.0 | 45.9 | 56.5 | 67.9 | 79.9 | 92.5 |
| .72 | 1.61 | 5.96 | 11.8 | 18.9 | 27.1 | 36.1 | 46.0 | 56.6 | 68.0 | 80.0 | 92.7 |
| .73 | 1.65 | 6.01 | 11.9 | 19.0 | 27.2 | 36.2 | 46.1 | 56.7 | 68.1 | 80.1 | 92.8 |
| .74 | 1.68 | 6.06 | 12.0 | 19.1 | 27.2 | 36.3 | 46.2 | 56.8 | 68.2 | 80.2 | 92.9 |
| .75 | 1.71 | 6.11 | 12.0 | 19.2 | 27.3 | 36.4 | 46.3 | 57.0 | 68.3 | 80.4 | 93.0 |
| .76 | 1.75 | 6.16 | 12.1 | 19.2 | 27.4 | 36.5 | 46.4 | 57.1 | 68.4 | 80.5 | 93.2 |
| .77 | 1.78 | 6.22 | 12.2 | 19.3 | 27.5 | 36.6 | 46.5 | 57.2 | 68.6 | 80.6 | 93.3 |
| .78 | 1.82 | 6.27 | 12.2 | 19.4 | 27.6 | 36.7 | 46.6 | 57.3 | 68.7 | 80.7 | 93.4 |
| .79 | 1.85 | 6.32 | 12.3 | 19.5 | 27.7 | 36.8 | 46.7 | 57.4 | 68.8 | 80.9 | 93.6 |
| 0.80 | 1.89 | 6.38 | 12.4 | 19.6 | 27.8 | 36.9 | 46.8 | 57.5 | 68.9 | 81.0 | 93.7 |
| .81 | 1.92 | 6.43 | 12.4 | 19.6 | 27.8 | 37.0 | 46.9 | 57.6 | 69.0 | 81.1 | 93.8 |
| .82 | 1.96 | 6.48 | 12.5 | 19.7 | 27.9 | 37.1 | 47.0 | 57.7 | 69.2 | 81.2 | 94.0 |
| .83 | 2.00 | 6.54 | 12.6 | 19.8 | 28.0 | 37.2 | 47.1 | 57.8 | 69.3 | 81.4 | 94.1 |
| .84 | 2.03 | 6.59 | 12.6 | 19.9 | 28.1 | 37.3 | 47.2 | 58.0 | 69.4 | 81.5 | 94.2 |
| .85 | 2.07 | 6.64 | 12.7 | 19.9 | 28.2 | 37.4 | 47.3 | 58.1 | 69.5 | 81.6 | 94.4 |
| .86 | 2.10 | 6.70 | 12.8 | 20.0 | 28.3 | 37.4 | 47.4 | 58.2 | 69.6 | 81.7 | 94.5 |
| .87 | 2.14 | 6.75 | 12.8 | 20.1 | 28.4 | 37.5 | 47.5 | 58.3 | 69.7 | 81.9 | 94.6 |
| .88 | 2.18 | 6.80 | 12.9 | 20.2 | 28.5 | 37.6 | 47.6 | 58.4 | 69.9 | 82.0 | 94.7 |
| .89 | 2.22 | 6.86 | 13.0 | 20.2 | 28.5 | 37.7 | 47.7 | 58.5 | 70.0 | 82.1 | 94.9 |
| 0.90 | 2.25 | 6.91 | 13.0 | 20.3 | 28.6 | 37.8 | 47.8 | 58.6 | 70.1 | 82.2 | 95.0 |
| .91 | 2.29 | 6.97 | 13.1 | 20.4 | 28.7 | 37.9 | 48.0 | 58.7 | 70.2 | 82.4 | 95.1 |
| .92 | 2.33 | 7.02 | 13.2 | 20.5 | 28.8 | 38.0 | 48.1 | 58.8 | 70.3 | 82.5 | 95.3 |
| .93 | 2.37 | 7.08 | 13.2 | 20.6 | 28.9 | 38.1 | 48.2 | 59.0 | 70.4 | 82.6 | 95.4 |
| .94 | 2.41 | 7.13 | 13.3 | 20.6 | 29.0 | 38.2 | 48.3 | 59.1 | 70.6 | 82.7 | 95.5 |
| .95 | 2.44 | 7.19 | 13.4 | 20.7 | 29.1 | 38.3 | 48.4 | 59.2 | 70.7 | 82.9 | 95.6 |
| .96 | 2.48 | 7.24 | 13.4 | 20.8 | 29.2 | 38.4 | 48.5 | 59.3 | 70.8 | 83.0 | 95.8 |
| .97 | 2.52 | 7.30 | 13.5 | 20.9 | 29.3 | 38.5 | 48.6 | 59.4 | 70.9 | 83.1 | 95.9 |
| .98 | 2.56 | 7.36 | 13.6 | 21.0 | 29.3 | 38.6 | 48.7 | 59.5 | 71.0 | 83.2 | 96.0 |
| .99 | 2.60 | 7.41 | 13.6 | 21.0 | 29.4 | 38.7 | 48.8 | 59.6 | 71.2 | 83.4 | 96.2 |
| 1.00 | 2.64 | 7.47 | 13.7 | 21.1 | 29.5 | 38.8 | 48.9 | 59.7 | 71.3 | 83.5 | 96.3 |

NOTE:—This table is applicable for use with broad-crested weirs exceeding 2 feet of crest width and for heads from 0.5 foot up to 1.5 or 2 times the breadth of weir crest.

DETERMINATION OF DISCHARGE OVER VARIOUS TYPES OF BROAD-CRESTED WEIRS.

From the weir experiments at the Cornell Hydraulic Laboratory, as outlined in United States Geological Survey Water-Supply Paper No. 200, Mr. E. C. Murphy has derived coefficients to be used in connection with a discharge table computed by Bazin's formula for sharp-crested weirs for determining the discharge over certain types of broad-crested weirs. Table IV gives the discharge per foot of length of crest by Bazin's formula for weirs having a height varying from 2 to 30 feet, and tables V, VI, and VII give the multipliers to be used with this table to give the discharge over broad-crested weirs. Example: Suppose the discharge is to be computed over a rectangular weir that is 10 feet long, 12 feet high, 6 feet crest width, and has an observed head of 2.4 feet.

Table IV shows that for a height (p) of 12 feet and a head (H) of 2.4, the discharge (Q) is 12.42 second-feet. Table V shows that for a height (p) of 12 feet, a crest width (c) of 6 feet, and head (H) of 2.4 feet the multiplier is 0.797. Hence, the discharge is $12.42 \times 0.797 \times 10 = 99.0$ second-feet.

Table IV.—Discharge in second-feet per foot of crest over sharp-crested rectangular weirs without end contractions.^a

$$\text{Formula: } Q = \left(0.405 + \frac{.00984}{H} \right) \left(1 + 0.55 \frac{H^2}{(p+H)^2} \right) LH \sqrt{2gH}.$$

[H =head, in feet, P =height of weir, in feet].

| $H \backslash P$ | 2 | 4 | 6 | 8 | 10 | 20 | 30 |
|------------------|------|------|------|------|------|------|------|
| 0.1 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 |
| .2 | .33 | .33 | .33 | .33 | .33 | .33 | .33 |
| .3 | .58 | .58 | .58 | .58 | .58 | .58 | .58 |
| .4 | .88 | .88 | .87 | .87 | .87 | .87 | .87 |
| .5 | 1.23 | 1.21 | 1.21 | 1.21 | 1.21 | 1.20 | 1.20 |
| .6 | 1.62 | 1.59 | 1.58 | 1.58 | 1.57 | 1.57 | 1.57 |
| .7 | 2.04 | 1.99 | 1.98 | 1.98 | 1.97 | 1.97 | 1.97 |
| .8 | 2.50 | 2.43 | 2.41 | 2.41 | 2.40 | 2.40 | 2.40 |
| .9 | 3.00 | 2.90 | 2.88 | 2.86 | 2.86 | 2.85 | 2.85 |
| 1.0 | 3.53 | 3.40 | 3.36 | 3.35 | 3.34 | 3.33 | 3.33 |
| 1.1 | 4.10 | 3.93 | 3.88 | 3.86 | 3.85 | 3.84 | 3.83 |
| 1.2 | 4.69 | 4.48 | 4.42 | 4.40 | 4.38 | 4.36 | 4.36 |
| 1.3 | 5.32 | 5.07 | 4.99 | 4.96 | 4.94 | 4.92 | 4.91 |
| 1.4 | 5.99 | 5.68 | 5.58 | 5.55 | 5.52 | 5.49 | 5.48 |

^aThis table should not be used where water on the downstream side of the weir is above the level of the crest, nor unless air circulates freely between the overfalling sheet and the downstream face of the weir. If a vacuum forms under the falling sheet the discharge may be 5 per cent greater than given in this table.


Table IV.—Continued.

| $R \backslash p$ | 2 | 4 | 6 | 8 | 10 | 20 | 30 |
|------------------|-------|-------|-------|-------|-------|-------|-------|
| 1.5 | 6.69 | 6.30 | 6.20 | 6.16 | 6.18 | 6.08 | 6.07 |
| 1.6 | 7.40 | 6.97 | 6.84 | 6.78 | 6.75 | 6.69 | 6.68 |
| 1.7 | 8.15 | 7.66 | 7.50 | 7.43 | 7.39 | 7.33 | 7.31 |
| 1.8 | 8.93 | 8.37 | 8.18 | 8.09 | 8.05 | 7.98 | 7.96 |
| 1.9 | 9.74 | 9.11 | 8.89 | 8.79 | 8.74 | 8.65 | 8.63 |
| 2.0 | 10.58 | 9.87 | 9.62 | 9.51 | 9.44 | 9.34 | 9.32 |
| 2.1 | 11.44 | 10.65 | 10.37 | 10.24 | 10.17 | 10.05 | 10.02 |
| 2.2 | 12.33 | 11.46 | 11.14 | 10.99 | 10.91 | 10.78 | 10.75 |
| 2.3 | 13.25 | 12.29 | 11.93 | 11.77 | 11.67 | 11.52 | 11.48 |
| 2.4 | 14.20 | 13.15 | 12.75 | 12.56 | 12.45 | 12.28 | 12.24 |
| 2.5 | 15.18 | 14.03 | 13.59 | 13.37 | 13.25 | 13.06 | 13.02 |
| 2.6 | 16.17 | 14.92 | 14.44 | 14.20 | 14.07 | 13.85 | 13.80 |
| 2.7 | 17.19 | 15.84 | 15.31 | 15.05 | 14.90 | 14.65 | 14.60 |
| 2.8 | 18.23 | 16.79 | 16.21 | 15.92 | 15.76 | 15.48 | 15.42 |
| 2.9 | 19.29 | 17.75 | 17.12 | 16.81 | 16.63 | 16.32 | 16.25 |
| 3.0 | 20.38 | 18.74 | 18.06 | 17.71 | 17.52 | 17.18 | 17.10 |
| 3.1 | 21.50 | 19.74 | 19.01 | 18.64 | 18.42 | 18.05 | 17.96 |
| 3.2 | 22.64 | 20.77 | 19.98 | 19.58 | 19.34 | 18.93 | 18.83 |
| 3.3 | 23.80 | 21.82 | 20.98 | 20.54 | 20.28 | 19.83 | 19.72 |
| 3.4 | 24.98 | 22.89 | 21.99 | 21.52 | 21.24 | 20.75 | 20.63 |
| 3.5 | 26.20 | 23.98 | 23.01 | 22.51 | 22.22 | 21.69 | 21.55 |
| 3.6 | 27.42 | 25.09 | 24.06 | 23.52 | 23.20 | 22.62 | 22.48 |
| 3.7 | 28.67 | 26.23 | 25.13 | 24.55 | 24.21 | 23.58 | 23.43 |
| 3.8 | 29.94 | 27.38 | 26.22 | 25.60 | 25.23 | 24.56 | 24.39 |
| 3.9 | 31.23 | 28.55 | 27.32 | 26.66 | 26.27 | 25.54 | 25.37 |
| 4.0 | 32.54 | 29.74 | 28.45 | 27.74 | 27.32 | 26.55 | 26.35 |
| 4.1 | 33.87 | 30.96 | 29.59 | 28.84 | 28.39 | 27.56 | 27.34 |
| 4.2 | 35.22 | 32.18 | 30.75 | 29.96 | 29.48 | 28.59 | 28.35 |
| 4.3 | 36.59 | 33.43 | 31.92 | 31.09 | 30.58 | 29.68 | 29.38 |
| 4.4 | 37.99 | 34.70 | 33.12 | 32.24 | 31.70 | 30.68 | 30.42 |
| 4.5 | 39.40 | 35.98 | 34.33 | 33.40 | 32.83 | 31.74 | 31.47 |
| 4.6 | 40.83 | 37.29 | 35.56 | 34.58 | 33.98 | 32.82 | 32.53 |
| 4.7 | 42.28 | 38.61 | 36.80 | 35.78 | 35.14 | 33.92 | 33.61 |
| 4.8 | 43.75 | 39.96 | 38.07 | 37.00 | 36.32 | 35.04 | 34.70 |
| 4.9 | 45.23 | 41.32 | 39.35 | 38.23 | 37.52 | 36.17 | 35.80 |
| 5.0 | 46.73 | 42.69 | 40.65 | 39.48 | 38.74 | 37.21 | 36.91 |
| 5.1 | 48.25 | 44.09 | 41.96 | 40.73 | 39.97 | 38.45 | 38.08 |
| 5.2 | 49.79 | 45.50 | 43.29 | 42.01 | 41.20 | 39.61 | 39.17 |
| 5.3 | 51.36 | 46.93 | 44.64 | 43.30 | 42.45 | 40.78 | 40.31 |
| 5.4 | 52.94 | 48.38 | 46.00 | 44.60 | 43.71 | 41.96 | 41.47 |
| 5.5 | 54.54 | 49.85 | 47.38 | 45.93 | 45.00 | 43.16 | 42.64 |
| 5.6 | 56.15 | 51.34 | 48.79 | 47.27 | 46.31 | 44.38 | 43.83 |
| 5.7 | 57.78 | 52.83 | 50.19 | 48.62 | 47.62 | 45.60 | 45.02 |
| 5.8 | 59.42 | 54.34 | 51.62 | 49.99 | 48.94 | 46.83 | 46.22 |
| 5.9 | 61.09 | 55.88 | 53.07 | 51.38 | 50.29 | 48.08 | 47.44 |
| 6.0 | 62.77 | 57.43 | 54.53 | 52.78 | 51.64 | 49.34 | 48.67 |
| 6.1 | 64.46 | 59.00 | 56.00 | 54.20 | 53.02 | 50.61 | 49.91 |
| 6.2 | 66.18 | 60.58 | 57.50 | 55.63 | 54.40 | 51.90 | 51.16 |
| 6.3 | 67.91 | 62.18 | 59.01 | 57.07 | 55.80 | 53.20 | 52.42 |
| 6.4 | 69.65 | 63.79 | 60.53 | 58.53 | 57.22 | 54.50 | 53.70 |

RIVER DISCHARGE.

Table IV.—Continued.

| $\frac{R}{P}$ | 2 | 4 | 6 | 8 | 10 | 20 | 30 |
|---------------|--------|--------|--------|--------|--------|--------|--------|
| 6.5 | 71.42 | 65.42 | 62.07 | 60.01 | 58.65 | 55.82 | 54.98 |
| 6.6 | 73.19 | 67.07 | 63.63 | 61.50 | 60.09 | 57.16 | 56.27 |
| 6.7 | 74.99 | 68.74 | 65.20 | 63.00 | 61.55 | 58.50 | 57.58 |
| 6.8 | 76.80 | 70.42 | 66.78 | 64.53 | 63.02 | 59.96 | 58.90 |
| 6.9 | 78.62 | 72.11 | 68.38 | 66.06 | 64.50 | 61.23 | 60.22 |
| 7.0 | 80.46 | 73.82 | 70.00 | 67.00 | 66.00 | 62.61 | 61.56 |
| 7.1 | 82.32 | 75.55 | 71.63 | 69.17 | 67.52 | 64.00 | 62.91 |
| 7.2 | 84.18 | 77.29 | 73.28 | 70.74 | 69.04 | 65.40 | 64.27 |
| 7.3 | 86.07 | 79.04 | 74.94 | 72.34 | 70.58 | 66.81 | 65.64 |
| 7.4 | 87.97 | 80.81 | 76.61 | 73.94 | 72.14 | 68.24 | 67.02 |
| 7.5 | 89.89 | 82.60 | 78.30 | 75.56 | 73.70 | 69.68 | 68.41 |
| 7.6 | 91.82 | 84.40 | 80.01 | 77.19 | 75.28 | 71.13 | 69.81 |
| 7.7 | 93.76 | 86.22 | 81.73 | 78.84 | 76.88 | 72.59 | 71.23 |
| 7.8 | 95.72 | 88.06 | 83.46 | 80.50 | 78.48 | 74.06 | 72.65 |
| 7.9 | 97.70 | 89.90 | 85.21 | 82.18 | 80.11 | 75.55 | 74.09 |
| 8.0 | 99.68 | 91.75 | 86.97 | 83.87 | 81.74 | 77.04 | 75.58 |
| 8.1 | 101.69 | 93.63 | 88.75 | 85.57 | 83.39 | 78.55 | 76.98 |
| 8.2 | 103.70 | 95.51 | 90.54 | 87.29 | 85.25 | 80.06 | 78.44 |
| 8.3 | 105.73 | 97.42 | 92.34 | 89.02 | 86.72 | 81.59 | 79.92 |
| 8.4 | 107.78 | 99.34 | 94.16 | 90.76 | 88.41 | 83.13 | 81.40 |
| 8.5 | 109.84 | 101.27 | 96.00 | 92.52 | 90.11 | 84.69 | 82.90 |
| 8.6 | 111.91 | 103.21 | 97.84 | 94.29 | 91.82 | 86.25 | 84.41 |
| 8.7 | 113.99 | 105.17 | 99.70 | 96.07 | 93.55 | 87.82 | 85.92 |
| 8.8 | 116.09 | 107.14 | 101.57 | 97.87 | 95.28 | 89.40 | 87.44 |
| 8.9 | 118.20 | 109.13 | 103.46 | 99.68 | 97.04 | 91.00 | 88.98 |
| 9.0 | 120.33 | 111.13 | 105.36 | 101.50 | 98.80 | 92.61 | 90.52 |
| 9.1 | 122.47 | 113.15 | 107.28 | 103.34 | 100.58 | 94.23 | 92.08 |
| 9.2 | 124.62 | 115.18 | 109.21 | 105.19 | 102.37 | 95.86 | 93.65 |
| 9.3 | 126.79 | 117.22 | 111.15 | 107.06 | 104.17 | 97.49 | 95.22 |
| 9.4 | 128.97 | 119.27 | 113.10 | 108.93 | 105.90 | 99.14 | 96.80 |
| 9.5 | 131.16 | 121.34 | 115.07 | 110.82 | 107.82 | 100.80 | 98.40 |
| 9.6 | 133.36 | 123.42 | 117.05 | 112.72 | 109.65 | 102.48 | 100.00 |
| 9.7 | 135.58 | 125.51 | 119.04 | 114.64 | 111.50 | 104.16 | 101.62 |
| 9.8 | 137.82 | 127.63 | 121.05 | 116.57 | 113.37 | 105.85 | 103.25 |
| 9.9 | 140.06 | 129.74 | 123.07 | 118.51 | 115.25 | 107.56 | 104.88 |
| 10.0 | 142.31 | 131.87 | 125.10 | 120.46 | 117.14 | 109.27 | 106.52 |



F.g. 38. —Types of Weirs referred to in Tables V, VI, and VII.

Table VII.—Multipliers to be used in connection with Table IV to obtain the discharge over broad-crested weirs of compound cross-section of types *d* to *m* inclusive, fig. 38.

[*p*=Height of weir, in feet; *H*=observed head, in feet.]

| <i>p</i> | 4.57 | 4.56 | 4.58 | 5.28 | 11.25 | 11.25 | 11.25 | 11.25 | 11.25 | 11.25 |
|---------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Type, fig. 38 | <i>d</i> | <i>e</i> | <i>f</i> | <i>g</i> | <i>h</i> | <i>i</i> | <i>j</i> | <i>k</i> | <i>l</i> | <i>m</i> |
| <i>H</i> | | | | | | | | | | |
| 0.5 | | | | | 0.941 | 0.924 | 0.933 | 0.962 | 0.971 | 0.947 |
| 1.0 | 0.842 | 0.836 | 0.929 | 0.976 | 1.039 | 1.033 | .988 | 1.045 | 1.033 | 1.000 |
| 1.5 | .866 | .834 | .960 | .979 | 1.087 | 1.093 | 1.018 | 1.066 | 1.042 | 1.036 |
| 2.0 | .888 | .831 | .963 | .988 | 1.109 | 1.133 | 1.033 | 1.063 | 1.035 | 1.063 |
| 2.5 | .906 | .826 | .947 | 1.000 | 1.118 | 1.153 | 1.045 | 1.020 | 1.033 | 1.085 |
| 3.0 | .927 | .822 | .942 | 1.016 | 1.120 | 1.163 | 1.054 | .997 | 1.045 | 1.096 |
| 3.5 | .945 | .817 | .936 | 1.032 | 1.127 | 1.169 | 1.060 | .994 | 1.054 | 1.108 |
| 4.0 | .965 | .812 | .931 | 1.044 | 1.123 | 1.165 | 1.060 | .991 | 1.057 | 1.110 |
| 5.0 | 1.00 | .80 | .92 | 1.05 | 1.11 | 1.16 | 1.05 | .98 | 1.05 | 1.10 |
| 6.0 | | | | | 1.11 | 1.15 | 1.04 | .98 | 1.04 | 1.10 |
| 7.0 | | | | | 1.10 | 1.14 | 1.04 | .97 | 1.04 | 1.09 |
| 8.0 | | | | | 1.10 | 1.14 | 1.04 | .97 | 1.03 | 1.09 |
| 9.0 | | | | | 1.09 | 1.14 | 1.03 | .97 | 1.03 | 1.08 |
| 10.0 | | | | | 1.09 | 1.13 | 1.03 | .97 | 1.03 | 1.08 |

Table VIII.—Three-halves powers for numbers from 0 to 12.

| Units Hundredths | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
|---------------------|--------|--------|--------|--------|--------|---------|---------|---------|---------|---------|---------|---------|
| 0.00 | 0.0000 | 1.0000 | 2.8284 | 5.1962 | 8.0000 | 11.1803 | 14.6969 | 18.5203 | 22.6274 | 27.0000 | 31.6228 | 36.4829 |
| .01 | .0010 | 1.0150 | 2.8497 | 5.2222 | 8.0300 | 11.2139 | 14.7837 | 18.5600 | 22.6699 | 27.0450 | 31.6702 | 36.5326 |
| .02 | .0028 | 1.0302 | 2.8710 | 5.2482 | 8.0601 | 11.2475 | 14.7705 | 18.5997 | 22.7123 | 27.0890 | 31.7177 | 36.5824 |
| .03 | .0052 | 1.0453 | 2.8923 | 5.2743 | 8.0902 | 11.2811 | 14.8073 | 18.6394 | 22.7548 | 27.1351 | 31.7652 | 36.6322 |
| .04 | .0080 | 1.0606 | 2.9137 | 5.3004 | 8.1203 | 11.3148 | 14.8442 | 18.6792 | 22.7973 | 27.1802 | 31.8127 | 36.6820 |
| .05 | .0112 | 1.0759 | 2.9352 | 5.3266 | 8.1505 | 11.3485 | 14.8810 | 18.7190 | 22.8399 | 27.2258 | 31.8602 | 36.7319 |
| .06 | .0147 | 1.0913 | 2.9567 | 5.3528 | 8.1807 | 11.3822 | 14.9179 | 18.7589 | 22.8825 | 27.2705 | 31.9078 | 36.7818 |
| .07 | .0185 | 1.1068 | 2.9782 | 5.3791 | 8.2109 | 11.4160 | 14.9549 | 18.7988 | 22.9251 | 27.3156 | 31.9554 | 36.8317 |
| .08 | .0226 | 1.1224 | 2.9998 | 5.4054 | 8.2412 | 11.4497 | 14.9919 | 18.8387 | 22.9677 | 27.3608 | 32.0030 | 36.8816 |
| .09 | .0270 | 1.1380 | 3.0215 | 5.4317 | 8.2715 | 11.4836 | 15.0289 | 18.8786 | 23.0103 | 27.4060 | 32.0506 | 36.9315 |
| 0.10 | 0.0316 | 1.1537 | 3.0432 | 5.4581 | 8.3019 | 11.5174 | 15.0659 | 18.9185 | 23.0530 | 27.4512 | 32.0983 | 36.9815 |
| .11 | .0365 | 1.1695 | 3.0650 | 5.4845 | 8.3323 | 11.5513 | 15.1030 | 18.9585 | 23.0957 | 27.4965 | 32.1460 | 37.0315 |
| .12 | .0416 | 1.1853 | 3.0868 | 5.5110 | 8.3627 | 11.5852 | 15.1400 | 18.9985 | 23.1384 | 27.5418 | 32.1937 | 37.0815 |
| .13 | .0469 | 1.2012 | 3.1086 | 5.5375 | 8.3932 | 11.6192 | 15.1772 | 19.0386 | 23.1812 | 27.5871 | 32.2414 | 37.1315 |
| .14 | .0524 | 1.2172 | 3.1306 | 5.5641 | 8.4237 | 11.6532 | 15.2143 | 19.0786 | 23.2240 | 27.6324 | 32.2892 | 37.1816 |
| .15 | .0581 | 1.2332 | 3.1525 | 5.5907 | 8.4542 | 11.6872 | 15.2515 | 19.1187 | 23.2668 | 27.6778 | 32.3370 | 37.2317 |
| .16 | .0640 | 1.2494 | 3.1745 | 5.6173 | 8.4848 | 11.7213 | 15.2887 | 19.1589 | 23.3096 | 27.7232 | 32.3848 | 37.2817 |
| .17 | .0701 | 1.2656 | 3.1966 | 5.6440 | 8.5154 | 11.7554 | 15.3260 | 19.1990 | 23.3525 | 27.7686 | 32.4326 | 37.3319 |
| .18 | .0764 | 1.2818 | 3.2187 | 5.6708 | 8.5460 | 11.7896 | 15.3632 | 19.2392 | 23.3954 | 27.8140 | 32.4804 | 37.3820 |
| .19 | .0828 | 1.2981 | 3.2409 | 5.6975 | 8.5767 | 11.8236 | 15.4005 | 19.2794 | 23.4383 | 27.8595 | 32.5283 | 37.4322 |

RIVER DISCHARGE.

Table VIII.—Continued.

| <div> Date. Hundredths. </div> | 6 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
|------------------------------------|--------|--------|--------|--------|---------|---------|---------|---------|---------|---------|---------|---------|
| 0.20 | 0.0894 | 1.3145 | 3.2631 | 5.7248 | 8.0074 | 11.8578 | 15.4879 | 19.3196 | 23.4812 | 27.9060 | 32.5762 | 37.4924 |
| .21 | .0962 | 1.3310 | 3.2854 | 5.7512 | 8.0382 | 11.8720 | 15.4752 | 19.3599 | 23.5242 | 27.9514 | 32.6241 | 37.5326 |
| .22 | .1032 | 1.3475 | 3.3077 | 5.7781 | 8.0690 | 11.9268 | 15.5126 | 19.4002 | 23.5672 | 27.9960 | 32.6720 | 37.5628 |
| .23 | .1103 | 1.3641 | 3.3301 | 5.8050 | 8.0998 | 11.9606 | 15.5401 | 19.4405 | 23.6102 | 28.0416 | 32.7200 | 37.6331 |
| .24 | .1176 | 1.3808 | 3.3525 | 5.8320 | 8.7307 | 11.9949 | 15.5666 | 19.4808 | 23.6538 | 28.0872 | 32.7690 | 37.6683 |
| .25 | .1250 | 1.3975 | 3.3750 | 5.8590 | 8.7616 | 12.0293 | 15.6250 | 19.5212 | 23.6963 | 28.1328 | 32.8160 | 37.7396 |
| .26 | .1326 | 1.4144 | 3.3975 | 5.8861 | 8.7925 | 12.0636 | 15.6616 | 19.5576 | 23.7394 | 28.1784 | 32.8640 | 37.7840 |
| .27 | .1403 | 1.4312 | 3.4201 | 5.9132 | 8.8235 | 12.0981 | 15.7001 | 19.6021 | 23.7825 | 28.2241 | 32.9121 | 37.8343 |
| .28 | .1482 | 1.4482 | 3.4427 | 5.9403 | 8.8545 | 12.1326 | 15.7379 | 19.6425 | 23.8257 | 28.2698 | 32.9600 | 37.8847 |
| .29 | .1562 | 1.4652 | 3.4654 | 5.9675 | 8.8856 | 12.1670 | 15.7752 | 19.6880 | 23.8689 | 28.3155 | 33.0068 | 37.9351 |
| 0.30 | 0.1643 | 1.4822 | 3.4881 | 5.9947 | 8.9167 | 12.2015 | 15.8129 | 19.7285 | 23.9121 | 28.3612 | 33.0564 | 37.9855 |
| .31 | .1726 | 1.4994 | 3.5109 | 6.0220 | 8.9478 | 12.2361 | 15.8506 | 19.7641 | 23.9558 | 28.4069 | 33.1046 | 38.0359 |
| .32 | .1810 | 1.5166 | 3.5337 | 6.0493 | 8.9790 | 12.2706 | 15.8882 | 19.8046 | 23.9986 | 28.4527 | 33.1527 | 38.0864 |
| .33 | .1896 | 1.5338 | 3.5566 | 6.0767 | 9.0102 | 12.3053 | 15.9260 | 19.8452 | 24.0413 | 28.4985 | 33.2009 | 38.1369 |
| .34 | .1983 | 1.5512 | 3.5796 | 6.1041 | 9.0414 | 12.3399 | 15.9637 | 19.8858 | 24.0851 | 28.5444 | 33.2492 | 38.1874 |
| .35 | .2071 | 1.5686 | 3.6026 | 6.1315 | 9.0726 | 12.3746 | 16.0015 | 19.9255 | 24.1285 | 28.5902 | 33.2974 | 38.2379 |
| .36 | .2160 | 1.5860 | 3.6255 | 6.1590 | 9.1040 | 12.4093 | 16.0393 | 19.9672 | 24.1718 | 28.6361 | 33.3457 | 38.2884 |
| .37 | .2251 | 1.6035 | 3.6486 | 6.1865 | 9.1353 | 12.4440 | 16.0772 | 20.0079 | 24.2152 | 28.6820 | 33.3940 | 38.3390 |
| .38 | .2342 | 1.6211 | 3.6717 | 6.2141 | 9.1667 | 12.4788 | 16.1150 | 20.0486 | 24.2586 | 28.7279 | 33.4423 | 38.3896 |
| .39 | .2436 | 1.6388 | 3.6949 | 6.2417 | 9.1981 | 12.5136 | 16.1529 | 20.0894 | 24.3021 | 28.7739 | 33.4906 | 38.4402 |
| 0.40 | 0.2530 | 1.6565 | 3.7181 | 6.2693 | 9.2296 | 12.5485 | 16.1909 | 20.1302 | 24.3455 | 28.8199 | 33.5390 | 38.4908 |
| .41 | .2625 | 1.6743 | 3.7413 | 6.2970 | 9.2610 | 12.5833 | 16.2288 | 20.1710 | 24.3890 | 28.8659 | 33.5874 | 38.5415 |
| .42 | .2722 | 1.6921 | 3.7646 | 6.3247 | 9.2925 | 12.6182 | 16.2666 | 20.2118 | 24.4325 | 28.9119 | 33.6358 | 38.5922 |
| .43 | .282 | 1.7100 | 3.7880 | 6.3525 | 9.3241 | 12.6533 | 16.3048 | 20.2527 | 24.4761 | 28.9579 | 33.6842 | 38.6429 |
| .44 | .2919 | 1.7280 | 3.8114 | 6.3803 | 9.3557 | 12.6882 | 16.3429 | 20.2936 | 24.5196 | 29.0040 | 33.7327 | 38.6936 |
| .45 | .3019 | 1.7460 | 3.8349 | 6.4081 | 9.3873 | 12.7232 | 16.3810 | 20.3345 | 24.5632 | 29.0501 | 33.7811 | 38.7443 |
| .46 | .3120 | 1.7641 | 3.8584 | 6.4360 | 9.4189 | 12.7582 | 16.4191 | 20.3755 | 24.6068 | 29.0962 | 33.8297 | 38.7951 |
| .47 | .3222 | 1.7823 | 3.8819 | 6.4639 | 9.4506 | 12.7933 | 16.4572 | 20.4165 | 24.6505 | 29.1424 | 33.8782 | 38.8459 |
| .48 | .3325 | 1.8005 | 3.9055 | 6.4919 | 9.4824 | 12.8284 | 16.4954 | 20.4575 | 24.6941 | 29.1886 | 33.9267 | 38.8967 |
| .49 | .3430 | 1.8188 | 3.9292 | 6.5199 | 9.5141 | 12.8635 | 16.5336 | 20.4985 | 24.7378 | 29.2347 | 33.9753 | 38.9475 |
| 0.50 | 0.3536 | 1.8371 | 3.9529 | 6.5479 | 9.5459 | 12.8986 | 16.5718 | 20.5396 | 24.7815 | 29.2810 | 34.0239 | 38.9984 |
| .51 | .3642 | 1.8555 | 3.9766 | 6.5760 | 9.5778 | 12.9338 | 16.6101 | 20.5807 | 24.8253 | 29.3272 | 34.0725 | 39.0496 |
| .52 | .3750 | 1.8740 | 4.0004 | 6.6041 | 9.6097 | 12.9691 | 16.6484 | 20.6218 | 24.8691 | 29.3735 | 34.1211 | 39.1002 |
| .53 | .3858 | 1.8925 | 4.0242 | 6.6323 | 9.6416 | 13.0043 | 16.6867 | 20.6630 | 24.9129 | 29.4198 | 34.1698 | 39.1511 |
| .54 | .3968 | 1.9111 | 4.0481 | 6.6605 | 9.6735 | 13.0396 | 16.7250 | 20.7041 | 24.9567 | 29.4661 | 34.2185 | 39.2020 |
| .55 | .4079 | 1.9297 | 4.0720 | 6.6887 | 9.7055 | 13.0749 | 16.7634 | 20.7453 | 25.0005 | 29.5124 | 34.2672 | 39.2530 |
| .56 | .4191 | 1.9484 | 4.0960 | 6.7170 | 9.7375 | 13.1103 | 16.8018 | 20.7866 | 25.0444 | 29.5588 | 34.3159 | 39.3040 |
| .57 | .4303 | 1.9672 | 4.1200 | 6.7453 | 9.7695 | 13.1457 | 16.8402 | 20.8278 | 25.0883 | 29.6052 | 34.3647 | 39.3550 |
| .58 | .4417 | 1.9860 | 4.1441 | 6.7737 | 9.8016 | 13.1811 | 16.8787 | 20.8691 | 25.1322 | 29.6516 | 34.4135 | 39.4060 |
| .59 | .4532 | 2.0049 | 4.1682 | 6.8021 | 9.8337 | 13.2165 | 16.9172 | 20.9104 | 25.1762 | 29.6980 | 34.4623 | 39.4571 |
| 0.60 | 0.4648 | 2.0238 | 4.1924 | 6.8305 | 9.8659 | 13.2520 | 16.9557 | 20.9518 | 25.2202 | 29.7445 | 34.5111 | 39.5082 |
| .61 | .4764 | 2.0429 | 4.2166 | 6.8590 | 9.8981 | 13.2875 | 16.9943 | 20.9931 | 25.2642 | 29.7910 | 34.5599 | 39.5593 |
| .62 | .4882 | 2.0619 | 4.2408 | 6.8875 | 9.9303 | 13.3231 | 17.0328 | 21.0345 | 25.3082 | 29.8375 | 34.6088 | 39.6104 |
| .63 | .5000 | 2.0810 | 4.2651 | 6.9161 | 9.9626 | 13.3587 | 17.0714 | 21.0759 | 25.3522 | 29.8841 | 34.6577 | 39.6615 |
| .64 | .5120 | 2.1002 | 4.2895 | 6.9447 | 9.9949 | 13.3943 | 17.1101 | 21.1174 | 25.3963 | 29.9306 | 34.7066 | 39.7127 |
| .65 | .5240 | 2.1195 | 4.3139 | 6.9733 | 10.0272 | 13.4299 | 17.1488 | 21.1589 | 25.4404 | 29.9772 | 34.7557 | 39.7639 |
| .66 | .5362 | 2.1388 | 4.3383 | 7.0020 | 10.0596 | 13.4656 | 17.1874 | 21.2004 | 25.4845 | 30.0238 | 34.8045 | 39.8151 |
| .67 | .5484 | 2.1584 | 4.3628 | 7.0307 | 10.0920 | 13.5013 | 17.2272 | 21.2419 | 25.5287 | 30.0704 | 34.8535 | 39.8663 |
| .68 | .5607 | 2.1775 | 4.3874 | 7.0595 | 10.1244 | 13.5370 | 17.2649 | 21.2834 | 25.5729 | 30.1171 | 34.9025 | 39.9176 |
| .69 | .5732 | 2.1970 | 4.4119 | 7.0883 | 10.1569 | 13.5728 | 17.3037 | 21.3250 | 25.6171 | 30.1638 | 34.9516 | 39.9689 |

Table VIII.—Continued.

| Units. Hundredths. | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
|-----------------------|--------|--------|--------|--------|---------|---------|---------|---------|---------|---------|---------|---------|
| 0.70 | 0.5857 | 2.2165 | 4.4366 | 7.1171 | 10.1894 | 13.6086 | 17.3425 | 21.3666 | 25.6613 | 30.2105 | 35.0006 | 40.0202 |
| .71 | .5983 | 2.2361 | 4.4612 | 7.1460 | 10.2214 | 13.6444 | 17.3814 | 21.4083 | 25.7056 | 30.2572 | 35.0497 | 40.0715 |
| .72 | .6109 | 2.2558 | 4.4859 | 7.1749 | 10.2545 | 13.6803 | 17.4202 | 21.4499 | 25.7499 | 30.3040 | 35.0988 | 40.1228 |
| .73 | .6237 | 2.2755 | 4.5107 | 7.2038 | 10.2871 | 13.7161 | 17.4591 | 21.4916 | 25.7942 | 30.3507 | 35.1479 | 40.1742 |
| .74 | .6366 | 2.2952 | 4.5355 | 7.2328 | 10.3197 | 13.7521 | 17.4981 | 21.5333 | 25.8395 | 30.3975 | 35.1971 | 40.2256 |
| .75 | .6495 | 2.3150 | 4.5604 | 7.2618 | 10.3524 | 13.7880 | 17.5370 | 21.5751 | 25.8828 | 30.4444 | 35.2462 | 40.2770 |
| .76 | .6625 | 2.3349 | 4.5853 | 7.2909 | 10.3851 | 13.8240 | 17.5760 | 21.6169 | 25.9272 | 30.4912 | 35.2954 | 40.3284 |
| .77 | .6757 | 2.3548 | 4.6102 | 7.3200 | 10.4178 | 13.8600 | 17.6150 | 21.6587 | 25.9716 | 30.5381 | 35.3446 | 40.3798 |
| .78 | .6889 | 2.3748 | 4.6352 | 7.3492 | 10.4506 | 13.8961 | 17.6541 | 21.7005 | 26.0161 | 30.5850 | 35.3939 | 40.4313 |
| .79 | .7022 | 2.3949 | 4.6602 | 7.3783 | 10.4834 | 13.9321 | 17.6931 | 21.7423 | 26.0605 | 30.6319 | 35.4431 | 40.4828 |
| 0.80 | 0.7155 | 2.4150 | 4.6853 | 7.4076 | 10.5163 | 13.9682 | 17.7322 | 21.7842 | 26.1050 | 30.6789 | 35.4924 | 40.5343 |
| .81 | .7290 | 2.4351 | 4.7104 | 7.4368 | 10.5492 | 14.0044 | 17.7714 | 21.8261 | 26.1495 | 30.7258 | 35.5417 | 40.5859 |
| .82 | .7425 | 2.4553 | 4.7356 | 7.4661 | 10.5812 | 14.0406 | 17.8105 | 21.8681 | 26.1941 | 30.7728 | 35.5911 | 40.6374 |
| .83 | .7562 | 2.4756 | 4.7608 | 7.4955 | 10.6150 | 14.0768 | 17.8507 | 21.9100 | 26.2386 | 30.8198 | 35.6404 | 40.6890 |
| .84 | .7699 | 2.4959 | 4.7861 | 7.5248 | 10.6480 | 14.1130 | 17.8889 | 21.9520 | 26.2832 | 30.8669 | 35.6898 | 40.7406 |
| .85 | .7837 | 2.5163 | 4.8114 | 7.5542 | 10.6810 | 14.1493 | 17.9282 | 21.9940 | 26.3278 | 30.9139 | 35.7392 | 40.7922 |
| .86 | .7975 | 2.5367 | 4.8367 | 7.5837 | 10.7141 | 14.1856 | 17.9674 | 22.0361 | 26.3725 | 30.9610 | 35.7886 | 40.8439 |
| .87 | .8115 | 2.5572 | 4.8621 | 7.6132 | 10.7472 | 14.2219 | 18.0067 | 22.0781 | 26.4171 | 31.0081 | 35.8380 | 40.8955 |
| .88 | .8255 | 2.5777 | 4.8875 | 7.6427 | 10.7803 | 14.2582 | 18.0461 | 22.1202 | 26.4618 | 31.0553 | 35.8875 | 40.9472 |
| .89 | .8396 | 2.5983 | 4.9130 | 7.6723 | 10.8134 | 14.2946 | 18.0854 | 22.1623 | 26.5065 | 31.1024 | 35.9370 | 40.9989 |
| 0.90 | 0.8538 | 2.6190 | 4.9385 | 7.7019 | 10.8466 | 14.3311 | 18.1248 | 22.2045 | 26.5523 | 31.1496 | 35.9865 | 41.0507 |
| .91 | .8681 | 2.6397 | 4.9641 | 7.7315 | 10.8798 | 14.3675 | 18.1642 | 22.2467 | 26.5990 | 31.1968 | 36.0360 | 41.1024 |
| .92 | .8824 | 2.6604 | 4.9897 | 7.7702 | 10.9131 | 14.4040 | 18.2037 | 22.2889 | 26.6408 | 31.2441 | 36.0856 | 41.1542 |
| .93 | .8969 | 2.6812 | 5.0154 | 7.7909 | 10.9464 | 14.4405 | 18.2432 | 22.3311 | 26.6856 | 31.2913 | 36.1352 | 41.2060 |
| .94 | .9114 | 2.7021 | 5.0411 | 7.8207 | 10.9797 | 14.4770 | 18.2827 | 22.3733 | 26.7305 | 31.3386 | 36.1848 | 41.2578 |
| .95 | .9259 | 2.7230 | 5.0668 | 7.8505 | 11.0131 | 14.5136 | 18.3222 | 22.4156 | 26.7753 | 31.3850 | 36.2344 | 41.3097 |
| .96 | .9406 | 2.7440 | 5.0926 | 7.8808 | 11.0464 | 14.5502 | 18.3617 | 22.4579 | 26.8202 | 31.4332 | 36.2841 | 41.3615 |
| .97 | .9553 | 2.7650 | 5.1184 | 7.9102 | 11.0799 | 14.5869 | 18.4013 | 22.5008 | 26.8651 | 31.4806 | 36.3337 | 41.4134 |
| .98 | .9702 | 2.7861 | 5.1443 | 7.9401 | 11.1133 | 14.6235 | 18.4409 | 22.5426 | 26.9100 | 31.5280 | 36.3834 | 41.4653 |
| .99 | .9850 | 2.8072 | 5.1702 | 7.9700 | 11.1468 | 14.6602 | 18.4806 | 22.5850 | 26.9550 | 31.5754 | 36.4331 | 41.5173 |
| 1.00 | 1.0000 | 2.8284 | 5.1962 | 8.0000 | 11.1803 | 14.6969 | 18.5203 | 22.6274 | 27.0000 | 31.6228 | 36.4829 | 41.5692 |

Table IX.—For converting discharge in second-feet per square mile into run-off in depth in inches over the area.

| Second-feet per square mile. | Period in days. | | | | |
|------------------------------|-----------------|---------|---------|---------|---------|
| | 1 | 28 | 29 | 30 | 31 |
| | Inches. | Inches. | Inches. | Inches. | Inches. |
| 1..... | .03719 | 1.041 | 1.079 | 1.116 | 1.153 |
| 2..... | .07438 | 2.083 | 2.157 | 2.231 | 2.305 |
| 3..... | .11157 | 3.124 | 3.36 | 3.347 | 3.459 |
| 4..... | .14876 | 4.165 | 4.314 | 4.453 | 4.612 |
| 5..... | .18595 | 5.207 | 5.393 | 5.579 | 5.764 |
| 6..... | .22314 | 6.248 | 6.471 | 6.694 | 6.917 |
| 7..... | .26033 | 7.289 | 7.550 | 7.810 | 8.070 |
| 8..... | .29752 | 8.331 | 8.628 | 8.926 | 9.223 |
| 9..... | .33471 | 9.372 | 9.707 | 10.041 | 10.376 |

NOTE.—For partial month multiply the values for one day by the number of days.

Table X.—For converting discharge in second-feet into run-off in acre-feet.

| Second-feet. | Period in days. | | | | |
|--------------|-----------------|-----------------|-----------------|-----------------|-----------------|
| | 1 | 28 | 29 | 30 | 31 |
| | <i>Acre-ft.</i> | <i>Acre-ft.</i> | <i>Acre-ft.</i> | <i>Acre-ft.</i> | <i>Acre-ft.</i> |
| 1..... | 1.983 | 55.54 | 57.52 | 59.50 | 61.49 |
| 2..... | 3.967 | 111.1 | 115.0 | 119.0 | 123.0 |
| 3..... | 5.950 | 166.6 | 172.6 | 178.5 | 184.5 |
| 4..... | 7.934 | 222.1 | 230.1 | 238.0 | 246.0 |
| 5..... | 9.917 | 277.7 | 287.6 | 297.5 | 307.4 |
| 6..... | 11.90 | 333.2 | 345.1 | 357.0 | 368.9 |
| 7..... | 13.88 | 388.8 | 402.6 | 416.5 | 430.4 |
| 8..... | 15.87 | 444.3 | 460.2 | 476.0 | 491.9 |
| 9..... | 17.85 | 499.8 | 517.7 | 535.5 | 553.4 |

NOTE.—For partial month multiply values for one day by the number of days.

Table XI.—For converting discharge in second-feet per day into run-off in millions of gallons.

1 second foot, or 7.4805 gallons per second for 1 day, or 86,400 seconds=646,300 gallons.

| Tens. | Units. | | | | | | | | | |
|--------|--------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| 0..... | | 0.65 | 1.29 | 1.94 | 2.59 | 3.23 | 3.88 | 4.52 | 5.17 | 5.82 |
| 1..... | 6.46 | 7.11 | 7.76 | 8.40 | 9.05 | 9.69 | 10.34 | 10.99 | 11.63 | 12.28 |
| 2..... | 12.93 | 13.57 | 14.22 | 14.87 | 15.51 | 16.16 | 16.80 | 17.45 | 18.10 | 18.74 |
| 3..... | 19.39 | 20.04 | 20.68 | 21.33 | 21.97 | 22.62 | 23.27 | 23.91 | 24.56 | 25.21 |
| 4..... | 25.85 | 26.50 | 27.15 | 27.79 | 28.44 | 29.08 | 29.73 | 30.38 | 31.02 | 31.67 |
| 5..... | 32.32 | 32.96 | 33.61 | 34.25 | 34.90 | 35.55 | 36.19 | 36.84 | 37.49 | 38.13 |
| 6..... | 38.78 | 39.43 | 40.07 | 40.72 | 41.36 | 42.01 | 42.66 | 43.30 | 43.95 | 44.60 |
| 7..... | 45.24 | 45.89 | 46.53 | 47.18 | 47.83 | 48.47 | 49.12 | 49.77 | 50.41 | 51.06 |
| 8..... | 51.71 | 52.35 | 53.00 | 53.64 | 54.29 | 54.94 | 55.58 | 56.23 | 56.88 | 57.52 |
| 9..... | 58.17 | 58.81 | 59.46 | 60.11 | 60.75 | 61.40 | 62.05 | 62.69 | 63.34 | 63.99 |

Table XII.—For converting run-off in millions of gallons into discharge in second-feet per day.

1 million gallons per 24 hours = $\frac{231,000,000}{1,728 \times 86,400}$ cubic feet per second, or 1.547 second feet.

| Tens. | Units. | | | | | | | | | |
|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| 0..... | | 1.55 | 3.09 | 4.64 | 6.19 | 7.74 | 9.28 | 10.83 | 12.38 | 13.93 |
| 1..... | 15.47 | 17.02 | 18.57 | 20.11 | 21.66 | 23.21 | 24.76 | 26.30 | 27.85 | 29.40 |
| 2..... | 30.94 | 32.49 | 34.04 | 35.59 | 37.13 | 38.68 | 40.23 | 41.78 | 43.32 | 44.87 |
| 3..... | 46.42 | 47.96 | 49.51 | 51.06 | 52.61 | 54.15 | 55.70 | 57.25 | 58.79 | 60.34 |
| 4..... | 61.80 | 63.44 | 64.98 | 66.53 | 68.08 | 69.63 | 71.17 | 72.72 | 74.27 | 75.81 |
| 5..... | 77.36 | 78.91 | 80.46 | 82.00 | 83.55 | 85.10 | 86.64 | 88.19 | 89.74 | 91.29 |
| 6..... | 92.83 | 94.38 | 95.93 | 97.48 | 99.02 | 100.57 | 102.12 | 103.66 | 105.21 | 106.76 |
| 7..... | 108.31 | 109.85 | 111.40 | 112.95 | 114.49 | 116.04 | 117.59 | 119.14 | 120.68 | 122.23 |
| 8..... | 123.78 | 125.33 | 126.87 | 128.42 | 129.97 | 131.51 | 133.06 | 134.61 | 136.16 | 137.70 |
| 9..... | 139.25 | 140.80 | 142.34 | 143.89 | 145.44 | 146.99 | 148.53 | 150.08 | 151.63 | 153.18 |

Table XIII.—For converting run-off in acre-feet into run-off in million gallons.

1 acre-foot = 43,560 cubic feet = $\frac{43,560 \times 1,728}{231}$, or $\frac{75,271,680}{231}$ or 325,850 gallons.

| Tens. | Units. | | | | | | | | | |
|-------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| 0 | | 0.326 | 0.652 | 0.978 | 1.303 | 1.629 | 1.955 | 2.281 | 2.607 | 2.933 |
| 1 | 3.258 | 3.584 | 3.910 | 4.236 | 4.562 | 4.888 | 5.214 | 5.540 | 5.865 | 6.191 |
| 2 | 6.517 | 5.843 | 7.169 | 7.495 | 7.820 | 8.146 | 8.472 | 8.798 | 9.124 | 9.450 |
| 3 | 9.776 | 10.101 | 10.427 | 10.753 | 11.079 | 11.405 | 11.731 | 12.056 | 12.382 | 12.708 |
| 4 | 13.034 | 13.360 | 13.686 | 14.012 | 14.337 | 14.663 | 14.989 | 15.315 | 15.641 | 15.967 |
| 5 | 16.293 | 16.618 | 16.944 | 17.270 | 17.596 | 17.922 | 18.248 | 18.574 | 18.899 | 19.225 |
| 6 | 19.551 | 19.877 | 20.203 | 20.529 | 20.854 | 21.180 | 21.506 | 21.832 | 22.158 | 22.484 |
| 7 | 22.810 | 23.135 | 23.461 | 23.787 | 24.113 | 24.439 | 24.765 | 25.090 | 25.416 | 25.742 |
| 8 | 26.069 | 26.394 | 26.720 | 27.046 | 27.372 | 27.697 | 28.023 | 28.349 | 28.675 | 29.001 |
| 9 | 29.327 | 29.652 | 29.978 | 30.304 | 30.630 | 30.955 | 31.282 | 31.608 | 31.933 | 32.259 |

Table XIV.—For converting run-off in million gallons into run-off in acre-feet.

One million United States liquid gallons or 231 million cubic inches = 133,680,555 cubic feet, or $\frac{133,680}{43,560}$ = 3.0689 acre-feet.

| Tens. | Units. | | | | | | | | | |
|-------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| 0 | | 3.07 | 6.14 | 9.21 | 12.28 | 15.34 | 18.41 | 21.48 | 24.55 | 27.62 |
| 1 | 30.69 | 33.76 | 36.83 | 39.90 | 42.96 | 46.03 | 49.10 | 52.17 | 55.24 | 58.31 |
| 2 | 61.38 | 64.45 | 67.52 | 70.58 | 73.65 | 76.72 | 79.79 | 82.86 | 85.93 | 89.00 |
| 3 | 92.07 | 95.14 | 98.20 | 101.27 | 104.34 | 107.41 | 110.48 | 113.55 | 116.62 | 119.69 |
| 4 | 122.76 | 125.82 | 128.89 | 131.96 | 135.03 | 138.10 | 141.17 | 144.24 | 147.31 | 150.38 |
| 5 | 153.44 | 156.51 | 159.58 | 162.65 | 165.72 | 168.79 | 171.86 | 174.93 | 178.00 | 181.06 |
| 6 | 194.13 | 197.20 | 200.27 | 203.34 | 206.41 | 209.48 | 212.55 | 215.62 | 218.68 | 221.75 |
| 7 | 214.82 | 217.89 | 220.96 | 224.03 | 227.10 | 230.17 | 233.24 | 236.30 | 239.37 | 242.44 |
| 8 | 245.51 | 248.58 | 251.65 | 254.72 | 257.79 | 260.86 | 263.92 | 266.99 | 270.06 | 273.13 |
| 9 | 276.20 | 279.27 | 282.34 | 285.41 | 288.48 | 291.54 | 294.61 | 297.68 | 300.75 | 303.82 |

Table XV.—Values of c for use in the Chezy formula $V = c_1/\sqrt{R_s}$.

| Slope. | R. | n .020 | n .025 | n .030 | n .035 | n .040 | n .045 | n .050 | n .055 | n .060 |
|--------|------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| .0001 | 3.28 | 91 | 73 | 60 | 52 | 46 | 40 | 36 | 33 | 30 |
| | 10 | 111 | 92 | 78 | 69 | 62 | 55 | 50 | 46 | 42 |
| | 20 | 122 | 102 | 89 | 79 | 71 | 65 | 60 | 55 | 51 |
| | 50 | 134 | 114 | 100 | 91 | 83 | 76 | 71 | 67 | 63 |
| .0002 | 100 | 140 | 121 | 108 | 98 | 91 | 84 | 79 | 74 | 70 |
| | 10 | 108 | 89 | 76 | 67 | 60 | 53 | 49 | 45 | 41 |
| | 20 | 117 | 98 | 85 | 76 | 68 | 61 | 57 | 53 | 49 |
| | 50 | 126 | 108 | 94 | 85 | 78 | 71 | 66 | 62 | 58 |
| .0004 | 100 | 131 | 113 | 99 | 90 | 83 | 77 | 72 | 68 | 64 |
| | 10 | 107 | 88 | 75 | 66 | 59 | 53 | 48 | 44 | 41 |
| | 20 | 115 | 96 | 83 | 73 | 66 | 60 | 55 | 51 | 48 |
| | 50 | 123 | 104 | 91 | 82 | 75 | 68 | 63 | 59 | 56 |
| .0010 | 100 | 127 | 108 | 96 | 87 | 80 | 73 | 68 | 64 | 61 |
| | 10 | 105 | 87 | 74 | 65 | 58 | 52 | 47 | 44 | 40 |
| | 20 | 113 | 94 | 81 | 72 | 65 | 59 | 54 | 50 | 47 |
| | 50 | 120 | 101 | 89 | 79 | 72 | 66 | 61 | 57 | 54 |
| .010 | 100 | 124 | 105 | 94 | 85 | 77 | 71 | 66 | 62 | 59 |
| | 10 | 105 | 86 | 74 | 65 | 58 | 51 | 47 | 43 | 40 |
| | 20 | 112 | 93 | 80 | 71 | 64 | 58 | 53 | 49 | 46 |
| | 50 | 119 | 100 | 87 | 78 | 71 | 65 | 60 | 56 | 53 |
| | 100 | 122 | 104 | 91 | 82 | 75 | 69 | 65 | 61 | 58 |

NOTE.—For $R = 3.28$ feet, n constant, c is constant for all values of slope. For slopes greater than 0.01, or fall of 52.8 feet per mile, c remains nearly constant.

Table XVI.—Square roots of numbers ($\sqrt{R} \sqrt{s}$) for use in Kutter's formula. See Pl. V, Chapter III.

| R | \sqrt{R} | R | \sqrt{R} | R | \sqrt{R} | R | \sqrt{R} | R | \sqrt{R} | s | \sqrt{s} |
|------|------------|------|------------|------|------------|-------|------------|-------|------------|----------|------------|
| 0.05 | 0.224 | 3.05 | 1.746 | 6.05 | 2.460 | 9.05 | 3.008 | 20.25 | 4.500 | .00002 | .00447 |
| 0.10 | 0.316 | 3.10 | 1.761 | 6.10 | 2.470 | 9.10 | 3.017 | 20.50 | 4.528 | .000025 | .005 |
| 0.15 | 0.387 | 3.15 | 1.775 | 6.15 | 2.480 | 9.15 | 3.025 | 20.75 | 4.555 | .0000275 | .00548 |
| 0.20 | 0.447 | 3.20 | 1.789 | 6.20 | 2.490 | 9.20 | 3.033 | 21.00 | 4.583 | .00003 | .00592 |
| 0.25 | 0.500 | 3.25 | 1.803 | 6.25 | 2.500 | 9.25 | 3.041 | 21.25 | 4.610 | .000035 | .00632 |
| 0.30 | 0.548 | 3.30 | 1.817 | 6.30 | 2.510 | 9.30 | 3.050 | 21.50 | 4.637 | .00004 | .00671 |
| 0.35 | 0.592 | 3.35 | 1.830 | 6.35 | 2.520 | 9.35 | 3.058 | 21.75 | 4.664 | .000045 | .00707 |
| 0.40 | 0.632 | 3.40 | 1.844 | 6.40 | 2.530 | 9.40 | 3.066 | 22.00 | 4.690 | .00005 | .00745 |
| 0.45 | 0.671 | 3.45 | 1.857 | 6.45 | 2.540 | 9.45 | 3.074 | 22.25 | 4.717 | .00006 | .00783 |
| 0.50 | 0.707 | 3.50 | 1.871 | 6.50 | 2.550 | 9.50 | 3.082 | 22.50 | 4.743 | .00007 | .00827 |
| 0.55 | 0.742 | 3.55 | 1.884 | 6.55 | 2.559 | 9.55 | 3.090 | 22.75 | 4.770 | .00008 | .00864 |
| 0.60 | 0.775 | 3.60 | 1.897 | 6.60 | 2.569 | 9.60 | 3.098 | 23.00 | 4.796 | .00009 | .00909 |
| 0.65 | 0.806 | 3.65 | 1.910 | 6.65 | 2.579 | 9.65 | 3.106 | 23.25 | 4.822 | .0001 | .01 |
| 0.70 | 0.837 | 3.70 | 1.924 | 6.70 | 2.588 | 9.70 | 3.114 | 23.50 | 4.848 | .00012 | .0110 |
| 0.75 | 0.866 | 3.75 | 1.936 | 6.75 | 2.598 | 9.75 | 3.122 | 23.75 | 4.873 | .00014 | .0118 |
| 0.80 | 0.894 | 3.80 | 1.949 | 6.80 | 2.608 | 9.80 | 3.130 | 24.00 | 4.899 | .00016 | .0126 |
| 0.85 | 0.922 | 3.85 | 1.962 | 6.85 | 2.617 | 9.85 | 3.138 | 24.25 | 4.924 | .00018 | .0134 |
| 0.90 | 0.949 | 3.90 | 1.975 | 6.90 | 2.627 | 9.90 | 3.146 | 24.50 | 4.950 | .0002 | .0141 |
| 0.95 | 0.975 | 3.95 | 1.987 | 6.95 | 2.636 | 9.95 | 3.154 | 24.75 | 4.975 | .00025 | .0158 |
| 1.00 | 1.000 | 4.00 | 2.000 | 7.00 | 2.646 | 10.00 | 3.162 | 25.00 | 5.000 | .0003 | .0173 |
| 1.05 | 1.025 | 4.05 | 2.012 | 7.05 | 2.655 | 10.25 | 3.202 | 25.25 | 5.025 | .00035 | .0187 |
| 1.10 | 1.049 | 4.10 | 2.025 | 7.10 | 2.665 | 10.50 | 3.240 | 25.50 | 5.050 | .0004 | .02 |
| 1.15 | 1.072 | 4.15 | 2.037 | 7.15 | 2.674 | 10.75 | 3.279 | 25.75 | 5.074 | .0005 | .0224 |
| 1.20 | 1.095 | 4.20 | 2.049 | 7.20 | 2.683 | 11.00 | 3.317 | 26.00 | 5.099 | .0006 | .0245 |
| 1.25 | 1.118 | 4.25 | 2.062 | 7.25 | 2.693 | 11.25 | 3.354 | 26.25 | 5.123 | .0007 | .0265 |
| 1.30 | 1.140 | 4.30 | 2.074 | 7.30 | 2.702 | 11.50 | 3.391 | 26.50 | 5.148 | .0008 | .0285 |
| 1.35 | 1.162 | 4.35 | 2.086 | 7.35 | 2.711 | 11.75 | 3.428 | 26.75 | 5.172 | .0009 | .03 |
| 1.40 | 1.183 | 4.40 | 2.098 | 7.40 | 2.720 | 12.00 | 3.464 | 27.00 | 5.196 | .001 | .0316 |
| 1.45 | 1.204 | 4.45 | 2.110 | 7.45 | 2.729 | 12.25 | 3.500 | 27.25 | 5.220 | .0012 | .0346 |
| 1.50 | 1.225 | 4.50 | 2.121 | 7.50 | 2.739 | 12.50 | 3.536 | 27.50 | 5.244 | .0014 | .0374 |
| 1.55 | 1.245 | 4.55 | 2.133 | 7.55 | 2.748 | 12.75 | 3.571 | 27.75 | 5.268 | .0016 | .04 |
| 1.60 | 1.265 | 4.60 | 2.145 | 7.60 | 2.757 | 13.00 | 3.606 | 28.00 | 5.292 | .0018 | .0424 |
| 1.65 | 1.285 | 4.65 | 2.156 | 7.65 | 2.766 | 13.25 | 3.640 | 28.25 | 5.315 | .002 | .0447 |
| 1.70 | 1.304 | 4.70 | 2.168 | 7.70 | 2.775 | 13.50 | 3.674 | 28.50 | 5.339 | .003 | .0548 |
| 1.75 | 1.323 | 4.75 | 2.179 | 7.75 | 2.784 | 13.75 | 3.708 | 28.75 | 5.362 | .004 | .0632 |
| 1.80 | 1.342 | 4.80 | 2.191 | 7.80 | 2.793 | 14.00 | 3.742 | 29.00 | 5.385 | .005 | .0707 |
| 1.85 | 1.360 | 4.85 | 2.202 | 7.85 | 2.802 | 14.25 | 3.775 | 29.25 | 5.408 | | |
| 1.90 | 1.378 | 4.90 | 2.214 | 7.90 | 2.811 | 14.50 | 3.808 | 29.50 | 5.431 | | |
| 1.95 | 1.396 | 4.95 | 2.225 | 7.95 | 2.820 | 14.75 | 3.841 | 29.75 | 5.454 | | |
| 2.00 | 1.414 | 5.00 | 2.236 | 8.00 | 2.828 | 15.00 | 3.873 | 30.00 | 5.477 | | |
| 2.05 | 1.432 | 5.05 | 2.247 | 8.05 | 2.837 | 15.25 | 3.905 | 30.25 | 5.500 | | |
| 2.10 | 1.449 | 5.10 | 2.258 | 8.10 | 2.846 | 15.50 | 3.937 | 30.50 | 5.523 | | |
| 2.15 | 1.466 | 5.15 | 2.269 | 8.15 | 2.855 | 15.75 | 3.969 | 30.75 | 5.545 | | |
| 2.20 | 1.483 | 5.20 | 2.280 | 8.20 | 2.864 | 16.00 | 4.000 | 31.00 | 5.568 | | |
| 2.25 | 1.500 | 5.25 | 2.291 | 8.25 | 2.872 | 16.25 | 4.031 | 31.25 | 5.590 | | |
| 2.30 | 1.517 | 5.30 | 2.302 | 8.30 | 2.881 | 16.50 | 4.062 | 31.50 | 5.612 | | |
| 2.35 | 1.533 | 5.35 | 2.313 | 8.35 | 2.890 | 16.75 | 4.093 | 31.75 | 5.635 | | |
| 2.40 | 1.549 | 5.40 | 2.324 | 8.40 | 2.898 | 17.00 | 4.123 | 32.00 | 5.657 | | |
| 2.45 | 1.565 | 5.45 | 2.335 | 8.45 | 2.907 | 17.25 | 4.153 | 32.25 | 5.679 | | |
| 2.50 | 1.581 | 5.50 | 2.345 | 8.50 | 2.915 | 17.50 | 4.183 | 32.50 | 5.701 | | |
| 2.55 | 1.597 | 5.55 | 2.356 | 8.55 | 2.924 | 17.75 | 4.213 | 32.75 | 5.723 | | |
| 2.60 | 1.612 | 5.60 | 2.366 | 8.60 | 2.933 | 18.00 | 4.243 | 33.00 | 5.745 | | |
| 2.65 | 1.628 | 5.65 | 2.377 | 8.65 | 2.941 | 18.25 | 4.272 | 33.25 | 5.766 | | |
| 2.70 | 1.643 | 5.70 | 2.387 | 8.70 | 2.950 | 18.50 | 4.301 | 33.50 | 5.788 | | |
| 2.75 | 1.658 | 5.75 | 2.398 | 8.75 | 2.958 | 18.75 | 4.330 | 33.75 | 5.809 | | |
| 2.80 | 1.673 | 5.80 | 2.408 | 8.80 | 2.966 | 19.00 | 4.359 | 34.00 | 5.831 | | |
| 2.85 | 1.688 | 5.85 | 2.419 | 8.85 | 2.975 | 19.25 | 4.387 | 34.25 | 5.852 | | |
| 2.90 | 1.703 | 5.90 | 2.429 | 8.90 | 2.983 | 19.50 | 4.416 | 34.50 | 5.874 | | |
| 2.95 | 1.718 | 5.95 | 2.439 | 8.95 | 2.992 | 19.75 | 4.444 | 34.75 | 5.895 | | |
| 3.00 | 1.732 | 6.00 | 2.449 | 9.00 | 3.000 | 20.00 | 4.472 | 35.00 | 5.916 | | |

Table XVII.—Convenient equivalents.

| |
|--|
| 1 second-foot equals 40 California miner's inches. (Law of March 23, 1901.) |
| 1 second-foot equals 38.4 Colorado miner's inches. |
| 1 second-foot equals 40 Arizona miner's inches. |
| 1 second-foot equals 7.48 United States gallons per second; equals 448.8 gallons per minute; equals 646,272 gallons for one day. |
| 1 second-foot equals 6.23 British imperial gallons per second. |
| 1 second-foot for one year covers one square mile 1.131 feet deep; 13.57 inches deep. |
| 1 second-foot for one year equals 31,536,000 cubic feet. |
| 1 second-foot equals about 1 acre-inch per hour. |
| 1 second-foot falling 10 feet equals 1.136 horsepower. |
| 100 California miner's inches equal 15.7 United States gallons per second. |
| 100 California miner's inches equal 96.0 Colorado miner's inches. |
| 100 California miner's inches for one day equal 4.96 acre-feet. |
| 100 Colorado miner's inches equal 2.60 second-feet. |
| 100 Colorado miner's inches equal 19.5 United States gallons per second. |
| 100 Colorado miner's inches equal 104 California miner's inches. |
| 100 Colorado miner's inches for one day equal 5.17 acre-feet. |
| 100 United States gallons per minute equal 0.223 second-foot. |
| 100 United States gallons per minute for one day equal 0.442 acre-foot. |
| 1,000,000 United States gallons per day equal 1.55 second-feet. |
| 1,000,000 United States gallons equal 3.07 acre-feet. |
| 1,000,000 cubic feet equal 22.95 acre-feet. |
| 1 acre-foot equals 325,850 gallons. |
| 1 inch deep on 1 square mile equals 2,323,200 cubic feet. |
| 1 inch deep on 1 square mile equals 0.0737 second-foot per year. |
| 1 inch equals 2.54 centimeters. |
| 1 foot equals 0.3048 meter. |
| 1 yard equals 0.9144 meter. |
| 1 mile equals 1.60935 kilometers. |
| 1 mile equals 1,760 yards; equals 5,280 feet; equals 63,360 inches. |
| 1 square yard equals 0.836 square meter. |
| 1 acre equals 0.4047 hectare |
| 1 acre equals 43,560 square feet; equals 4,840 square yards. |
| 1 acre equals 209 feet square, nearly. |
| 1 square mile equals 259 hectares. |
| 1 square mile equals 2.59 square kilometers. |
| 1 cubic foot equals 0.0283 cubic meter. |
| 1 cubic foot equals 7.48 gallons; equals 0.804 bushel. |
| 1 cubic foot of water weighs 62.5 pounds. |
| 1 cubic yard equals 0.7646 cubic meter. |
| 1 gallon equals 3.7854 liters. |
| 1 gallon equals 8.36 pounds of water. |
| 1 gallon equals 231 cubic inches (liquid measure). |
| 1 pound equals 0.4536 kilogram. |
| 1 avoirdupois pound equals 7,000 grains. |
| 1 troy pound equals 5,760 grams. |

RIVER DISCHARGE.

- 1 meter equals 39.37 inches. Log. 1.5951654.
 1 meter equals 3.280833 feet. Log. 0.5159842.
 1 meter equals 1.093611 yards. Log. 0.0388629.
 1 kilometer equals 3,281 feet; equals five-eighths mile, nearly.
 1 square meter equals 10.764 square feet; equals 1.196 square yards.
 1 hectare equals 2.471 acres.
 1 cubic meter equals 35.314 cubic feet; equals 1.308 cubic yards.
 1 liter equals 1.0567 quarts.
 1 gram equals 15.43 grains.
 1 kilogram equals 2.2046 pounds.
 1 tonneau equals 2,204.6 pounds.
 1 foot per second equals 1.097 kilometers per hour.
 1 foot per second equals 0.68 mile per hour.
 1 cubic meter per minute equals 0.5886 second-foot.
 1 atmosphere equals 15 pounds per square inch; equals 1 ton per square foot;
 equals 1 kilogram per square centimeter.
 Acceleration of gravity equals 32.16 feet per second every second.
 1 horsepower equals 550 foot-pounds per second.
 1 horsepower equals 76.04 kilogram-meters per second.
 1 horsepower equals 746 watts.
 1 horsepower equals 1 second-foot falling 8.80 feet.
 1½ horsepowers equal about 1 kilowatt.
 To calculate water power quickly: $\frac{\text{Sec.-ft.} \times \text{fall in feet}}{11} = \text{Net horsepower on}$
 water wheel, realizing 80 per cent of the theoretical power.
 To change miles to inches on map:
 Scale 1:125000, 1 mile=0.50688 inch.
 Scale 1:90000, 1 mile=0.70400 inch.
 Scale 1:62500, 1 mile=1.01376 inches.
 Scale 1:45000, 1 mile=1.40800 inches.

INDEX.

| | PAGE. | | PAGE. |
|--|------------------------|---|--------------|
| Accuracy of stream-flow data | 122 | Connecticut River, basin of, average rain-fall and run-off in | 146-149, 153 |
| Acre-feet, table for computing from million gallons | 175 | Controls, artificial | 42, 43 |
| table for converting into million gallons | 175 | Control section | 45, 46 |
| Acre-foot, use of, as unit of run-off | 121 | Cost of records, conditions affecting | 46 |
| value of | 177 | Cross-section, determination of | 50, 51 |
| Appomattox River, basin of, average rain-fall and run-off in | 146-149, 153 | standard | 51 |
| Area curves, construction of | 92-95 | typical, figure showing | 65 |
| definition of | 92 | Cross-section paper, use of | 97-104 |
| figures showing | 93, 91, 96, 98, 100 | Cultivation, effect of, on stream flow | 1:6 |
| use of, in constructing rating curves | 94, 99 | Current meters, care of | 16-20 |
| Areas, measurement of | 125, 129 | description of | 6-22 |
| of quadrilaterals | 127-128 | discharge measurements by means of | 61-76 |
| Artificial channels, discharge measurements in | 76 | plate showing | 6 |
| Automatic gages | 30-36 | rating of | 20-22 |
| | | use of, in determining velocity | 51-61 |
| Bazin formulas, discussion of | 88, 89 | Current-meter rating curves, figure showing | 21, 23 |
| use of, in computing discharge over sharp-crested weirs | 166 | Current-meter rating station, plate showing | 22 |
| Bench marks, establishment and use of | 23-36, 85 | Current-meter stations, requisite conditions for | 44 |
| Boat stations, establishment of | 41 | Daily discharge. <i>See</i> Discharge, daily. | |
| Bolster method of interpolating discharge, description of | 110-113 | Dams. <i>See</i> Weirs. | |
| figure illustrating | 111 | Diagrams, value of, as compared with rating tables | 90 |
| Cable car, plate showing | 34, 36 | Discharge, daily, computation of | 91-120 |
| Cable stations, equipment of, description of | 37-41 | relation of, to gage height | 83 |
| plate showing | 36 | table for computing, from run-off | 174 |
| Car, cable, description of | 39-40 | tables for converting, into run-off | 173, 174 |
| plate showing | 34, 36 | units of | 121 |
| Census. <i>See</i> United States Census | | Discharge measurements, data obtained in, use of | 91-140 |
| Chenango River, vertical velocity-curves on, figure showing | 53 | methods of making | 49-80 |
| Chezy formula, use of, in determining velocity | 1, 77 | Drainage, artificial, for controlling stream flow | 156 |
| values of <i>c</i> for, table showing | 175 | Duration of flow. <i>See</i> Stream flow, duration of. | |
| Cippoletti weir, construction of | 84 | Ellet, Charles | 2 |
| discharge over, determination of | 163 | End contraction, allowance for, in weir formulas | 87 |
| figure showing | 83 | Engineers, Chief of, United States Army, reports of | 139 |
| formula applicable to | 88 | Equipment for gaging streams, description of | 5-43 |
| City officials, reports of | 139 | Error, sources of, in estimating stream flow | 122 |
| Coefficient of roughness. <i>See</i> Roughness, coefficient of. | | Estimates of stream flow, sources of error in | 122 |
| Commissions, special, reports of | 139 | suggestions for | 125 |
| Computation, methods of, in discharge measurements | 61-67, 89, 90, 113-120 | | |

| | PAGE. | | PAGE. |
|--|----------------|--|--------------|
| Evaporation, discussion of, as affecting | | Indicators, current-meter, description of . | 12, 13 |
| stream flow | 150-152 | Initial point. <i>See</i> Soundings. | |
| effect on, of character of soil | 153-154 | Instruments for gaging stream, descrip- | |
| effect on, of vegetation | 155-156 | tion of | 5-43 |
| measurement of | 43, 150-152 | for determining climatological data . | 43 |
| seasonal variations in | 152 | Integration method, determination of | |
| seasonal variations in | 152 | mean velocity by | 61 |
| Float stations, requisite conditions for . . | 76, 77 | James River, basin of, average rainfall | |
| Floats, description of | 5, 6 | and run-off in | 146-149, 153 |
| use of, in determining velocity | 76, 77 | Kutter formula, diagram for applica- | |
| Flow of stream. <i>See</i> Stream flow. | | tion of | 78 |
| Forests, effect of, on stream flow | 155, 156 | square roots for use in, table of | 176 |
| Formulas for discharge measurements . . | 64 | use of, in constructing rating curves . | 102 |
| discussion of | 65 | in determining velocity | 77, 78 |
| <i>See also</i> Bazin formula; Chezy formula; | | Lakes, effect of, on stream flow | 155, 156 |
| Francis formula; Kutter for- | | Logarithmic cross-section paper, use of . | 143, |
| mula; Weir formulas. | | 104, 129-137 | |
| Francis formula, discussion of | 87, 88 | Low water, discharge measurements at . | 65, 68 |
| first use of | 2 | Maps, measurement of areas on | 125-129 |
| Freshets, conditions causing | 154, 155 | Mean velocity-curves, construction of . . | 95-97 |
| Friez gage, plate showing | 30 | figures showing | 96, 98, 130 |
| Fteley current meter, description of . . . | 7, 8 | use of, in constructing rating curves | 97, 99, 101 |
| plate showing | 6 | Meters, current. <i>See</i> Current meters. | |
| Gage height, relation of, to discharge . . | 91 | Methods, outline of, used in stream gaging | 3, 4 |
| limits of use | 104-107 | Metric terms, equivalents of | 178 |
| Gage readers, instructions to | 23-36, 80, 81 | Million gallons, table for computing, from | |
| Gages, datum of | 23-36 | acre-feet | 175 |
| description of | 23-36 | table for converting, into acre-feet . . | 175 |
| installation of | 28, 35, 48, 85 | Miner's inch, use of, as unit of discharge . | 121 |
| methods of using | 80, 81 | values of | 177 |
| use of, with stilling box | 30 | Murphy, E. C., coefficients obtained by, for | |
| Gaging stations. <i>See</i> Velocity-area sta- | | computing discharge over | |
| tions; Weir stations. | | broad-crested weirs | 166-171 |
| Gallons per minute, use of, as unit of dis- | | Ohio River, basin of, average rainfall and | |
| charge | 121 | run-off in | 146-149, 153 |
| Geological Survey. <i>See</i> United States | | discharge, mean velocity and area | |
| Geological Survey. | | curves on, figure showing | 100 |
| Geology, discussion of, as affecting stream | | discharge measurements of | 101 |
| flow | 153, 154 | Ponds, effect of, on stream flow | 155, 156 |
| Government publications, method of ob- | | Potomac River, basin of, average rain-fall | |
| taining | 139, 140 | and run-off in | 146-149, 153 |
| Gurly gage, description of | 31-34 | curves of discharge and duration of | |
| plate showing | 30 | flow, figure showing | 123 |
| Haskell current meter, description of . . | 7, 8 | discharge and horsepower table for . . | 124 |
| plate showing | 6 | discharge, mean velocity, and area | |
| High water, discharge measurements at . . | 68, 69 | curves on, figure showing | 96 |
| Hook gage, description of | 25, 26 | discharge measurements on | 108, 109 |
| figure showing | 26 | station rating table for | 108 |
| Horsepower. <i>See</i> Power. | | Powell, J. W., on stream gaging | 2 |
| Housatonic River, basin of, average rain- | | Power, determination of amount avail- | |
| fall and run-off in | 146-149, 153 | able | 122-124 |
| Hydraulics, historical sketch of | 1, 2 | rule for calculating | 178 |
| Hydrograph of Potomac River, figure | | | |
| showing | 123 | | |
| Hydrographs, construction of | 125 | | |
| Ice conditions, daily discharge under, | | | |
| computation of | 113-120 | | |
| discharge measurements under | 69-83 | | |

| | PAGE. | | PAGE. |
|---|------------------|---|-----------------------|
| Precipitation, conditions affecting | 144 | Staff gage, description of | 24, 25 |
| discussion of, as affecting stream flow | 141-150 | State officials, reports of | 139 |
| effect on, of topography | 154 | Station rating tables. <i>See</i> Rating tables. | |
| mean annual, in United States, map showing | 141 | Stay lines, description of | 16, 42 |
| measurement of | 43, 141-143 | Stevens gage, description of | 31-33 |
| seasonal variations in | 143-149 | plate showing | 30 |
| Precipitation station, plate showing | 142 | Stilling box, description of | 30 |
| Price current meter, description of | 9-16 | Stop-watches, use of | 13 |
| plate showing | 6 | Storage, artificial, for controlling stream flow | 156 |
| Radius, hydraulic, determination of (diagram) | 78 | due to snow and ice, measurement of | 152, 153 |
| symbol used for | 51 | effect on, of vegetation | 155 |
| Rain gage, description of | 141-143 | Stout method of interpolating discharge, description of | 109, 110, 112, 113 |
| illustration showing | 142 | figure illustrating | 111 |
| use of | 142, 143, 145 | Stream flow, computation of | 64-67, 89, 90, 91-120 |
| Rainfall, relation of, to run-off | 145-150, 153 | conditions affecting | 141-156 |
| <i>See also</i> Precipitation. | | control of, by artificial means | 156 |
| Rating curves, construction of | 97-104 | duration of, curve of, figure showing | 123 |
| figures showing | 96, 98, 100, 102 | determination of | 122-124 |
| Rating tables, application of | 104-108 | <i>See also</i> Discharge. | |
| construction of | 104 | Stream-gaging data, accuracy of | 122 |
| value of, as compared with diagrams | 90 | sources of | 137-140 |
| Recorders, current-meter, use of | 12, 13 | Surface method, determination of mean velocity by | 60 |
| Recording gages | 30-36 | Susquehanna River, basin of, average rainfall and run-off in | 146-149, 153 |
| Roanoke River, basin of, average rainfall and run-off in | 146-149, 153 | cable station on, plate showing | 112 |
| measurements of | 67 | Swamps, effect of, on stream flow | 155 |
| Rome, water supply of, in first century | 1 | Tables, miscellaneous | 157-178 |
| Roughness, coefficient of, determination of (diagram) | 10 | Temperature, discussion of, as affecting stream flow | 152-155 |
| symbol used for | 51 | effect of, on evaporation | 152, 153 |
| value of | 79, 80 | Three-halves powers, table of | 171-173 |
| Run-off, effect on, of character of soil | 153, 154 | Three-point method, determination of mean velocity by | 61 |
| effect on, of topography | 154, 155 | Topography, discussion of, as affecting stream flow | 154, 155 |
| relation between rainfall and | 145-150, 153 | Two-point method, determination of mean velocity by | 60 |
| tables for computing, from discharge | 173, 174 | United States, mean annual rainfall in, map showing | 144 |
| tables for converting, into discharge | 174, 175 | United States Census, reports of | 138 |
| units of | 121 | United States Geological Survey, reports of weight gage used by, description of | 26-30 |
| Second-foot, definition of | 3 | work of, on hydrography | 2 |
| use of, as unit of discharge | 121 | United States Weather Bureau, rain gage used by | 141, 142 |
| values of | 177 | reports of | 138 |
| Shenandoah River, basin of, average rainfall and run-off in | 146-149, 153 | Vegetation, discussion of, as affecting stream flow | 155-156 |
| Six-tenths depth method, determination of mean velocity by | 59, 60 | Velocity, determination of | 51-61 |
| Slope, determination of (diagram) | 78 | distribution of, in vertical line | 54-59 |
| symbol used for | 51 | instruments for measuring, description of | 5-22 |
| Slope measurements, determination of velocity by | 77, 78 | laws governing | 52-55 |
| Slope stations | 77, 78 | mean, relation of, to surface velocity | 55 |
| Snowfall, measurement of | 143, 145 | | |
| Sounders. <i>See</i> Indicators. | | | |
| Soundings, appliances for, description of | 22 | | |
| errors in | 51 | | |
| method of making | 50, 51 | | |
| Square roots, table of | 176 | | |

| | PAGE. | | PAGE. |
|---|----------------|--|----------|
| Velocity-area stations, classes of | 44 | Weather Bureau. <i>See</i> United States Weather Bureau. | |
| conditions at, permanence in | 44, 45 | Weight gage, description of | 26-30 |
| cost of records at | 46 | figure showing | 27 |
| discharge measurements at | 49-50 | Weights for current meters, description of | 12 |
| establishment | 48, 49 | Weir formulas, discussion of | 84-89 |
| Velocity-area stations, discussion of | 44-81 | Weir stations, discharge measurements at plate showing | 82-90 |
| selection of site | 44-47 | Weirs, broad-crested, description of | 84-86 |
| Velocity-curves, mean. <i>See</i> Mean velocity curves. | | broad-crested, discharge over, table showing | 164, 165 |
| Vertical, determination of | 53, 54 | discharge over, tables for computing | 169, 171 |
| determination of mean velocity by | 55-59 | figure showing | 170 |
| figures showing | 53, 58, 72 | formulas applicable to | 89 |
| form of | 54 | Cippoletti. <i>See</i> Cippoletti weir. | |
| tables showing | 56, 57, 70, 71 | rectangular, formulas applicable to | 87, 88 |
| Velocity of approach, allowance for, in weir formulas | 87 | Weirs, sharp-crested, description of | 82, 84 |
| Vertical velocity-curves. <i>See</i> Velocity-curves, vertical. | | discharge over, tables showing | 160 |
| Wading stations, methods used at | 65, 68 | 161-164, 166-168 | |
| plate showing | 36 | trapezoidal, formulas applicable to | 88 |
| Watches, stop. <i>See</i> Stop-watches. | | use of, in discharge measurements | 68 |
| Water power. <i>See</i> Power. | | Wind, effect of, on precipitation measurements | 142, 143 |



THIS BOOK IS DUE ON THE LAST DATE
STAMPED BELOW

AN INITIAL FINE OF 25 CENTS
WILL BE ASSESSED FOR FAILURE TO RETURN
THIS BOOK ON THE DATE DUE. THE PENALTY
WILL INCREASE TO 50 CENTS ON THE FOURTH
DAY AND TO \$1.00 ON THE SEVENTH DAY
OVERDUE.

DEC 6 1937

NOV 13 1946

DEC 2 1958

9 Oct '58 PY

9 Nov. '58

Dec 2, 1958

DEC 16 1938

REC'D LD

DEC 22 1958

DEC 19 1939

DEC 12 1940

SEP 14 1942

JAN 31 1943

FEB 2 1943

LD 21-95m-7

YC 13490

293064

TC175
H7
1914

UNIVERSITY OF CALIFORNIA LIBRARY

